


# SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1904, by Munn & Co.]


Vol. XC.—No. 13.  
ESTABLISHED 1845.

NEW YORK, MARCH 26, 1904.


8 CENTS A COPY  
\$3.00 A YEAR.



Breech Open, Loading Tray With Charge Swung Round in Position for Loading.



Breech Closed, Loading Tray With Charge Swung Clear of Breech.



**Length Over All, 37.2 feet. Diameter at Breech, 36 inches. Diameter at Muzzle, 18 inches. Weight of Gun, 28 tons. Weight of Projectile, 380 pounds. Muzzle Velocity, 2,900 feet per second. Muzzle Energy, 22,160 foot-tons. Penetration of Wrought Iron at Muzzle, 37 inches. Penetration of Krupp Steel at 3,000 Yards Range, 11 inches. Rounds Per Minute, 4.**

NOTE: The large 9.2-inch gun, whose length and diameter of chase and muzzle are greatly distorted by the photograph, is on a proving-ground mount. The gun at the extreme right is the new 7.5-inch gun that forms the secondary battery in the "Constitution" and "Libertad."

**THE NEW VICKERS-MAXIM 9.2-INCH, 47-CALIBER, WIRE-WOUND GUN, FOR INTERMEDIATE BATTERY OF BRITISH BATTLESHIPS.—[See page 250.]**

## SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN &amp; CO., - - Editors and Proprietors

Published Weekly at  
No. 361 Broadway, New York

## TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico, \$3.00  
One copy, one year, to any foreign country, postage prepaid, £0 16s. 6d. 4.00

## THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845).....\$3.00 a year  
Scientific American Supplement (Established 1876)..... 3.00 "

Scientific American Building Monthly (Established 1885)..... 2.50 "

Scientific American Export Edition (Established 1878)..... 3.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.

MUNN &amp; CO., 361 Broadway, New York.

NEW YORK, SATURDAY, MARCH 26, 1904.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

## SALT-WATER MAINS FOR FIRE PROTECTION.

The provision of water mains and pumping stations as a protection against fire continues to be the subject of earnest and very intelligent discussion in the daily and scientific press; which in itself is proof that the Baltimore and Rochester fires have served the valuable purpose of opening the eyes of other large cities to the ever-present and stupendous danger which confronts them.

In our recent article urging the installation of a salt-water service, we stated that in this matter, while New York had been talking, other cities such as Philadelphia and Cleveland had been acting, and that the latter were now in possession of a thoroughly efficient equipment. The subsequent quotation of this article in the New York Sun has brought a letter to that paper from an engineer, who draws attention to the fact that in a certain sense New York city and Brooklyn were the pioneers in this type of fire service, inasmuch as the fire-boat system was established in these cities about thirty years ago for water-front fire service. He claims that certain western cities, taking the hint, soon adopted the same method, and that being situated on fresh water, and using fresh water in their fire-boat service, they soon conceived the idea of running iron pipes up the various streets from the water front, to which the fire-boats might be connected when needed. The next step in the development was taken by Philadelphia, which substituted a stationary pumping plant for the fire-boats. The same correspondent points out that the objection to the use of salt water is that there would probably be serious and rapid deterioration of the mains and connections, due to the action of the water on the metal, if it were allowed to remain permanently in the mains.

Among the many articles which have appeared on this subject, we think that the most practical is that of our esteemed contemporary, Engineering News, which proposes that an auxiliary pipe system, of large volume and fitted with the necessary standpipes, should be provided for purposes of fire protection alone, and that these standpipes and mains should be filled with salt water only on the rare occasions when the magnitude of a fire may demand the calling in of an auxiliary source of water supply. Our contemporary proposes to lay a system of high-pressure mains, which would be distributed in respect of its capacity according to the particular requirements of the districts of the city that were served. This system would be provided, at points of special danger, with standpipes and street hydrants for hose connections. At some suitable point on the water front, a powerful pumping station would be located, containing high-pressure pumps, delivering directly into the high-pressure mains. Ordinarily these mains would be connected to the regular city fresh-water supply, and the standpipes, mains, etc., would be filled with fresh water only, thus obviating the dangers of corrosion and general deterioration. For all ordinary fires the pumping station would draw from the regular Croton water supply. But should a fire begin to assume serious proportions, the suction of the station pumps would be cut off from the Croton mains, and connected directly with the salt water of the Hudson or the East River, as the case might be, thereby giving the Fire Department an unlimited supply adequate to any possible magnitude of conflagration. When the fire was subdued, the salt-water connection would be cut off, and the mains would be thoroughly flushed out and filled with fresh water, thus removing all danger of corrosion.

In response to the letter of Mayor McClellan to the Department of Water Supply, Gas, and Electricity, to which we made reference in a recent issue, the department's commissioner has submitted a report of a comprehensive plan for protecting two large areas in Manhattan and Brooklyn. The report is published in the current issue of the SUPPLEMENT, and it will be sufficient to state here that the plan agrees broadly with the provisions above outlined. The first install-

ment in Manhattan would cover the area bounded by Twenty-third Street and Chambers Street, Fourth Avenue and the Bowery, and the North River. It would consist of a system of mains served by three separate pumping stations. Over one thousand hydrants would each supply five three-inch hose at a pressure at the nozzles of 200 pounds to the square inch. There would be two hydrants at each street intersection, thus providing forty such streams to each block. The total supply in emergencies that could be concentrated on a single block would be 1,200,000 gallons per hour. Provision would be made for salt water connections should they prove necessary.

Brooklyn would be similarly served in three districts: Coney Island, the dry goods district, and the lower water front district. The total first cost of the installation would be \$3,950,400 if electrical power were used, and \$5,293,200 if gas engines were employed. Although the first cost is large, it is small in comparison to the great value of the interests protected.

## FUTURE EXTENSION OF THE SUBWAY SYSTEM.

With the present subway lines in such a state of completion that the opening of the system for public use is only a matter of a few months' time at the most, the question of the location and inter-relation of new subways becomes of pressing importance, especially in view of the fact that at least four great corporations, to say nothing of the general public, are vitally interested.

The Inter-Borough Rapid Transit Company, in which is included the old Manhattan Elevated; the Metropolitan Railway Company, which owns practically all the street surface railways in Manhattan and the Bronx; and the New York and New Jersey Company, representing New Jersey trolley interests, have all applied to the Rapid Transit Commission for authority to build subways in this city; while the Brooklyn Rapid Transit Company, although not an applicant for authority to build, is anxious to cross the Williamsburg Bridge and run its cars over a belt line to be built between the two bridges that land in Manhattan, although it prefers that the connection should be made by means of an elevated structure.

It must be exceedingly gratifying to the Rapid Transit Commission to compare the present eagerness on the part of the big transportation companies to build subways with the indifference or distrust with which the rapid transit scheme was regarded by these same interests only four years ago, when bids for the construction of the present subway were solicited. At that time it looked for a while as though the years of labor entailed in arousing public interest, and securing the necessary legislative powers, were to be rendered useless by the reluctance of capital to embark upon an enterprise calling for such a large outlay of money, and necessarily involving many engineering problems of a novel and difficult nature. Great credit is due to the contractor, Mr. Macdonald, and his financial backer, Mr. Belmont, for the courage with which they took hold of this scheme, and the successful issue to which they have carried it. The practicability of building subways, the solution which it has afforded of many questions of construction and cost, and the flattering prospects of profitable operation, have removed subway enterprises from the domain of doubtful ventures to that of practical and very promising investments.

By the middle of the present summer, or at the latest by the early fall, when the term of the present subway contract expires, the new system will be in operation, and it will provide New York city with a four-track road from City Hall Park by way of Elm Street, Fourth Avenue, Forty-second Street, Broadway, and the Boulevard to 104th Street, and two divisions from 104th Street, one running north to the Harlem River and the other extending northeastwardly to a tunnel beneath the Harlem River, and through the Bronx to Bronx Park. The extensions now proposed are as follows: The Inter-Borough Company has applied to the Rapid Transit Company for permission to build an extension of the present subway system below Broadway from Broadway and Forty-second Street, where there is a station on the present subway, to Twenty-third Street, and thence south below Fifth Avenue, West Broadway, and Greenwich Street, to connect with the subway loop, which is now under construction at the Battery as part of the present extension of the subway to Brooklyn. They also seek authority for the construction of a subway and elevated system from the intersection of the present subway and Melrose Avenue in the Bronx, to and beneath the Harlem River, and down Lexington Avenue to a junction with the present subway at Forty-second Street and Fourth Avenue, in front of the Grand Central Station. This is obviously the next natural extension to be made of the present system; seeing that it provides an independent north-and-south line to the west of the present subway below Forty-second Street, and an independent line in the eastern section of the city north of Forty-second Street.

The Metropolitan Street Railway Company, which is one of those interests that was earnestly urged to undertake the construction of the present subway four

years ago, are now so thoroughly convinced of the value of the system, that they have filed with the Rapid Transit Board an application for an even more extensive series of lines than that asked for by the Inter-Urban Company. They propose to build a subway from Third Avenue and 138th Street in the Bronx, to extend down Lexington Avenue to Fifteenth Street, then under Union Square to Broadway, down Broadway to Chambers Street, thence eastwardly below Chambers Street to William Street, down William Street to Hanover Square, and then to the Battery, by way of Coenties Slip and South Street; around the Battery outside of the present subway to Greenwich Street; up Greenwich Street, West Broadway, and Hudson Street to Eighth Avenue; and up Eighth Avenue, through the new Pennsylvania tunnel, and eastwardly through Thirty-fourth Street to a junction with its proposed line down Lexington Avenue. There would also be a crosstown connection between the east and west side branches on Thirty-fourth and Chambers Streets. As it is carefully stated in the application that the proposed subway would pass under the existing subway, evidently no connection is contemplated between the two, a defect which, we think, must militate very strongly against the application of the Metropolitan Company in its consideration by the Rapid Transit Commission. On the other hand, the company pledges itself to a system of transfers between its subway lines and the sixteen crosstown surface lines which it controls.

The evidently careful avoidance of the present subway lines, which is manifested in this application, will suggest at once to the public mind that the proposition, if accepted, will be directly opposed to that very unification of the transportation system of this city which is so eminently desirable, as proved by the good results shown in the excellent management by the Metropolitan Company of its own amalgamated street surface lines.

In addition to these very ambitious proposals, the New York and New Jersey Company, which has just completed its first tunnel beneath the river, has applied to the Rapid Transit Commission for authority to extend its tunnel by way of Tenth Street and Sixth Avenue to Herald Square, an extension which would put the large residential districts of New Jersey in direct touch with what is rapidly becoming the principal shopping district of New York city.

The last, and not by any means the least important, subway extension is that proposed by the Rapid Transit Commission itself, which has for its object the provision of a belt line between the termini of the Brooklyn and Williamsburg bridges. This subway would extend from the Brooklyn Bridge by way of Centre Street, Grand Street, and Delancey Street to the terminus of the Williamsburg Bridge. It is sincerely to be hoped that the connection between the two bridges will be made by subway, and not by elevated structure. The elevated structure is preferred by the Brooklyn Rapid Transit Company, for the reason that the Brooklyn Rapid Transit Company's cars are not suited, because of their lack of fireproof provision, for subway travel. If a subway is built, it would be necessary for the company to provide an entirely new equipment of cars, and this, in their present condition, they are utterly incapable of doing. To build an elevated structure between these points would add a further disfigurement to the city and would be a step backward from modern, up-to-date methods. Perhaps the best way out of the dilemma would be to build a subway between the bridges, and operate it as a separate system, providing loops at the Manhattan end of the Williamsburg Bridge for the return of the Brooklyn cars. This would serve until the advent of the day, which is most certainly coming, when the whole of the transportation system in Greater New York, elevated, surface, and subway, in Manhattan, the Bronx, and Queens, will be unified in one system, with a single five-cent fare between all points.

## A FLORAL MAP OF THE UNITED STATES AT THE ST. LOUIS EXPOSITION.

The exhibit of the Bureau of Plant Industry of the United States at the St. Louis Exposition will be one of the most interesting exhibits at the Fair. Work has already been commenced upon the making of the monster map of the United States, to form a greater portion of the exhibit. Mr. D. A. Brodie, an expert in the employ of the Plant Department, is superintending the work of laying out the map, though the United States government board appointed by Congress to represent the Federal government at the Exposition will have charge of the appropriation of \$5,000. The map will cover six acres, and each State is to be outlined by a cinder path. The entire area has already been underlaid with wooden drains, plowed deep and planted in cow-peas as fertilizers. In each State reservation will be shown plants grown in that State. Where the climatic conditions of St. Louis forbid the growing of plants out of doors, they will be grown under glass. Cotton, tobacco, and sugar cane are to be shown in the Southern States, orange and pineapple in Florida, and corn and wheat in the Middle States. No attempt



will be made to show the principal waterways of the United States. The waste places on the margin of the map, resulting from irregular coast lines, will be used for plant exhibits of various kinds, showing plants grown around the world. Men in the employ of the Bureau of Plant Industry are now scouring the world in search of grasses and plants to be shown to visitors at the Exposition. One patch of ground is to be devoted to cereals, another to poisonous plants, another to fiber, and still another to seed production, grasses, plant breeding, etc. A school of gardening will also be a portion of this exhibit. School children living in St. Louis will attend to a model school garden to be furnished by the government. Prizes are to be awarded to the most apt pupil at this school. School gardens are now becoming more and more popular. The map is located on a sloping hill, and adjoins the agricultural and horticultural exhibits and buildings. It may be seen from any portion of the main exposition grounds, and will be one of the instructive and beauty spots of the Fair.

#### BORINGS ON A CORAL REEF.

One of the most complete and important contributions to the study of coral reefs and their mode of formation that has so far appeared, even if we bear in mind Prof. Alexander Agassiz's recent work "The Coral Reefs of the Tropical Pacific" (Memoirs, Museum of Comparative Zoology, Harvard College, 1903), may be seen in a monograph just issued by the Royal Society of London, entitled "The Atoll of Funafuti: Borings Into a Coral Reef and the Results."

The project for the investigation of a coral reef with the object of elucidating its structure, originated at the Nottingham meeting of the British Association, held in 1893. At that gathering Prof. W. J. Sollas was successful in promoting a committee, charged to consider whether an exploring expedition was feasible; in the end it was decided to go forward with such an undertaking, and eventually the Royal Society took over the necessary arrangements.

After many meetings and consultations, it was decided to select Funafuti, an island in the Pacific Ocean, as the site for inquiry, the primary aim being the bringing up of a core of rock in order that the composition of the reef might be determined from zoological and chemical standpoints. Actual operations at this ring-shaped spot of land were begun as long ago as 1896, and they continued until 1898.

The well-known hypothesis of Darwin respecting the development of coral reefs in their several forms, although at one time regarded as a truth in geology, is no longer tenable in its entirety, a result largely due to the later observations of Agassiz and Murray. Darwin, himself, however, earnestly desired a fuller examination, *in situ*, than had been at all practicable in his own day, and in fact went so far as to express his conviction (in a letter to Agassiz in 1881) that nothing of a really satisfactory nature could be brought forward as contributory evidence until a boring was made in one or other of the Pacific and Indian atolls, and a core obtained down to a depth of at least 500 or 600 feet. That hoped-for consummation has, however, been over-achieved, since the boring at Funafuti was carried down to a limit of 1,114 feet.

Three expeditions were made before this could be accomplished. The first attempt was made in 1896 with Prof. Sollas as leader, but it ended in failure owing to a breakdown of the diamond-drill borer, consequent upon an inrush of reef "sand." A second, which set out in 1897, having Prof. Edgeworth David, of Sydney, as conductor, and aided by the loyal co-operation of various authorities in Australia, so profited by past experience that a depth of 698 feet was attained; while a third, under the guidance of Mr. A. E. Finckh, also of Sydney, carried the main bore down to 1,114 feet.

The general story of the expeditions is given in the monograph by the leaders who took part in them, and the narratives, whether detailing the various steps in making borings, or treating of the difficulties and even dangers that were encountered, provide a fascinating chapter of plucky and long-sustained effort. Besides the primary purpose of the survey, a good deal of correlated scientific work was done, in which Capt. Field, R.N., of H.M.S. "Penguin," who conveyed the first party, took a prominent part. He made a complete topographical survey of the atoll, and charted an extensive series of soundings in the waters of the lagoon and the outer sea, as well as carrying out a magnetic survey of Funafuti, not alone in the interests of terrestrial magnetism, but as specially bearing upon the geological investigation that was in hand. Then again, the opportunity was embraced of making collections representative of the general fauna, flora, and anthropology of Funafuti and adjacent islands in the Ellice group.

The cores from the early borings, and that from the later and main bore, were all of them shipped to Prof. J. W. Judd, F.R.S., of the Royal College of Science, London, for detailed examination by him and by other experts, thus fulfilling Darwin's old wish, and it may

be readily imagined that this transport virtually marked the commencement of the inquiry. Although many papers and memoirs in various departments of science have laid Funafuti under contribution during the years that have passed since the expeditions, it was only to be expected that a long interval would elapse before the materials that were obtained could form the subject of a satisfactory official report. The magnitude of the task is abundantly indicated by the present monograph.

Dr. G. J. Hinde supplies an elaborated descriptive account of the organisms which have contributed to the building up of the atoll, compiled from an examination of hundreds of microscopic core slittings and other desiderata. The evidence derived from this piece of work goes to show that, whether in the form of solid rock-cores or as incoherent granular particles, the material appears to be entirely of organic character, traceable to the calcareous skeletons of marine invertebrate animals and calcareous algæ; of the latter, Halimeda and Lithothamnion occur in abundance. And Prof. Judd's comment is that "from top to bottom the same organisms occur, sometimes plants, sometimes foraminifera, and sometimes corals predominating; but in the whole depth bored the same genera and species of these various groups of organisms take their part in the building up of the mass," a striking and significant summary. The only portion of a vertebrate noticed in the borings was a fragment of bone or spine, met with in the center of a core of compact dolomite, from a depth of 1,060 feet, which appears to belong to a fish. Mr. Finckh deals with the biology of the living reef-forming organisms at the atoll, and the mode of formation of rock brought about by their presence. He assigns their relative importance thus: (1) Lithothamnion, (2) Halimeda, (3) the Foraminifera, (4) the Corals. This, and another important section on the geology of Funafuti, by Prof. Edgeworth David and Mr. G. Sweet, are of especial value.

The conclusions reached in this opportune monograph are presented in no controversial fashion; the idea has been to put forward facts and leave the interpretation to others. But unfolding as they do the conditions surrounding the present-day life of an atoll and the structure of the deeper parts of its body, they will be read with profound interest by all who study the problems indicated by the formation of coral reefs.

#### THE UNITED STATES IN 1903.

The Statistical Abstract of the United States for the year 1903, issued by the Department of Commerce and Labor through its Bureau of Statistics, has just made its appearance. It is a solid mass of 650 pages of figures, with scarcely a line of "reading matter" other than the tables of figures and their necessary headlines. Yet a study of its tabular statements develops many interesting facts about the United States, its progress, development, and relation to the other countries of the world. It is interesting, for example, to observe, as shown on page 564, that the exports of domestic products from the United States now exceed those of any other country of the world. They amounted to \$1,392,231,000, against \$1,379,283,000 from the United Kingdom, \$1,113,313,000 from Germany, \$820,671,000 from France, and \$732,975,000 from Netherlands. In imports the United States stands third, the world's largest importer being the United Kingdom, \$2,571,416,000; Germany second, \$1,340,178,000; the United States third, \$1,025,719,000; Netherlands fourth, \$867,308,000, and France fifth, \$848,046,000. The above figures of imports and exports are, in the case of the United States, for the year ending June 30, 1903; the others, the calendar year 1902.

Regarding the details of the foreign commerce of the United States, the Abstract shows that 72 per cent of the exports were sent to Europe, 15 per cent to North America, and the remainder distributed in much smaller percentages to South America, Asia, Oceania, and Africa. The total value of the exports from the United States to Europe in 1903 was \$1,029,256,000; to North America, \$215,483,000; to South America, \$41,138,000; to Asia, \$58,359,000; to Oceania, \$37,468,000; and to Africa, \$38,437,000. Considering the exports by countries, the largest total is to the United Kingdom, \$524,263,000; the next largest to Germany, \$193,842,000; and to Canada, \$123,267,000.

Comparing conditions in 1903 with those of 1873, the exports have grown from \$522,000,000 to \$1,420,000,000, including domestic products and foreign merchandise re-exported. Agricultural products of course still form the largest group of exports, amounting to \$873,000,000 in 1903, or 63 per cent of the total, while manufactures amount to \$407,000,000, or 29 per cent of the total. Manufactures are, however, gaining rapidly upon agricultural products in the share which they form of the total exports. In 1880 agricultural products formed 83 per cent and manufactures but 12½ per cent of the total exports of domestic products, while in 1903, as already indicated, agricultural products formed 63 per cent and manufactures over 29 per cent of the total.

The value of domestic manufactures exported had

never reached so much as \$100,000,000 prior to 1876, and in 1896 for the first time crossed the \$200,000,000 line. Since 1896, however, the growth has been rapid, the total exceeding \$300,000,000 in 1899, passing the \$400,000,000 line in 1900, and remaining above \$400,000,000 constantly since that date, with a prospect that the total exports of manufactures for the fiscal year 1904 will exceed in value those of any previous year.

#### SCIENCE NOTES.

Dr. Hildebrandsson has presented his report to the International Meteorological Committee respecting the position, number, and dimensions of the permanent air currents of the globe. The summary of this report as the result of direct observations is as follows: (1) Above the heat equator and the equatorial calms there is throughout the year a current from the east, which appears to have very great velocities at great altitudes. (2) Above the trade winds there is an anti-trade current from the southwest in the northern, and from the northwest in the southern, hemisphere, respectively. (3) This anti-trade wind does not extend farther than the polar limit of the ordinary trade winds, but is deflected more and more to the right in the northern, and more and more to the left in the southern hemisphere, until it finally becomes a current from the west above the crest of the tropical high-pressure belts, where it descends to supply the trades. (4) There is an anti-trade upper monsoon above the districts at the equatorial margin of the trades, the anti-trade in winter and the equatorial current from the east in summer. (5) From the tropical high-pressure belts, the air pressure decreases on the whole as it approaches the poles; while the air of the temperate zone is drawn into a vast polar whirl turning from west to east. The air of the higher strata flows away from the whirl, and the air of the lower strata flows toward the center of the whirl. Furthermore Dr. Hildebrandsson asserts that the theory that there is a vertical circulation of air from the equator to the higher regions, finally falling at the poles, is altogether a fallacy. Dr. Hildebrandsson's report is a valuable and important contribution to the science of the new meteorology, and destroys many existing notions respecting the permanent air currents of the world.

Before the Institution of Civil Engineers, on December 22, Dr. T. E. Stanton read a paper on the resistance of plane surfaces in a uniform current of air. The paper deals with the results of experiments made in the engineering department of the National Physical Laboratory on the distribution and intensity of the pressure on thin plates and combinations of plates placed in a uniform current of air, and is intended as the first part of a research on the nature and distribution of the pressure of the wind on structures. By a uniform current of air is meant a current in what is known as "eddy motion" as distinguished from stream-line motion, the mean velocity at any point in the direction of flow being uniform across the current. This condition of motion is considered to be the nearest approximation to that of winds of fairly high intensity. The main object of the present research was to determine, if possible, a general relation between the velocity of the current, the dimensions of the plates, and the resultant pressure, as it was felt that experiments in the open air could not be undertaken with any prospect of success until some general relation of the kind has been established. The results of the experiments show that, under the given experimental conditions, a definite relation of the kind existed, and may be stated thus—for similar and similarly situated plates or combinations of plates in a uniform current of air, the intensity of pressure is the same for the same velocity of current and general atmospheric conditions. On the assumption that the motion of the wind approximates to that of a uniform current as defined above, the above relation shows that the distribution and intensity of the pressure of the wind on structures may be studied experimentally by means of models of the structures set up in a current of air produced by means of a fan, as in the present case. In illustration of this, the results of experiments made on models of roofs and lattice girders of simple form are given in the paper. Tabulated results are also given for the cases of parallel plates at varying distances apart, plates inclined at varying angles to the direction of the current, and the rectangular plates of varying ratio of length to width.

The Belgian and French governments have come to an agreement relating to the establishment of telegraph communication between the Congo Free States and the French Congo. Under the agreement a submarine cable is to be laid between Brazzaville and Kinshassa, the cost of which is to be borne equally by the two countries concerned. It is proposed to use Morse registering apparatus in the stations at either end of the cable. The tariff will probably be 2¼d. a word, with a minimum rate of 10d. per message.

### CONCRETE PILING.

The extensive improvements made at the Washington barracks have attracted not a little attention to a system of concrete piling which was there employed with marked success, and which promises to displace, for certain kinds of work, the wooden piles which have been used so long. The work at the Washington barracks presented obstacles which could not be overcome by the use of the ordinary pile—obstacles due to the constantly changing condition of the ground, which was alternately wet and dry as a result of heavy and frequent rains.

Through the courtesy of Mr. Frank S. Shuman, we are enabled to present the following description and the accompanying illustrations of this method of utilizing concrete piles.

Four different types of piles are employed. The one illustrated in Fig. 1 A, and known as "the preparatory removable pile," is to be used in earth reasonably firm in its texture and free from water. A preparatory tube, consisting of a length of extra heavy iron pipe, fitted with a driving head of oak, and a conical steel point of a somewhat larger diameter than the pipe, is driven into the ground to the required depth, and thereupon withdrawn. The hole formed is filled with well-rammed concrete. Obviously, any desired length of pile can be obtained by driving the outer tube deep enough into the ground; and obviously that outer tube can be removed with but a fraction of the force required in pulling out or planting the ordinary pile. After the rammed concrete has once set, the pile becomes literally a pillar of stone. Fig. 1 B shows the general appearance of the pile after the removal of the outer tube. The frictional hold of the pile is much augmented, because the larger pieces of the aggregate are forced into the sides of the hole, thereby forming innumerable lateral anchors. We are informed that a pile of this type, 14 inches in diameter and 13 feet 2 inches in length, successfully sustained a direct pressure of more than 21 tons of pig iron for a period of ten days without any signs of settling.

It sometimes happens that the fixed steel point cannot be used to advantage. Particularly is this the case where the earth is soft or marshy, or where quicksand or water is encountered. For this purpose, a detachable point of concrete, as shown in Fig. 2 A, is substituted for the fixed steel point, and driven to the required depth. As the pipe is lifted out, concrete is rammed home through the pipe. A head of concrete

is maintained inside the pipe while it is being gradually withdrawn. In this manner, all water is displaced, and the closing in of the sides of the aperture is avoided.

In driving piles under water, the system illustrated in Fig. 3 A is employed. The pipe with its concrete point is surrounded by a sheet-iron coffer-dam, which

If, on the other hand, the pile is required to rise above the water, as for example in the construction of a wharf, the sheet-iron coffer-dam is not removed, but is left in position and filled up with concrete (Fig. 3 C). To lend additional stability to a pile of this construction, a cylinder of 3-inch mesh expanded metal may be embedded in the concrete, and likewise a piece of structural iron, to which the superstructure can be fastened.

In soil that is alternately wet and dry, these piles are obviously able to provide a permanent foundation, which could not be secured by wooden piles. The system is economical and easy of application.

### The First Modern Ship Canal.

In these days of ship canals we hear little or nothing about the earliest enterprise of the kind during modern times, namely, the Berkeley and Gloucester Ship Canal. Although Gloucester is situated on the Severn, access to the port is really afforded by the canal. Owing to the dangerous condition of the river, an Act was obtained in 1793 for the construction of a ship canal commencing at Berkeley, some sixteen miles lower down the Severn, and the works were completed in the year 1827. This waterway follows the Vale of Berkeley, originally commencing with a tidal-basin and lock at Sharpness Point and ending at the docks in Gloucester, where there is another lock communicating with the Severn. The original cost was about


£500,000, but within the last forty years considerable outlay has been incurred in opening a new entrance half a mile lower down the river, with additional dock accommodation. These works were finally completed in 1874.

Although vessels of more than 600 tons cannot pass up the canal to the port, ships of 2,500 tons can enter the outer basin, where cargo is transferred to barges. The dimensions of this ship canal may be small compared with more recent developments, but its continuously successful operation has certainly had some useful effect in the encouragement of more ambitious schemes of the same kind.—Builder.


The topography of the Pennsylvania anthracite coal regions is shown at the World's Fair by a large relief map. A model of a mining plant, showing both the interior and exterior works, forms a part of the exhibit. The actual position of coal seams under the surface is shown by means of cross sections. An actual breaker is shown in operation.



Concrete Points for Long, 17-inch Diameter Piles. Engineers' School, Washington Barracks, D. C.



Concrete Pile, 13 Feet 2 Inches Long by 14 Inches Diameter. Dug Out Perfectly Intact After Test.



Preparatory Pile Removed, Leaving Hole Ready for Concrete.




Fig. 1 A Fig. 1 B Fig. 2 A Fig. 2 B Fig. 3 A Fig. 3 B Fig. 3 C


Various Systems of Concrete Piling.

### CONCRETE PILING.



### A SINGLE-CYLINDER, REVERSIBLE, FOUR-CYCLE GASOLINE ENGINE.

The engine shown in the accompanying cut is the invention of Mr. A. F. Law, of Bridgeport, Conn., and is manufactured by the Royal Equipment Company, of



### A NOVEL, FOUR-CYCLE, REVERSIBLE, GASOLINE MOTOR.


that city. It is of the usual four-cycle type, having a 4-inch bore by 5-inch stroke, and is adapted especially for marine purposes, where its use makes a reversible-blade propeller or other reversing gear unnecessary, except in cases where the boat must always be instantly reversible. The marine motor is rated at 3 horse-power at 600 R. P. M., and it can be made to develop 5 horse-power by running it at a higher speed. Its weight complete is 235 pounds. The plunger water pump seen beside the cylinder, in front, is driven by an eccentric beside the flywheel. Variable jump-spark ignition is used, the spark being advanced or retarded by moving vertically over its notched segment the lower of the two levers seen beside the base. The upper lever, which moves in a horizontal direction, shifts the small plunger that operates the exhaust valve, from the regular cam on the secondary, or half-speed, shaft to another cam beside it, which is set so as to open and close the valve at the proper time when the engine is running backward. To reverse, it is only necessary to cut off the ignition current when the motor is running with the spark advanced, throw over the reversing lever as soon as the motor slows down, and cut in the ignition current again. The spark, being advanced for running forward, will of course be retarded for running backward, and as soon as the motor starts to turn in the latter direction, the spark must be advanced in order to secure full power.

The motor can generally be reversed without stopping it, but, in the event that it does stop while being reversed, it can of course be at once started again by hand in the reverse direction. In other words, this four-cycle engine comprises all the advantages of engines of this type, with the reversible feature of the two-cycle engine added. The engine is well constructed throughout, has a hand-hole in the base for adjusting bearings, and is built up to a four-cylinder size, which, for automobile use, is rated at 20 horse-power.


As stated in a paper recently read before the Russian Physico-Chemical Society, Mr. N. Awerkieff observed that in connection with the action of hydrochloric acid on metallic gold in the presence of formaldehyde, trioximethyl, methyl, ethyl, and amyl alcohol, as well as in that of phenol, chloroform, and several other organic bodies, a dissolution of the gold would take place. The solutions obtained in this way, on being vaporized, dried, and heated, would leave a residuum of metallic gold.

### A NEW GASOLINE MOTOR FOR AIRSHIPS.


The six-cylinder motor shown herewith was designed and built by Mr. Charles E. Duryea, of the Duryea Power Company, Reading, Pa., for use on an airship. The cylinders have a 4½-inch bore and the pistons a 5½-inch stroke, and when turning at 900 R. P. M. the motor developed 40½ horse-power. Its weight stripped, as shown, but with complete equipment of two carbureters, battery, spark coil, water, and gasoline tanks, with a gallon of the respective liquids in each, was 232 pounds, or less than 5¾ pounds per horse-power. The three-throw crank shaft of 1¾-inch diameter is hand forged and has a ¾-inch hole bored in it to carry oil to the crank pins. These are 1½-inch in diameter and are provided with a ¼-inch central hole for oiling. The wrist pins of the pistons are hollow and are plugged so as to prevent the oil going out at the bottom. Instead of setscrews to hold them in place, oil cups screw into the lug on the inside of the piston wall. These oil cups have an opening on the upper side for filling, and they can be filled when the piston is at the end of its stroke. The reciprocating motion causes the oil to feed properly. The cylinders of the motor are of cast iron, machined inside and outside. They are fitted with copper water jackets. At the base of each cylinder there is a slightly conical space on which the copper water jacket fits with a steel ring around it, which, when it is driven up on the cone, clamps the jacket to it, making a tight joint. The motor is a particularly light and compact one, and should fulfill well the purpose for which it was designed.




The Transmitter and the Receiver.



Message Ready for Transmission at a Speed of 1,000 Words a Minute



Recording the Message Electrolytically on a Chemically-Prepared Tape.




Machine for Perforating the Transmitting Tape.

### A NEW SYSTEM OF RAPID TELEGRAPHY.

### A NEW SYSTEM OF RAPID TELEGRAPHY.

The difficulties which have hitherto blocked the path to the invention of a successful high-speed telegraph system are of an electrical, rather than a mechanical nature. Many transmitters and receivers have been devised, which are mechanically capable of operating at a high rate of speed; but which have utterly failed when used on any but short telegraph lines, because, owing to static capacity of the line,



A 40½-H. P., WATER-COOLED, GASOLINE MOTOR FOR AN AIRSHIP.


they are too rapid for the electric impulses. A telegraph line presents features and effects similar to those of a Leyden jar. Though these effects are too small to be noticeable in a short line, in a distance of several hundred miles they become so great as to seriously interfere with high-speed transmission of telegraphic signals. Dots and dashes, instead of being sharply defined, are prolonged until they are run together by the sluggishly flowing current, rendering the message unintelligible.

A system recently invented by Mr. Patrick B. Delany, of South Orange, N. J., is not in the least hindered by the static capacity of the line; but on the contrary utilizes the "static discharge" and is inoperative without it, so that, when used on short lines whose capacity is small, it is necessary to bring these lines up to the requisite capacity by the use of condensers.

The system is designed to transmit and receive messages at the rate of one thousand words a minute over distances of one thousand miles, though a speed of eight thousand words a minute has been attained on a short experimental line. In the accompanying illustrations we show the three machines which are used in the operation of this system, namely, the perforator, the transmitter, and the recorder. Messages are sent by means of a perforated tape, which is prepared in the perforating machine. The tape is drawn at any desired speed through the perforating machine under a pair of steel punches. Each of these punches is operated by a magnet. The magnets are controlled by a Morse transmitting key, shown at the right in our illustration. A downward stroke of the key causes one of the punches to operate, and on release of the key the other punch operates. Thus each operation of a key, whether for a dot or a dash, serves to make two perforations, one near the upper edge, and the other near the lower edge of the tape. As shown in our illustration of the perforated tape, the primary and secondary perforations have an angular relation to each other, which is due to the fact that the tape is constantly running, and which varies with the interval of time between the downward stroke and release of the key. When a message has been perforated in the tape, the latter is passed through the transmitting machine. Here the primary perforations co-operate with suitable mechanism to send positive electric impulses through the line, while the secondary perforations permit the passage of negative electric impulses.

The accompanying diagram clearly shows the method of sending and receiving the message. The perforated tape, A, at the transmitting end passes between two primary contact fingers, B and B', and two secondary contact fingers, C and C'. B' is connected with the positive pole of a battery whose

negative pole is earthed, and  $C'$  is connected with the negative pole of a battery whose positive pole is earthed. When the fingers,  $B$  and  $B'$ , make a contact through a perforation in the tape, they send a positive impulse over the line. This impulse is followed at the proper interval by a negative impulse by contact of fingers  $C$  and  $C'$  through the secondary perforation. The signal is electrolytically recorded at the receiving end on a chemically-prepared tape,  $F$ , by means of an iron electrode,  $E$ , connected to the line and a platinum electrode,  $D$ , connected to earth. The current in passing through the moistened chemical tape from the iron to the platinum electrode forms a blue mark on the tape, at the contact point of the iron finger. When the current is reversed, no such mark is formed. A momentary positive impulse sent by contact fingers  $B$  and  $B'$  causes such a mark to be



The Same Word as Perforated on the Transmitting Tape and Electrolytically Produced on the Recording Tape.

produced on the moving tape at  $E$ , and this mark is protracted by the slow outflowing current, which is retarded by the inductive capacity of the line, until a negative impulse produced on contact of fingers  $C$  and  $C'$  abruptly stops this after-flow by reversing the current. Thus it will be seen that the impulses, whether for a dot or a dash, are all of equal duration, and it is the interval between the positive and negative impulses that determines the length of the mark on the paper.

The practical advantages of this system will be readily comprehended. A number of perforating machines can be used in connection with a single transmitter, so that a large number of messages can be prepared simultaneously, and then passed through the transmitter at speeds of 1,000 or more words a minute. Furthermore, Mr. Delany has invented a perforating machine, which is operated from a keyboard similar to that of a typewriter. This can be operated by any typewritist at twice the speed at which the Morse keys are ordinarily operated, and if desired can be used in any business office to perforate messages on the tape. The tape can then be sent to the telegraph station, and run at a high speed through the transmitting machine. At the receiving end the record may be transcribed before being sent out, or the original may be sent to its destination, where any typewritist who has had a few days' instruction can reproduce the message in typewritten form, and in this way absolute secrecy in transmitting the message can be maintained.

#### Commercial Korea.

"Commercial Korea in 1904" is the title of a monograph just issued by the Department of Commerce and Labor through its Bureau of Statistics. It discusses commercial and other conditions in Korea, showing area, population, transportation facilities, railways, telegraphs, postal service, and foreign commerce, including imports and the countries from which they are drawn, and exports and the countries to which they are sent. The population of Korea the monograph in question puts at about 15 millions in round numbers, the area at about equal to that of the State of Kansas, and the foreign commerce at about \$12,000,000, of which imports form about \$7,500,000. A part of the Chinese Empire prior to the Christian era, Korea remained under the control of that country until about the end of the sixteenth century, when the Japanese sent a large invading army to Korea for the purpose of driving out the Chinese and taking possession. The Japanese rule, however, was comparatively brief, and in 1627 the people of Manchuria placed the country under vassalage, and until 1894 Korea recognized the control of China by sending tribute-bearing missions annually to Peking.

In 1894 an insurrection led the country to ask aid from China, and Chinese troops were sent. This action, being looked upon by the Japanese as a step toward the complete control of Korea by China, precipitated a war between China and Japan in 1894, which resulted favorably to Japan and was followed by a renunciation of Chinese sovereignty by the Korean king, the substitution of Japanese for Chinese influence, and the introduction of many important reforms under Japanese advisers. These reforms included adjustment of taxation, abolition of slavery, establishment of educational institutions, introduction of a postal system, membership in the International Postal Union, and a reform of the judiciary.

Commercially the development of Korea begins with 1876, when two ports, Gensan and Fusan, were, upon the insistence of Japan, opened to trade with that country only. In 1882 Admiral Shufeldt, of the United States navy, visited Korea and secured a treaty of friendship between the United States and Korea by which American vessels were given access to its treaty

ports and the safety of American vessels and citizens assured. This was followed by treaties with Germany and Great Britain in 1883, Russia and Italy in 1884, France in 1886, Austria in 1892, and China in 1897. The formation of the treaty between Korea and the United States in 1882 was immediately followed by a visit from a Korean embassy to Washington, sent to exchange ratifications of the treaty. From this time forward Korea was opened to foreign trade and Western civilization, and the Korean government established its legations in the United States and other great commercial nations. With the opening of the treaty ports and the establishment of commerce an official record of Korean imports and exports began. This shows imports in 1884 amounting to about \$800,000 and exports amounting to \$475,000. By 1890 imports had grown to \$3,850,000 and exports to \$2,975,000. In 1894 imports and exports fell considerably below those of 1890, but in 1897 again increased, being for that year of imports about \$5,000,000 and exports about \$500,000. In 1902 the imports at the treaty ports amounted to about \$7,000,000 and the exports of merchandise to about \$4,200,000. In addition to this, exports of gold amounted to over \$2,000,000, while the imports and exports at other than treaty ports are estimated as being sufficient to bring the total commerce of 1902 up to fully \$15,000,000, exclusive of gold exports, which, as above indicated, amounted to about \$2,000,000.

The most important articles in the export trade are rice, which shows an annual exportation of more than \$1,000,000; beans, \$500,000; ginseng, nearly \$500,000; and hides, about \$100,000 in value in the latest available year. Of the importations, cotton goods form the largest item, from \$3,000,000 to \$3,500,000 per annum; silk piece goods imported from Japan and China amount to \$600,000 per annum; kerosene oil, about \$300,000; railway materials, about \$250,000; mining supplies, about \$200,000; and bags and ropes for packing, \$150,000. Of the cotton goods imported in 1902, British shirtings formed the largest single item, amounting to \$800,000; British and American sheetings, \$260,000; Japanese sheetings, \$350,000; Japanese piece goods and yarn for use in manufacturing cotton cloths, \$800,000. Korea, like China, is now drawing considerable quantities of cotton yarn from Japan, and considerable supplies of cotton manufactures. Great progress is being made by Japan in the manufacture of cotton, and in addition to supplying cotton cloths to China and Korea in large quantities it is now supplying the cotton yarns which are used in household manufacture as well as in certain of the cotton mills which exist, and are proving quite successful.

The foreign commerce is carried on through the treaty ports of Chemulpo, Fusan, Wonsan, Chinampo, Mokpo, Kunsan, Masampo, and Song Chin. Chemulpo, which is located on the western coast of Korea, about midway from its southernmost point to the northern boundary, has by far the largest commerce. Its imports in 1902 were reported at \$1,250,000 out of a total of \$1,920,000. The exports of Chemulpo, however, are very much less than those of other ports, being \$45,000 in 1902 out of a total of \$1,830,000. Its pre-eminence over the other treaty ports as a point of importation is due largely to the fact that it is of itself a considerable city with a comparatively large foreign population and is in direct railway communication with the capital of Korea, Seoul, which is only 35 miles distant.

The principal imports in 1902, stated in United States currency, are as follows: Shirtings, gray and white, \$860,000; silk piece goods, \$480,000; cotton yarn, \$490,000; American kerosene, \$385,000; Japanese sheetings, \$360,000; Japanese piece goods, cotton, \$325,000; British and American sheetings, \$285,000; grass cloth, \$285,000; railway plant and material, \$230,000; bags and ropes for packing, \$150,000; mining supplies, \$230,000; clothing and haberdashery, \$100,000; provisions, \$95,000; matches, \$90,000; saké samshu, \$75,000; sugar, \$74,000; machinery, \$70,000; cotton wadding, \$60,000.

#### The Current Supplement.

The current SUPPLEMENT, No. 1473, opens with an admirably illustrated article on the canalization of the Elbe and the Moldau. Mr. O. Chanute presents an excellent discussion of aerial navigation from the historical standpoint. Emile Guarini describes the Dick system of lighting trains by electricity. "Coloring of Metals" is the title of a paper by Paul Malherbe on a subject which is of considerable technological importance. A simple explanation of the N-rays is given for the benefit of those readers who have not been able to follow the more technical articles which have thus far appeared. Mr. Foster H. Jennings begins a very thorough treatise on Korean head-dress, which is well illustrated by pen-and-ink drawings.

Workmen are installing the wonderful floral clock at the World's Fair. The steel framework, which was made in Milwaukee, Wis., is being placed. The flowers that will conceal the mechanism are in pots in the greenhouses, and will be installed about April 15. The dial of the clock is 112 feet across.

#### THE NEW VICKERS-MAXIM 9.2-INCH WIRE-WOUND GUN.

The powerful weapon which we illustrate on the front page of this issue is a good representative of the latest improvements which have been introduced into heavy ordnance, with a view to securing at once greater range, increased penetration, and a higher rapidity of fire, without adding materially to the weight of the piece. The theory of design and methods of construction by which these results have been secured are not by any means peculiar to this piece, inasmuch as they have been followed by gun makers for many years; but the significance of this 9.2-inch gun is that in it we see what is, perhaps, the most successful combination of these qualities that has yet been attained. Although this gun weighs only 28 tons, and has a service rapidity of fire of five rounds in a minute and a half, it has a power of penetration at 3,000 yards (the minimum fighting range of to-day) approximately equal to that of the 13½-inch English gun, of more than twice the weight, of a dozen years ago.

The immediate cause of this increase in efficiency is the greater velocities that are secured with modern guns; and the increase in velocity is due to the enlargement of the powder chamber, the use of slow-burning powder, and the lengthening of the bore, so as to enable the products of combustion as they are given off by the burning powder to exert their accelerating effect upon the projectile for a longer period and with a higher average pressure. To such a successful point have these principles been carried, that the latest types of gun, such as the one herewith shown, have fully fifty per cent greater velocity than the guns of ten or fifteen years ago. The gun weighs 28 tons, has a total length of 37.2 feet, a bore of 9.2 inches, and measures 36 inches in external diameter at the breech and 18 inches at the muzzle. It fires a 380-pound projectile with a muzzle velocity of 2,900 feet per second, and a muzzle energy of 22,160 foot-tons. The penetration of wrought iron at the muzzle is 37 inches, and at the minimum fighting range of 3,000 yards its projectile striking squarely would pass through 11 inches of Krupp steel, so that the water-line armor of practically every battleship afloat would be penetrable by this gun.

The piece is built by the wire-wound method. It consists of an inner tube containing the powder chamber and the rifling, over which is shrunk a heavier inclosing tube of gun steel, and upon this is wound, under very high tension, the wire upon which the gun mainly depends for its tangential strength. Over the wire is shrunk on a single heavy jacket, which extends from the breech for nearly two-thirds of the length of the gun, and a chase hoop, or tube, which extends to the muzzle, which latter is slightly swelled to a large diameter, to give the extra reinforcement needed to prevent splitting at this point.

The breech mechanism is shown very clearly in our illustrations. The whole of the breech action, namely, unscrewing the plug, withdrawing it, and swinging it clear of the breech box, is accomplished by the continuous rotation of the hand-wheel shown to the right of the breech. The breech plug is of the same type as that used in our navy. It is threaded in segmental portions on steps of varying radii, an arrangement which enables three-quarters of its circumference to be threaded, and to be available for meeting the longitudinal thrust on the block. The ordinary type of block has only half of its circumference threaded, so that the new type of plug may be made proportionately shorter than the old. This shortness of the plug enables it to be swung clear from the breech as soon as it is unscrewed, thus saving the time occupied in the old type of block in withdrawing the plug in line with the axis of the gun, before swinging it clear of the breech box.

Another element of interest in this gun is found in the fact that it is built upon the same principles and is of the same general efficiency as the Armstrong gun, with which nearly the whole of the Japanese navy is armed; although it should be understood that this particular caliber of gun is not used by the Japanese, whose battleships and cruisers are armed with the 12-inch, 8-inch, 6-inch, and 4.7-inch Armstrong guns. The 9.2-inch gun, however, forms the primary armament of the British cruisers, and the intermediate battery of the latest types of British battleships, just as the 8-inch gun occupies the same place in the respective classes of ships of our own navy. The latest British designs carry eight of these 9.2-inch guns in four barbetstes, in addition to the primary armament of four 12-inch guns—an impressive evidence of the vast increase in the offensive power of warships, due to the improvement of ordnance and the increase in displacement.

Underground hospitals and mule stables, methods of ventilating and draining mines, of robbing pillars, and flooding with culm are illustrated in an interesting world's Fair exhibit made by the Pennsylvania commission in the Palace of Mines and Metallurgy at the World's Fair.



## Correspondence.

## A Letter from Leo Stevens.

To the Editor of the SCIENTIFIC AMERICAN:

I have decided not to enter the airship contest at St. Louis. The speed expected is too great. The man who enters this contest has everything to lose and nothing to gain.

The rules call for a speed of at least 20 miles per hour. This is impossible. The prize is perfectly safe with the Exposition Company.

I think the rules might have been modified just a little. For instance, the man making best time should be allowed to take first prize, second man second prize, and third man third prize. There would then be something in sight. Many Americans would certainly enter.

I will continue experimenting in this vicinity during this year and will prove what the American can do.  
Aeronaut LEO STEVENS.

New York, March 5, 1904.

[The rules governing the airship competition at St. Louis have, we understand, recently been modified, so that the speed required is now 18½ miles an hour, and the course to be covered 10 miles.—Eb.]

## Draper's Specula Test.

To the Editor of the SCIENTIFIC AMERICAN:

A paper by myself upon the above subject was published in the SUPPLEMENT, page 23232. A criticism by Mr. Edmund M. Tydeman appears in the SCIENTIFIC AMERICAN for November 14, page 348. Residence in Australia precluded earlier rejoinder.

In my paper, by a purely analytical method, developed step by step from first principles, and given *in extenso* to enable the results to be checked, the connection between variation of ordinate and variation of the position of the axial intersection of a ray after reflection from a parabolic surface is demonstrated. The results are compared with those computed for identical conditions by Draper's rule, and the latter is proved to be 50 per cent in error.

Mr. Tydeman in his strictures has wholly failed to grasp the significance of the third (III.) premise, clearly expressed, of the analysis, or to assimilate the subsequent treatment. Mr. Tydeman misquotes. In the second paragraph the factors represented by  $x$  and  $z$  are transposed; by this and the succeeding quotation a serious false issue has been raised. In the next instance the expression the "*constant H P*" (italicized in the letter) is substituted for the correct definition—"normal"—used by me. The position of the critic that the angle contained by an incident and reflected ray is *not* bisected by the correlated normal (not "*constant*" as wrongly quoted)  $DH$  to the reflecting surface is, of course, untenable. The matter, although a most essential point, is, optically, elementary; bisection is the corollary of Newton's second axiom in optics, hitherto unquestioned.

In the same paragraph Foucault's and Draper's methods are classed together as though identical; they differ broadly, as all who have used both know, and as recourse to the original memoirs will prove. In compilations they are not infrequently erroneously conjoined. My paper deals specifically with Draper's formula.

In the last paragraph Draper's formula is defended by attributing error to rules differing from it.

The errors and misapprehensions indicated wholly vitiate the criticism, and confirm the opinion that the reputation of the reflecting telescope, as an instrument of precision, has suffered by the unquestioning acceptance, without investigation as to their genesis, of "authoritative" formulae.

It is assumed that the original will be compared by those interested.  
JAS. ALEX SMITH.

Melbourne, January 13, 1904.

## Actinic Light.

To the Editor of the SCIENTIFIC AMERICAN:

An article on "Some Experiments with Actinic Light," by J. W. Kime, M.D., appeared in the SCIENTIFIC AMERICAN for June 20, 1903. There are in this article several very misleading statements and erroneous conclusions. Soon after its appearance, having occasion to prepare a paper for the Scientific Society of the Ohio University, with the help of Mr. J. O. Wright, assistant in the department of physics and electrical engineering, I prepared to demonstrate the fallacies of Mr. Kime, and to set forth the correct views of the subject. This was done by citing authorities, by a number of experiments, and by the use of lantern slides showing the effects of light under a number of different conditions.

In this communication I only desire to select from the paper above referred to a few points, which will sufficiently show forth Mr. Kime's mistaken notions about actinic light.

In the very first paragraph we read, "the light of the sun is composed of *three distinct kinds of rays*,

luminous, heat, and chemical, or actinic." Italics are mine. Now, the fact is, the only inherent physical difference in light waves so called, is one of *wave length*. Moreover, the very same rays may produce all three of the effects named, though in varying degrees depending on the wave length. Electro-magnetic waves of the magnitude of sound-producing air waves are now utilized in the transmission of wireless messages; when they are much shorter, and approach the infrared, but still too long to affect the sense of sight, they begin to produce heat. Still shorter, produce more intense heat effect. When we come into the region of  $\lambda = 0.8 \mu$  (micron), we have the first visible portion of the spectrum. As the waves become shorter and shorter, the color changes through orange, yellow, green, blue, indigo, to violet,  $\lambda = 0.36 \mu$ , the heat effect in the meantime decreasing and the actinic effect increasing. Passing out into the ultra-violet invisible rays, the chemical action continues to increase; indeed, it is those radiations whose wave lengths are below 0.36 micron which produce the greatest part of the total chemical effect of a given beam of light. Continuing down the scale, we reach the extremely short waves, which exhibit the properties attributed to the X-rays.

It is at least misleading to speak of "those bands of the spectrum which are rich" and "those which are poor" in certain rays. It leaves the impression all the time that a mixture of rays of very different properties, regardless of wave length, is to be understood. Color itself is subjective, the physiological and psychological effect of wave length. Therefore it is absurd to speak of a color being rich or poor in heat or actinism.

In Mr. Kime's fifth paragraph he explains that colored strips of glass corresponding to the spectrum colors were used. "In this manner," he says, "we obtained a *true photograph of actinic light*," etc. In his sixth paragraph we read, "we are unable to recognize any difference whatever between the open space (no colored glass) and the blue glass." Also, he says less light passed through clear glass (one thickness) than either the clear space or the blue glass. These statements will be examined further down. In the next paragraph he concludes from his observations just quoted that "blue glass cuts off no chemical light," and that "the ultra-violet rays are either not markedly actinic, or that blue glass does not retard their passage. It is very evident one hundred per cent of actinic light has reached the plate through the blue glass." He also finds no regularity of actinic effect. "The yellow," he informs us, "transmits an *appreciable* amount, and the green *just enough* to be seen. From this point we jump from almost zero in the green to *one hundred per cent* in the blue." "In the violet," again, "we drop back to almost the same percentage as in the yellow." And now to the profound and revolutionary conclusion that "*wave length has nothing to do with determining the chemical activity of light*." From this list of insufficient and erroneous data he further generalizes: "It is apparent from our photographs that color, *independently of wave length, influences the chemical action of light*." In all cases the italics are mine.

In the paragraph headed "Experiment No. 2," Mr. Kime either does not say what he intends, or else he does not know exactly what his photographer did. He informs his readers that No. 2 is a positive, yet immediately says it was taken on sensitized paper, just as No. 1 was taken on a dry plate. If this last is true, then No. 2 is a negative, just as No. 1. But anyone with the most rudimentary knowledge of photography knows that No. 2 is a positive, as stated at first. If so, then it was never printed through the glass strips as was No. 1. Moreover, a glance at once shows that No. 2 was obtained as a positive print through the negative corresponding to No. 1. The No. 1 may also have been made on paper as well as on glass. I do not see how we can do better than count as worthless all conclusions and inferences about relative actinic values when based upon experiments made, apparently, in darkness of the most elementary laws of light. We are also unable to make any extenuation, however conclusive the author of these experiments would have his results appear, in that they were "confirmed by repeatedly going over the experiments, and always with like findings."

Now to illustrate by a few notes from our own experiments the results obtained therefrom. In timing the exposures a seconds pendulum was used, being arranged so as to indicate magnetically its successive passages. In the development exactly the same kind of plates and developer were used throughout, and subjected to the same length of development where results in any way depended upon these conditions.

Two sets of negatives were made with 1.5 seconds exposure and 2 minutes development, under colored films, arranged to give six of the seven spectrum colors. The one set resulted from exposure to sunlight, diffused, and no glass intervening; the other set was exposed through four thicknesses of glass. In the positives the colors, beginning at the left in each, were red, orange, yellow, green, blue, and violet, the indigo

being omitted. There was observed a slight actinic effect through the red; orange, yellow, and green, practically none; blue and violet are alike strongly actinic. This photograph differed from Mr. Kime's result, as well it might. The effects in both sets are equally strong, both in the negative and in the print. The intervening glass, even four thicknesses, caused no difference capable of detection by this means when the visible portion of the spectrum, or that which apparently represents it, is employed. It is well known, however, that glass does have a powerful absorptive effect on those waves lying in the ultra-violet section, so that prisms and lenses made of quartz should be used when studying this portion. For convenience the above colors are 5, 7, 20, 30, 23, 28.

Another positive was made from a negative taken through six films arranged to represent the spectrum, and exposed six seconds, developed five minutes. The colors were 6, 17, 8, 10, 11, 27. Here the red, orange, yellow, and green cut off all actinic rays. The blue and violet only slightly absorb them.

Still another positive was made through seven films, 16, 7, 21, 30, 22, 12, 29. In this the red showed slight effect, orange none, yellow strong, green none, blue and indigo same as the yellow, none of them being 100 per cent. The violet absorbs a large part of the actinic waves. This supposed spectrum would be considered quite anomalous, did we not bear in mind that we are using colored films instead of the true spectrum.

Other photographs were made which showed the actinic effects of the wave lengths in the true spectrum of the voltaic arc. The spectrum was produced by projecting the light from the crater of the electric arc through a glass prism. The visible portion of the spectrum was about three feet long and one foot deep, so that ample room was given for studying the effects in the various bands, and indeed for several positions in the same color. Reference marks were made on the screen, so that the same positions could be used with accuracy any number of times. Mr. Wright constructed an apparatus for exposing successive parts of the same plate in successive parts of the spectrum. His arrangement permitted as many as ten exposures on the same plate.

We made a photograph to show the results in infrared, red, orange, yellow, green, blue, indigo, two positions in the violet, ultra-violet. The negative and print showed nothing for infra-red and red, orange very faint, yellow slightly stronger, still more intense in the green; neither plate nor print shows any difference for the blue, indigo, violet, and ultra-violet. It is known, however, that the effect *does actually* increase into the ultra-violet before beginning to decrease again.

A photograph from red, orange, yellow, green, blue, indigo, two in violet, ultra-violet, and ultra-violet taken far out, perhaps 12 inches beyond the last of the visible violet, showed a perceptible diminution of actinic intensity in the last band.

The conclusions from these data are obvious. It is certainly altogether unreliable to use colored glass or colored films to represent the spectrum. Their coloring matter may absorb some of the waves corresponding to their own apparent color, or let pass waves not corresponding to their color, or both. The experiments cited show that different films of apparently like color produced quite diverse photographic results. Further, it is certainly clear that there is *no irregularity* in the actinic effect, but rather that it increases progressively even to  $\lambda = 0.36 \mu$ , or less, from which point it begins to decrease. *Wave length, and not color*, determines the actinic effect, as it does every other property of electro-magnetic radiation.

A. A. ATKINSON.

Physical Laboratory, Ohio University, Athens, Ohio.

## A Union Building for New York Engineers.

With the present of \$1,500,000 made recently to the Mechanical, Mining and Electrical Engineers of this city, and the Engineers' Club, steps were immediately taken toward the completion of plans for a union building, which the gift provides for. The building will have a 125-foot frontage on West Thirty-ninth Street, and will be backed by the new Engineers' Club building—a separate structure opposite the new Public Library on West Fortieth Street. It will probably be twelve stories high, and besides spacious headquarters for the three national engineering societies, there will be several auditoriums of various sizes, one of which will seat 1,200 to 1,500 people; an engineering museum; and a library having at the start 50,000 volumes, and which, in co-operation with the Public Library, will be the finest technical library in the world.

The three societies, each of course maintaining its identity and autonomy, will need considerable room in the new building, which it is hoped to have completed by 1906. These societies have to-day a combined membership of over 9,000, and they are growing at the rate of from 10 to 15 per cent. annually. Besides these societies, there are other technical societies having some 5,000 members engaged in all branches of civil, mechanical, electrical and municipal engineering, whom it is desired to accommodate.

**THE ABRUZZI POLAR EXPEDITION.—I.\***  
Great interest attaches to the Abruzzi polar expedition in view of the fact that it was conducted by His


\* A review of "On the 'Polar Star' in the Arctic Sea," by his Royal Highness Luigi Amedeo of Savoy, Duke of the Abruzzi, New York: Dodd, Mead & Co. 1903. Two volumes.

Royal Highness Luigi Amedeo of Savoy, Duke of the Abruzzi, and a member of the Italian royal family. The object of the expedition of the "Polar Star" was to sail as far to the north as possible along some coast line, and then to travel on sledges toward the pole, from the place where the winter had been passed. The


pole was not reached by the sledge expedition, led by Commander Cagni, but he pushed on to a latitude which no man had previously attained, and proved that with determination and sturdy men and a number of well-selected dogs the frozen Arctic Ocean can actually be  
(Continued on page 254.)




Dr. Cavalli Prepares the Rations.




Christmas Dinner.



Clearing the Ship from the Ice.



The "Polar Star" Abandoned in the Ice.




The Hut by Moonlight.



Landing the Stores While the Ship Was Nipped by the Ice.



Dragging the Kennels up on the Beach.



View of the Camp from the West.

THE ABRUZZI POLAR EXPEDITION.—I.




THE HUDSON RIVER TUNNEL.

March 11, 1904, marks the successful culmination of the work begun thirty years ago on the Hudson River tunnel. On that day the junction was made between the New Jersey heading and the old New York section of the north tube and Mr. William G. McAdoo, president of the New York and New Jersey Company, was accorded the honor of being the first man to pass from Jersey City to New York under the Hudson River. The progress of this tunnel from its inception up to the present time has been periodically chronicled in these columns, so that our readers will not need a lengthy account of the undertaking, but a brief *résumé* of the principal events which mark the history of this great engineering enterprise may be in order.


The original projector of the tunnel was Mr. Dewitt Clinton Haskin, under whose direction the work was begun in 1874. A shaft was sunk at Fifteenth Street, Jersey City, and at the foot of Morton Street, New York, and from the bottoms of these shafts twin tunnels were run out under the river. In carrying out this work no excavating shield was used, as it was thought that the silt was sufficiently compact to hold its position until the two-foot brick lining was set in place. This surmise proved incorrect, and it was found necessary to use a five-foot pilot tube, which was pushed ahead of the main tunnel and used as a center for radial braces, which supported the tunnel wall under construction. The work was carried on without serious accident until in July, 1880, the shallow layer of silt between the tunnel roof and the river gave way under the pneumatic pressure in the tunnel, and the inrushing water drowned twenty of the workmen. The work was then continued half-heartedly for two years, when, with 2,000 feet of the north tunnel completed, it was abandoned. In

1890 an English company took up the work, using an excavating shield, and working from the Jersey end carried the tunnel forward to within 1,500 feet of the old New York heading. Again the work was aban-


doned until 1896, when the New York and New Jersey Company took charge of the work, and in 1902 began the work which has since been carried out to its present successful issue. This magnificent engineering achievement of Jacobs and Davies, engineers of the New York and New Jersey Company, in accomplishing that which had twice before been attempted and abandoned, is deserving of highest praise, particularly in view of the fact that difficulties were met and successfully overcome, which the other companies did not encounter and which, in fact, the engineering world has never before been called upon to master. The work had progressed only a few hundred feet when rock was encountered in the lower part of the tunnel. The excavating shield in use, the one that the English company had installed, was designed to be forced through silt, and it would merely have crumpled into a shapeless mass if it had been forced against this rock barrier. It was necessary, therefore, for the workmen to advance beyond the cutting edge of the shield, and blast out this rock before moving the shield forward. If the rock had covered the entire face of the shield, this would have been a comparatively easy matter; but the engineers were confronted by the unique problem of driving the floor of the tunnel through rock and the roof through silt. To meet these conditions, it was found necessary to build an apron out in front of the shield, which would protect the workmen from the silt above. This apron, as shown in one of our illustrations, extended from side to side of the tunnel shield near its center line, and projected forward about 6 feet. It was built of  $\frac{3}{4}$ -inch steel plates laid on brackets formed of 12-inch I-beams. This apron enabled the workmen to attack the rock without fear of being smothered by an avalanche of the soft silt above. Even with




Blasting Out Rock Under the Protecting Apron.



Junction of the Two Sections, Showing Also the Tilted Position of the Shield.



The New Shield at Morton Street, Which is to Continue the Tunnel Under the City.




Sectional View, Showing the Course of the Tunnel Under the Hudson River.  
THE HUDSON RIVER TUNNEL.

this protection the work was not without danger, as the rock varied in height from 1 to 16 feet. Fortunately, no casualties resulted, and the passage was slowly but steadily forced through the rock reef. With this danger past, the remainder of the work was comparatively simple, and the tunnel was rapidly pushed on to the New York heading.

As the work advanced, the course of the tunnel was carefully plotted out, and the excavating shield was steered by increased pressure in one or another of the hydraulic jacks, in order that it should be brought into perfect register with the brick lining of the New York heading at the point of juncture. So careful were these calculations, that when the shield met this heading, the lateral alinement was found to be almost perfect; but vertically, an error of a few inches was made. This break is temporarily sealed with blocks of wood driven into the silt above the shield, as shown in one of our photographs.

While the shield was being operated by the English company, it was noticed that instead of remaining stationary on its axis, it was gradually turning clockwise as viewed from the front. Every effort was made to stop this movement; but it continued, until now, having traversed 3,400 feet of silt, it presents the appearance illustrated, with the vertical plates lying almost horizontal. This curious action was probably due to a slight deflection of the plates in front of the diaphragm of the shield, which tended to turn the shield through an imperceptible angle every time it was jacked forward, and these slight deflections gradually accumulated until they became quite noticeable. The tunnel has an internal diameter of 18 feet 1½ inches, and is lined with cast-iron segments 1½ inches thick, braced with webs and formed with inwardly-projecting flanges, which provide means for firmly bolting the sections together. At present a pressure of 22 pounds per square inch above normal is still maintained in the greater part of the tunnel, to prevent water from seeping through the joints of the lining, which have not yet been calked up. The shield must now be dismantled, and the cast-iron sheathing or lining run out to join the brick lining of the old heading. The shell of the shield, however, cannot be removed, and will be buried behind the cast-iron lining, a final sacrifice to the work it has served so long and faithfully.



Proposed Extension of the Hudson River Tunnel.

pleted. The English company, in order to save the cost of cartage, spread the silt, as it was excavated, over the floor of the completed section, and as a consequence a large part of the tunnel on the Jersey side is more than half filled with this material, and it must all be removed before the work of laying car tracks can be commenced.

The south tunnel, which is being run parallel to the completed tunnel, is also being excavated from the New Jersey side, and is now well under way. A distance of three-quarters of a mile remains yet to be tunneled. A new shield was built for this work, and in anticipation of the difficulties encountered in the north tube, it was provided with an apron, which can be moved out in front of the shield to permit blasting out rock in front of the cutting edge.

We illustrate herewith a new shield, now in position, which will continue the north tunnel through the city under Morton Street and Ninth Avenue to Tenth Street, where the New York station is to be built. The course of this tunnel, together with the proposed extension, is shown in the accompanying map. The purpose is to continue the tunnel up Tenth Street to Sixth Avenue, and thence up to Herald Square, with intermediate stations at Greenwich, Fourteenth, Eighteenth, Twenty-third, and Twenty-eighth Streets.

These tunnels are intended only for the use of electric cars, and not, according to the popular misapprehension, for heavy railway trains. It is the opinion of the engineers that the silt foundation is too soft to permit the passage of heavy weights through the tunnel. The silt, though very compact under the weight of the water above, nevertheless has the properties of a viscous fluid, and it is feared that it would yield under the impact and weight of a heavy steam or electric locomotive. Such yielding, though but

little, would place a tremendous bending strain on the cast-iron lining, above that it could bear, and ever so slight a rupture would result in dire consequences.

A combined elevator and air lock is in use at the head of the New York shaft. The elevator shaft ends in an air lock at its upper end, and the circular platform of the cage, when in its highest position, completely closes the mouth of the shaft, and forms the bottom of the air lock. As the compressed air is released from the lock, this platform is forced snugly in place, making an air-tight closure. The cable by which the elevator is suspended must, of course, pass through the top of the air lock, and to prevent leakage of the compressed air it is incased in a long stuffing box. The movement of the cable through this stuffing box is so slow as not to seriously wear the packing.

#### THE ABRUZZI POLAR EXPEDITION.—I.

(Continued from page 252.)

crossed to the highest latitude. Besides attempting to reach the highest possible latitude, the expedition was also calculated to take observations on gravitation and terrestrial magnetism, and also to enlarge our meteorological and hydrographical knowledge of the localities which were to be visited and to collect as much information as possible with regard to the flora and fauna of Franz Josef Land.

Dogs are undeniably the most useful animals for man in his Polar expeditions where sledges must be dragged over the ice of the Polar Sea. They have this advantage also, that, unlike horses and reindeer, they readily eat their fellows. Their weight is small, and they can be easily carried on light boats or on ice floes. As the Danish government has forbidden the exportation of dogs from Greenland, it was decided to bring them from Western Siberia, and an order was given in July, 1898, for one hundred and twenty dogs.

The vessel selected was a whaler about to start for the seal fishery. The "Jason" as she was called, could carry 570 tons of cargo, was 131 feet long, 30 feet 6 inches wide, and drew about 16 feet. Her engines were of 60 nominal horse power and gave a speed of from 6 to 7 miles an hour. The ship had a new boiler and carried a spare propeller and rudder. Many changes were required to be made. Stanchions were placed in the hold, the lower deck, which is movable in a sealer, was firmly fixed, the masts were changed, and the vessel was transformed from a bark to a barkentine. As the object of the expedition was to reach that spot on the surface of the earth near the zenith of which shines a star, known to all from the man of learning to the peasant, what name could have been more appropriate to the ship than "Stella Polare"? So the "Jason" became the "Polar Star." The expedition consisted of His Royal Highness the Duke of the Abruzzi, Capt. Cagni, Lieut. Querini, Dr. Molinelli, Capt. Evanson, who navigated the vessel, three officers, four Alpine guides, and eight sailors. The expedition took with it supplies for four years and a preference was given to those kinds of food which had been chosen by Nansen for the first expedition of the "Fram," and Sverdrup had chosen for the second. As much variety as possible was aimed at in the choice of the supplies, so as to avoid tiring the palate. Food was divided into cases of 55 pounds each, containing the same variety, so that the contents would be accurately known at all times. Plenty of furs, coats, and woolen garments were taken. Special attention was given to caps, gloves, gauntlets, stockings, and shoes; so that all conditions of weather could be met. Stoves, tents, sledges, dog harness and firearms were also liberally provided, and 440 pounds of gun-cotton for blasting the ice were also taken. Great care was taken in the selection of the scientific instruments. Four balloons were provided, of varying shapes. Two of them were selected for actual use in the expedition. They were packed in crates to allow the air to circulate and were placed on deck along with the apparatus for producing hydrogen gas, and a small boiler. Thirty-six iron tanks containing about twelve tons of sulphuric acid were placed in the center of the deck in an inclosure lined with lead and provided with a gutter so as to prevent the acid from burning the boards of the deck in case of leakage. Six tons of iron filings completed the aeronautical outfit.


The "Polar Star" left Christiania on June 12, 1899, and Archangel was reached on June 30, where the dogs were embarked. Two rows of cages, one above the other, were built against the bulwarks of the ship on both sides. The first row rested on the deck, the other was one yard above it, and these cages were separated by wooden partitions. Four dogs were placed in each and chained to the corners so that they could not bite each other. As the cages and their floors were covered with gratings and tarpaulin, they could be frequently washed and the dogs were kept dry. The final departure of the expedition occurred on July 12 and three days later they met ice for the first time, and on July 20, the misty outlines of Northbrook Island were sighted; the Emperor Franz Josef archipelago lay be-

fore them, and the huts left by Jackson's expedition were discerned. Provisions for eight months and five tons of coal were landed, so that in case of any misfortune to the ship which would necessitate a retreat these stores would enable the explorers to subsist until the following summer. Various observations were made and on July 26 the trip was resumed. On August 5 a vessel was sighted and there was little question that this was the "Capella." The "Polar Star" signaled to know if the Wellman expedition was on board. A launch in which a man who had the appearance of an invalid was lying, with one leg stretched out, left the "Capella" and went toward the "Polar Star." Although very dissimilar from the photographs which the Duke had seen in the newspapers, he recognized Wellman. The latter was lifted on board and he was helped into the saloon. Other members of his party accompanied him. It seems that Wellman had met with an accident shortly before arriving, so that the expedition was forced to return, as it had lost some of its provisions when pressed by the ice floes and it had reached its highest latitude near the above-mentioned island. After a few pleasant hours the two ships sailed away, the "Capella" steering southward to return to civilization, while the "Polar Star" steered for Maria Elizabeth Island. On August 7, Prince Rudolph Island was reached, the latitude being 82 deg. 4 min. The "Polar Star" thus reached with the greatest ease the Emperor Franz Josef archipelago, which in 1873 Payer had thought so difficult to approach. The expedition disembarked in the Bay of Teplitz and its members immediately set to work to prepare the winter quarters. Kennels were built for the dogs, which showed little affection and still less obedience. They fear only the whip and water; for in the intensely cold regions where they live, if they get wet, the water freezes immediately on their bodies and forms a cuirass which hinders every movement. The ice field driven by the pack closed up the channel made by the "Polar Star," heeling her over about thirteen feet. The ship was righted by means of some gun-cotton mines which had been sprung on the left side, but the vessel did not remain long in normal position, as the ice again succeeded in heeling her over. The ice field in the bay driven by the ice pack had risen all around over that which lay along the coast and had reached up to the kennels, against the door of which some large floes had been piled up, thus preventing egress. When the dogs gave the alarm the crew ran to extricate them by breaking the inner partitions and letting them out on the side of the land. The vessel had also sprung a leak. There was grave danger that if the ice gave way the boat would sink, and, therefore, they were obliged to land with the utmost haste the stores for winter, and to secure the necessary materials for building a dwelling house. The outlook of a winter passed in this bay, with but scanty resources, and of a retreat to be carried out with still more scanty resources in the following spring, was gloomy. It was hard to work on board as the ship heeled over so much and the deck was covered with ice. Disembarkation continued all that day with the exception of intervals for meals. As the ship still remained in the same situation, which had not become more dangerous, and as all that was required to pass the winter had been rescued, they began to disembark what would be wanted for the sledge expedition, so that if the vessel was lost they would still have the means of accomplishing the undertaking for which they had set out. The heeling over of the vessel had rendered life on board uncomfortable, and any further pressure of the ice might have cast her on her beam ends and obliged the expedition to abandon her completely. It was therefore decided that it was better to leave her and take up land quarters where they would be safe from any sudden danger. The expedition had been provided with two field tents which would lodge the whole crew, though they alone would not suffice to protect them during the winter, or to resist the violence of the wind, but were strengthened with additional covers, also of canvas, so as to form air spaces between them, so that a sufficiently high temperature could be kept up inside, and, if the outer covering were made of stronger sail cloth, it would be able to resist the wind. The canvas awning which had stood on the deck, with the poles and cross-bars which formed its framework, was well suited to stand over the field tents. With the spars and the sails of the ship the third tent was constructed which covered the others.

(To be concluded.)

Newton's law of gravitation, which states that two bodies attract each other with a force inversely proportional to the square of the distance between them, has been made the subject of an exhaustive investigation by Prof. Brown, of Haverford College, says the Iron Age. He announces that his calculations show Newton's law to represent the motion of our moon to within the one-millionth part of one per cent, and states that no other physical law has ever been expressed with anything like the precision of the simple statement of this one.





#### A Bill for Establishing a Sliding Scale for Copies of Patents.

A very obnoxious bill has been reported by the House Committee on Patents, and is now before both Houses of Congress. The matter in itself is a very small one, but should this bill become a law, it will prove to be a most vexatious measure and, instead of facilitating and expediting the work of the office, it will serve to embarrass and annoy inventors, and produce a condition of affairs which is as unnecessary as it would be intolerable. The bill as presented to the House is as follows:

"Sec. 493. The price to be paid for uncertified printed copies of specifications and drawings of patents shall be determined by the Commissioner of Patents: Provided, That the maximum cost of a copy shall be ten cents for each unit of five pages, or fraction thereof, contained in the specification and drawing of such printed copy."

We cannot but feel that this measure providing for a sliding scale of cost savors of a petty and useless economy, which should not for a moment be considered by Congress. Instead of interposing vexatious conditions, every facility should be afforded inventors and attorneys for procuring copies of patents with the greatest possible ease and dispatch.

Copies of patents are now furnished at the general rate of five cents each. The Commissioner claims, however, that a few patents are very diffuse, and show an immense number of sheets of specifications and drawings, ranging sometimes from 50 to 200 pages, and that the price of five cents does not cover the cost of publishing patents of this size. This may be perfectly true, but on the great majority of patents there should be a good margin of profit to the Patent Office. For example, we have taken at random one hundred copies of patents which have recently come to hand; estimating the value of the paper at five cents a pound, which is more than liberal, we find that the cost of the paper for the one hundred copies comes to 19 cents, or in short, that the cost of the paper, per copy, averages less than two mills. It would seem that the printing should not much exceed the cost of the paper; in fact, a local printer has estimated the cost of the mere printing and paper, not including the original cost of plates, at about one and a half cents a copy. It is apparent, therefore, from this, that the average profit on the ordinary run of patent copies should far more than make up the loss on the few patents of excessive size which are issued.

Even if this department were run at a loss, which has been questioned by the Patent Law Association of Washington, which has begun a campaign against the bill, certainly the outlay on the part of the Patent Office is well expended, owing to the facilities which are offered and which should be offered to the inventors throughout the country. Attorneys throughout the land are perfectly familiar with the difficulties and delays now arising from the narrow policy already pursued by the Patent Office with reference to patent copies. Only 75 copies of each patent are printed. Of this number 35 are sent abroad for distribution among foreign patent offices and libraries. This leaves a supply of only 40 copies for distribution throughout this great and glorious land. The inventor himself can only procure 10 copies of his own patent at one time. The supply of copies is constantly running out, and attorneys and inventors are being constantly subjected to annoyance and delay incident to waiting upon the pleasure of the Patent Office to print new copies, or else they are obliged to have made hand copies, which are quite expensive.

The proposed introduction of a sliding scale of cost is quite out of the question in a great institution like the United States Patent Office. This system has been tried in England and has been abandoned as impracticable. In case the inventor writes to an attorney ordering a number of copies distributed through different classes, it would be necessary, first, for the attorney to send a clerk to the Patent Office, have a search made through the records, count the pages in each patent ordered, form an estimate of the extra cost of such patents as may have more than five pages, write back to the inventor informing him of the amount of the charge, and after all this work has been accomplished, has there been any saving to the Patent Office? No. A large force of clerks would be required in the Patent Office, to ascertain the cost of copies ordered and answer the many inquiries of attorneys all over the country. Such an expense would greatly add to the cost of obtaining the copies, and it is not readily seen how the income of the Patent Office would be greatly, if at all, increased by such a vexatious system. Considering that the United States Patent


Office turned into the Treasury last year a surplus of \$193,556, the necessity for such niggardliness as is shown in the proposed bill seems utterly inexplicable.

The Patent Office can well afford to bear a loss of several thousand dollars a year, were such an amount necessary, rather than subject the inventor and the public to such an annoyance. If Congress feels that the Patent Office should not be allowed the use of its own income, let it increase the price of copies from five to ten cents each; but let us have one uniform rate for all copies ordered, and let an adequate supply be printed every week, so that the delays, annoyances, and medieval methods now in vogue may be done away with.

#### COMBINATION LOCK FOR UMBRELLAS.


In order to prevent the misappropriation of umbrellas, whether intentional or otherwise, Dr. R. B. Waite, of Springville, N. Y., has provided a device which will increase the spring latch of an umbrella, to prevent the umbrella being opened by an unauthorized person. The device is provided with a simple combination lock, which will render it impossible for anyone not familiar with the proper combination to operate the latch. The lock is so arranged that the owner can open it in the dark, the proper combination being recognized by a number of clicking sounds produced when the lock is being operated. As shown in our illustration, the device consists of a casing which, at its lower end, fits snugly onto the runner sleeve of the umbrella, but is formed with an enlarged portion which covers the spring latch. A number of disks are held in the upper end of this casing, between an indented shoulder formed therein and a cap which is soldered to the top. A keyway is cut in each of these disks, and it is only by turning these disks until they are all brought into alignment with the key formed on the runner sleeve, that the casing can be pushed upward. The disks are brought into position by turning the casing a certain distance in one direction, and then a certain distance in the opposite direction, these distances being indicated in each case by a predetermined number of clicks, due to a spring pawl formed on the upper end of the casing slipping into notches formed on one of the disks. Our illustration shows the disks in the aligned position, and the casing partly moved upward. It is evident that further upward movement of the casing would result in pressing down the spring latch, thus releasing the runner sleeve from engagement therewith, and permitting the umbrella to be raised.

COMBINATION LOCK FOR UMBRELLAS.



#### HARROW TOOTH AND SIMPLE FASTENING DEVICE.

The harrow tooth which is illustrated herewith is adapted for convenient attachment upon a frame beam of a harrow, and its construction, which is extremely simple, is such as to prevent movement of the tooth in any direction while, at the same time, permitting it to be readily detached when desired. In the case of




HARROW TOOTH.

a double-pointed tooth the construction also permits the tooth to be readily reversed in position, thus substituting a sharp end of the tooth for one that is worn out. The shank or body of the tooth is formed with two lugs, that project from opposite faces of the tooth. The lower lug is adapted to fit under the angle-iron frame of the harrow, and the upper lug

rests on the fastening device. This fastening device or clamp consists of a U-shaped member, whose ends pass through perforations in the vertical flange of the angle iron. When the clamp is adjusted, it is permanently secured in place by means of nuts threaded on to these ends, and bearing against the rear face of the vertical flange. At the right in the illustration, we show a tooth pointed at both ends, and it will be evident at a glance that this tooth may be applied as readily with either point in the downward or operative position. This same construction may be advantageously applied to secure cultivator teeth to the frame beam of a cultivator. A patent for this invention has recently been granted to Mr. John Y. Cooper, Rural Route No. 5, Nashville, Tenn.

#### VALVE MECHANISM FOR LOCOMOTIVES.

We illustrate herewith a new valve mechanism for locomotives, which when the locomotive is starting and climbing grades may be operated by the engineer, to admit steam in the usual manner at both ends of the cylinders, but when running or traveling down-grade can be operated to admit steam only at the forward or at the rear ends of the cylinders. Mr. Martin Schilde, 432 Philip Street, New Orleans, La., is the inventor of this valve mechanism. The accompanying engraving shows in section two forms of Mr. Schilde's invention. The cylinder is provided with the usual steam admission ports *D* and *E*, and the exhaust port *L*, and in Figs. 1 and 2 these communicate through ports in a plate *G* with the valve cylinder of the valve *F*, which is connected by the valve stem *J* with the link movement in the usual manner. The plate *G* is secured to the bottom of the valve cylinder, and by means of the rod *H*, which leads to the engineer's cab, may be moved to any desired position over




VALVE MECHANISM FOR LOCOMOTIVES.

the ports of the main or piston cylinder. With the plate in its central position, as shown in Fig. 1, steam will be admitted to the cylinder at either end. When the valve *F* moves to the right, steam enters the cylinder at the left end through ports *A* and *D*, at the same time the left end of the piston cylinder is opened through ports *E* and *B* to the valve cylinder, and thence through ports *C* to the outlet port *L*. When the valve *F* is moved to the left, the conditions are reversed. Steam enters the cylinder through ports *B* and *E*, and the exhaust passes out through ports *D*, *A* and *C* to *L*. When it is desired to admit steam only to the forward end of the piston cylinder, the plate *G* is moved to the position shown in Fig. 2, when the port *D* is always in communication with the exhaust port *L* through port *A*. Now, when the piston is moved to the left, the port *C* is uncovered, permitting steam to flow through *E* into the cylinder; and when it is moved to the right, the steam is permitted to escape through ports *E*, *C* and *A* to the exhaust port *L*. It will be readily understood that when the plate *G* is moved so as to bring the port *C* into register with port *D*, the action will be reversed, steam being admitted at the left end of the cylinder only. In Fig. 3 we show a modification of the construction, as adapted for use with a slide valve. With the parts in the position illustrated, port *E* is always in communication with the exhaust *L*, through port *P*, and port *D* connects first with the steam chest through port *O*, and then with the exhaust port *L* by way of the cavity in the valve *K* and the port *P*. Steam would be admitted to either end of the cylinder alternately if ports *O*, *N* and *M* were brought into register respectively with ports *E*, *L* and *D*. In order to admit steam to port *E* only, the plate would have to be moved to the right until port *M* registered with port *E*, when port *D* would be connected with the exhaust through port *R*.

**BENDING DEVICE.**


The accompanying illustration shows a portable bending device for bending wrought-iron and steel pipes, such as are used for conveying gas, water, steam, and the like. The bending device is very simple, and can be easily operated, and owing to its portability it will be found very useful for bending pipes along the route of a pipe line. The device comprises a beam, formed at one end with a fork adapted to fit over the pipe which is to be bent. Conical plugs are removably secured to each end of this pipe, and these plugs are engaged by loops, which afford a means for attaching

**BENDING DEVICE.**

a pair of sheaves thereto. The cable passes over these sheaves, and also over a sheave secured to the lower end of the beam. The two ends of this cable are hooked over a horn formed on the upper end of a rack, which is slidably mounted on the beam. At its lower end this rack is held in a frame, which also carries a lever device, by which the rack may be moved downward, exerting a pull on the cable to bend the pipe until the desired curvature has been reached. In our illustration the right-hand end of the pipe is broken away to show the form of the plug used. It will be observed that aside from being formed with a projecting pin, which closely fits into the bore of the pipe, the plug is also provided with a sleeve, which fits snugly over the exterior of the pipe. This prevents the end of the pipe from losing its shape during the bending operation. The inventor of this bending device is Mr. Theodore Damm, care R. H. Smith, 606 Pennsylvania Avenue, West, Warren, Pa.

**IMPROVED WINDMILL.**

A patent has recently been granted to Mr. J. G. Benster, of 910 Railroad Avenue, Moline, Ill., for a

**IMPROVED WINDMILL.**

windmill of improved construction, which is designed to insure a direct and full transmission of the power developed in the wheel. The construction of the windmill is clearly shown in the accompanying engraving, in which the windwheel is partly broken away to show details. The frame of the windwheel is mounted to rotate on the upper end of a hollow mast. A horizontal stud projects from the frame, and on this the hub of the windwheel rotates. An eccentric disk formed on the inner end of this hub has peripheral engagement at the top and bottom, with friction rollers journaled in a vertically movable yoke. This yoke is secured to the top of the pump rod, which passes down through the hollow mast. Two elliptical

springs hold the friction rollers in engagement with the eccentric, so that when the windwheel rotates, a reciprocating movement is imparted to the pump rod. The vane which holds the wheel to the wind is journaled to the frame of the windwheel, and on the lower hub a segmental bevel gear is formed, which engages a similar gear segment mounted on a stud projecting from the windwheel frame. A weighted arm, which extends from the hub of the latter segment, normally holds these segments in such position that the vane lies at a right angle to the windwheel. Means for throwing the windwheel out of the wind are provided in a segmental spur gear, also formed on the hub of the weighted bevel-gear segment, which engages the teeth of a rack. This rack can be drawn down by means of two depending rods, thus rotating the gear wheels and shifting the vane to idle position; that is, to position parallel with the plane of the windwheel. The wings or sails of the windwheel are formed of wood, and are held in place by two concentric metal rings, which are slotted to receive these wings. The rings are supported by spokes from the central hub. In forming the slots in the rings, the metal is struck up to form flanges, which are bent around the wings and hold them firmly in place. By means of this simple construction it is possible to readily replace an injured wing with a new one whenever desired without taking the rest of the wheel apart.

**MAIL BOX FOR RURAL FREE DELIVERY ROUTES.**


A mail box which is particularly adapted to meet requirements that have arisen in connection with the rural free delivery system has recently been invented by Mr. Howard G. Leffingwell, of Severy, Kan. It will, of course, be understood that in rural delivery systems the mail boxes are placed along the delivery routes, which in many cases are some distance away from the houses of the owners. This box is, therefore, provided with means for automatically indicating to the box owner that mail has been deposited in the box by the postman, and to the postman that mail has been deposited in the box by the owner for collection. As shown in the illustration, a balanced platform is placed in the bottom of the box, and this is connected by a rod to one end of a lever pivoted near the top of this box. The other end of the lever normally lies just below a lug formed on the door of the mail box. When mail is placed in the box, its weight depresses the platform, thereby raising the outer end of the lever, so that it encounters this lug when the door is closed, and the lever is thus bodily pushed backward. The lever, it will be observed, is pivoted to a crank secured to a rod, which at its upper end carries a semaphore, and thus when the lever is forced backward, the rod is turned on its axis, swinging the semaphore to the position which indicates the presence of mail in a box. When the owner opens the door, the semaphore, under action of a spiral spring on the rod, swings back to normal position, and on removal of the mail the platform rises, permitting the outer end of the lever to drop, so that when the door is closed again, the lug will not strike the lever, but will pass over it. When the owner deposits mail in the box, he raises a crank at the side of the mail box. This operates to support the end of the platform, as shown in our small detail view, and prevents it from tilting, under the weight of the mail deposited thereon, so that when the door is closed the semaphore is not set. A signal is secured to the outer end of the crank, so that when raised, it will attract the attention of the postman, and notify him that mail has been deposited in the box for collection.

**Transfer of the Bottle Industry.**


There is every indication that the center of the glass-blowing industry has been shifted from the vicinity of Pittsburg, Pa., to Toledo, Ohio. This is a revolution which has been brought about by the general introduction of the bottle-blowing machinery. The Owens Company, which was organized to exploit valuable patents on machinery of this character, and which has its headquarters in the latter city, has, or is about to acquire the rights of its most formidable rivals, and the prospects are that the bottle-blowing industry of this country will be controlled, at an early date, by this company. The Flint Glass Workers' Association, which has for many years been located in Pittsburg, has moved its offices to Toledo. This necessitated the transferral of about \$150,000, the funds of the association which had been deposited with local institutions.

**ORE-SAMPLING MACHINE.**

The richness of mineral ores varies so greatly, that in order to make a correct valuation of a quantity of ore, it is necessary that the sample which is to be assayed should represent an average quality of that entire quantity. This average quality is obtained by means of mechanism, which thoroughly mixes the ore and separates a certain percentage of the material, which passes through it for sample. We illustrate herewith an improved ore-sampling machine, which is the invention of Mr. William L. Raht, of 140 West North Temple Street, Salt Lake City, Utah. Many ad-

**ORE-SAMPLING MACHINE.**

vantages are claimed from this machine. It can be easily inspected and cleaned. It does away with elevators, which are hard to clean and expensive to operate. The correctness of the sample is not jeopardized by slipping of belts, and it does not catch the sample while the ore is dropping. This latter advantage is quite important, as it entirely obviates an objection common to some constructions, in which large pieces properly belonging to the sample, strike the edge of the opening and bound off. Mr. Raht's machine consists of a cylinder, which is mounted in roller bearings at each end. A gear ring is secured to one end of the cylinder, and this is connected by a suitable train of gearing with a power-driven screw conveyer, which passes axially through the center of the cylinder. The gearing is so arranged that the conveyer and the cylinder will rotate in opposite directions. These two movements combine to thoroughly mix the ore as it is fed forward by the conveyer. An opening of any suitable size is cut in the wall of the

**MAIL BOX FOR RURAL FREE DELIVERY ROUTES.**

cylinder at the point near the discharge end. Every time this opening is rotated to its lowest position, the material overlying it drops through as a sample, while the remainder passes on and is discharged at the end of the cylinder. It will be observed that by this construction a certain constant percentage of ore, which depends on the size of the opening, will be constantly delivered as sample. One-half of the cylinder, that in which this opening is formed, is removable to permit of cleaning the interior of the machine. This section can also be replaced whenever desired by another containing a smaller or larger opening, thus affording a simple means for changing the percentage of the ore chosen for sample.



## RECENTLY PATENTED INVENTIONS.

## Electrical Devices.

**ELECTRIC SIGNAL.**—J. E. FELLER, Brooklyn, N. Y. In this case the invention relates to electric signals suitable for general use, and more particularly to a type of instrument in which the person signaled may indicate to the person signaling if the signal is properly received. It may be used in various relations, for instance, to advantage in hotels and in connection with block-signals of railways.

## Household Utilities.

**BED OR CUSHION.**—B. T. MILLIKEN, Ep-person, Ky. The invention relates to sectional beds and cushions to be made up by uniting and combining independent sections. One object is to provide an article so constructed as to allow its parts to be readily united or separated, thereby facilitating handling, repairing, and cleaning, as well as providing for extension or contraction in respect to length as different conditions of use may require. Improved ventilation is secured.

**PLATE-LIFTER.**—G. S. SOLOMON, Bisbee, Arizona Ter. In carrying out this invention, Mr. Solomon has in view the provision of a device exceedingly simple and durable in its construction and very positive in its operation, the device being so made that when the pan is grasped by the lifter such pan cannot turn or fall from the gripping-jaws and thereby spill the contents thereof. It may be adjusted to utensils of various dimensions or size.

## Machines and Mechanical Devices.

**TYPE-WRITING MACHINE.**—F. S. ROSE, Newark, N. J. In this patent the invention refers to improvements in type-writers, in which is sought the production of a construction of the support or carriage for the type-platen or cylindrical roller which enables the same to be folded into compact relation to the keyboard, thus making provision for ready and convenient transportation of the instrument. Means are provided for shifting the platen relatively to the point of impact of the type-faces on the type-levers.

**WOOL BURREING AND PICKING MACHINE.**—G. PROUVOT, Roubaix, Department of Nord, France. This mechanism cleans locks of wool from vegetable burrs, dirt, and other refuse which may be entangled therewith. It combs the locks of wool in order to loosen the fibers or filaments and to bring them into parallel relation, thus opening the locks and spreading out and loosening the fibers, so that they are thoroughly cleaned without unnecessary straining or tearing.

## Metallurgical Improvements.

**ROASTING-FURNACE.**—S. D. CRAIG, G. E. KELLY, and W. TURNER, Laharpe, Kan. In this instance the invention has reference to improvements in ore-roasting furnaces or kilns, and the object of the inventors is to provide a furnace in which ores may be rapidly and thoroughly roasted while being agitated by an automatically controlled device.

## Of General Interest.

**COMBINED SWING AND FAN.**—D. W. BASH, Buda, Ill. The invention relates to a class of swings that are adapted to actuate a fan, and has for its object to provide a device of the class mentioned with novel details of construction which adapt the fan-blast to blow directly upon the occupants of the swing while the latter is in motion. It may be placed indoors for winter use, but more generally employed for exercise and amusement during summer on a lawn for adults and children.

**MONKEY-WRENCH.**—E. A. RENOUF, Wells-ville, Ohio. In the present invention the improvement is in monkey-wrenches, and Mr. Renouf has for an object the provision of novel constructions for securing the movable jaw and for use in adjusting or moving the said jaw along the toothed wrench-bar. The device is simple and easily applied to use.

**ENVELOP.**—P. DAVALOS, Havana, Cuba. The purpose of this improvement is to provide means for facilitating opening envelopes, wrappers, etc., particularly those covers which are used on mail matters. This end Mr. Davalos attains by forming a tearing strip of the material of which the envelop itself is formed, thus not only cheapening the production of the self-opening envelop in cost of material, but also in labor necessary in constructing it.

**NECKWEAR.**—C. BABSON, Gloucester, Mass. The object in this instance is to provide a tip for necktie neckbands which will automatically lock itself in adjusted position, dispensing entirely with the ordinary retaining-pin, and to so construct such a tip that it will be not only simple, durable, and economic, but which may be threaded through the tie in the usual manner, expanding to retain its position the moment it is released in adjustment.

**OPTOMETER.**—W. J. LAUGHLIN, Waunakee, Wis. The object of this invention is to provide an improved optometer arranged to enable the optician to readily adjust the lenses to any desired power, for conveniently and quickly determining the visual powers and the pupillary distance of the eyes of the patient, for the

selection of proper eyeglasses, and for obtaining the height and inclination of the bridge.

**MEAT-PRESS.**—G. FREYSLEBEN, San Diego, Cal. In this patent the invention relates to meat-presses; and it consists in providing a press of this character with hinged sides and ends, detachable corners, and compressing means, all of simple and novel construction. It enjoys special advantage in the facility with which means are adapted, affording free access to the compressed meat.

**FASTENING AND SUSPENSION DEVICE.**—E. M. LEWIS, Moundsville, W. Va. Heretofore when a person decorating desired to use letters, figures, emblems, shields, etc., they had to be made for the occasion. This invention obviates such difficulties by providing a device which may be suitably secured to various articles made of paper, cardboard, cloth, metal, wood, china, glass, celluloid, candy, etc., or from a combination of any of these where-by they may be quickly attached to and removed from various objects, principally for decorative purposes.

**CRACKER-CASE.**—W. T. MAGNESS, Spartanburg, S. C. By this improvement the inventor provides in a case a framing provided with guides in which slide the shelves for supporting cracker-boxes, so the shelves can be adjusted out of the frame to permit access to the boxes and can be adjusted back in their guides to carry the cracker-boxes into the frame when storing the same. In connection with the sliding box-supporting shelves, lock devices secure the shelves in position and jointed links connect the outer ends of the sliding shelves with the casing to aid in guiding the movements of the shelves and to support the same when adjusted to their outer positions.

**POWDER-CONTAINER.**—JEANIE MCC. MCINTYRE, Jersey City, N. J. In this device the required quantity of powder is automatically, mechanically, and accurately measured from the container through an orifice in the container's exterior, in such a manner as to prevent contact of the drawer or any exterior portion of the device with the powder inside of the container. The powder always closes the orifice through which it passes by its own gravity into the exterior movable drawer, thus sealing the interior of the container from all exterior influences and preserving the flavor, fragrance, and freshness of the tooth or similar powder.

**PIPE-COVERING.**—M. SULLIVAN, New York, N. Y. The covering is intended to be applied particularly to joints between pipes which themselves have a non-conducting covering, and comprises a sectional frame arranged to be clamped on the pipe-sections and to inclose the joint or connection, this frame supporting a gauze or foraminated shield which itself carries the asbestos or other compound forming the non-conducting covering.

**SHIRT-WAIST HOLDER AND SKIRT-SUPPORTER.**—A. WILTSEY, New York, N. Y. The purpose in this case is to provide a device adapted to hold a shirt-waist or a dress-waist down and to simultaneously hold the skirt from sagging at the back portion of the waist-band and to so construct the device that it will be capable of convenient and expeditious application and worn without discomfort. The invention improves upon the construction of a similar device for which application for patent was made in a former serial and allowed to Mr. Wiltsey.

**DOOR-SECURER.**—F. E. WIESNER, Washington, D. C. The invention has for an object the provision of a construction which can be easily applied and readily folded when not in use into compact form for carrying in the pocket. The device consists of a shank, with teeth formed thereon, which when the door is closed are forced into the jamb of the door. A cross bar can be slipped through a slot in this shank against the face of the door, thus locking it.

**PARCEL-ATTACHING DEVICE.**—H. F. ROLL, St. Louis, Mo. One of the principal objects of this invention is to devise a retaining means attachable to the person or some part of the clothing and to which device an article, such as an umbrella, is secured, so that if it should happen that the user of the retainer should attempt to leave a car without picking up the parcel he or she would be reminded by a slight jerk or pull from the retainer. It is useful for old and young for holding napkins, scissors, etc., controlling suspenders, and many other operations, but is especially for use by ladies when they go shopping or when riding in street and other cars.

**CLOTHES-LINE HOLDER.**—G. H. DE VINE and A. BAUMANN, Jersey City, N. J. The purpose of the inventors is the provision of a holder capable of being readily placed in position for use and of being operated from the interior of the room when the clothes are placed on the line or are removed therefrom. After clothes have been placed upon the line the device and that portion of the line supported thereby can be swung out from the room and will be held in outer position by the weight of clothes on the line.

**MINER'S TOOL.**—A. V. DES MOINEAUX, Silverplume, Col. This invention relates to a tool for use by miners in preparing a blasting-fuse for service; and the subject-matter of this application is in part a division of a prior one filed by Mr. Des Moineaux. The object is to provide a tool with means for splitting the end of a fuse and with a guide by which the

fuse may be presented properly to the slitting devices and also held firmly in place during the slitting operation.

**WOVEN PILE FABRIC.**—H. SARAFIAN, Yonkers, N. Y. In this case the purpose is to provide a fabric in which the pile is exceedingly close, to give a fine appearance to the finished product, to produce an exceedingly strong and durable weave in which the piles are not liable to become loose or pull out when using the fabric as a rug, for instance, the fabric practically not showing weft or ground warp on either face, but only the pile on the face and the pile-loops on the back.

**HELMET.**—J. J. CURTIS, Jersey City, N. J. As is well known, the helmets ordinarily worn by policemen, firemen, and similar officials are objectionable, especially in warm weather, on account of the weight, and difficulty in ventilating to attain coolness and comfort. Mr. Curtis overcomes these difficulties. He gains an especial advantage in stiffening the brim with aluminium in that the helmet may be made of straw or any light flimsy material, a thing heretofore impossible, on account of the difficulty of stiffening the brim sufficiently.

**NOTE.**—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

## Business and Personal Wants.

**READ THIS COLUMN CAREFULLY.**—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. **In every case it is necessary to give the number of the inquiry.**

MUNN &amp; CO.

Marine Iron Works. Chicago. Catalogue free.

**Inquiry No. 5285.**—For a machine to pick sponges in small pieces without cutting them.

**AUTOS.**—Duryea Power Co., Reading, Pa.

**Inquiry No. 5286.**—For manufacturers of cheap toys and games.

**"U. S." Metal Polish.** Indianapolis. Samples free.

**Inquiry No. 5287.**—For makers of castings for gasoline engines  $\frac{1}{4}$  to 1 h. p., suitable for amateurs' use.

**Handle & Spoke Mch.** Ober Mfg. Co., 10 Bell St., Chagrin Falls, O.

**Inquiry No. 5288.**—For a heavy spring motor with governor to run a light machine.

Sawmill machinery and outfits manufactured by the Lane Mfg. Co., Box 13, Montpelier, Vt.

**Inquiry No. 5289.**—For makers of machinery to make stove pipe.

**Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway New York. Free on application.**

**Inquiry No. 5290.**—For machines for preparing cotton for surgical dressing.

Fine machine work of all kinds. Electrical instruments a specialty. Models built to order. Page Machine Co., 812 Greenwich Street, New York.

**Inquiry No. 5291.**—For machines for making pens and pen holders.

We manufacture anything in metal. Patented articles, metal stamping, dies, screw mach. work, etc., Metal Novelty Works, 43 Canal Street, Chicago.

**Inquiry No. 5292.**—For information regarding cost, etc., of small ice-making machinery, capacity of plant 500 pounds in 5 hours' run.

The largest manufacturer in the world of merry-go-rounds, shooting galleries and hand organs. For prices and terms write to C. W. Parker, Abilene, Kan.

**Inquiry No. 5293.**—For parties engaged in the manufacture and installation of electric light plants.

The celebrated "Hornsby-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 138th Street, New York.

**Inquiry No. 5294.**—For quotations on water motors.

Holtzapfel, screw cutting lathe, plain and complex turning; unequalled inventory of costly apparatus-chucks and tools. F. N. Massa, 84 Warren St., New York.

**Inquiry No. 5295.**—For makers of steel tanks to hold 25 cubic feet to stand 600 pounds' test and high pressure pumps to pump 300 pounds.

Manufacturers of patent articles, dies, metal stamping, screw machine work, hardware specialties, machinery and tools. Quadriga Manufacturing Company, 18 South Canal Street, Chicago.

**Inquiry No. 5296.**—For manufacturers of elevators.

**Inquiry No. 5297.**—Wanted, smooth, bright tin plate for plating purposes, in lots of one to twenty cases at the time direct from an independent mill.

**Inquiry No. 5298.**—For machinery for separating the outer hulls from the bean of the castor oil plant.

**Inquiry No. 5299.**—For manufacturers of smoke consumers.

**Inquiry No. 5300.**—For manufacturers of buckram wire used in manufacturing hat frames.

**Inquiry No. 5301.**—For makers of gasoline or hot air engines of about  $\frac{1}{2}$  h. p.

**Inquiry No. 5302.**—For makers of small steam engine cylinders of the slide valve type of about 13 $\frac{1}{2}$  inches stroke and  $\frac{3}{4}$ -inch bore, either metal or brass.

**Inquiry No. 5303.**—For a machine for printing on lead pencils.

**Inquiry No. 5304.**—For a Taylor calculating machine.

**Inquiry No. 5305.**—For makers of level glasses.

**Inquiry No. 5306.**—For makers of lathes, planers, drill presses, gasoline engine castings and automobile parts.

**Inquiry No. 5307.**—For a machine for imparting power to churn dashers, washing machines, also makers of corn-husking machines operated by hand.

**Inquiry No. 5308.**—For makers of dish-washing machines.

**Inquiry No. 5309.**—For makers of typewriters ranging in prices from \$35 to \$60.


**Inquiry No. 5310.**—For makers of handles for rakes, forks, etc.

**Inquiry No. 5311.**—For a covered automobile carrying 12 to 14 persons.

**Inquiry No. 5312.**—For broom-making machinery.

**Inquiry No. 5313.**—For a small model  $\frac{1}{4}$  h. p. steam engine boiler for demonstrating purposes.

**Inquiry No. 5314.**—For makers of papier maché toys.



## HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.

References to former articles or answers should give date of paper and page or number of question.

Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(9331) F. S. says: Could you give us a remedy for our gas-engine igniter points? Sometimes we try and start our engine as many as ten times before we get an explosion, and all at once it goes off and everything is all right. We blame it on the igniter points; they miss the spark quite often. The make of our engine is a C——— gas engine with electric spark. There seems to be a grease form over the points, and they get black, and then they will not spark; they are nothing but brass points. In order to get a spark again we have to take off the igniter plate and file the points. The batteries are all new. We have tried platinum points, but they break off every time. Sometimes during the day the engine stops itself because we do not get a spark. So if there is a remedy that will keep these points clean, we would like to know. We use gasoline to start our engine, which may be what causes the grease to form, but it won't start with gas. We thought that if we would make two points about  $\frac{1}{8}$  inch thick at one end, and about 3-16 inch at the other, they would make a bigger spark. Our points at present are the same thickness, about  $\frac{1}{8}$  inch thick. A. Gas engine troubles seem to be a frequent cause of complaint of late; principally due to want of knowledge of the true cause of the electric shortcoming by electric short-circuiting, of which absence of cleanliness of insulation and excess of explosive fuel are the main features of the trouble. It is not the cleaning or the filing of the points alone that is the true remedy for these troubles, but rather the thorough cleaning of the insulating surface of the ignition plug, which is the proper place to make the remedy. Grease and carbon from defective combustion deposit on the stationary insulated pole of the plug, and sometimes cause this to become short-circuited. In the event of this happening from the employment of too much lubricating oil or of a bad mixture, the igniter will not work at all until it has been removed and the insulated pole thoroughly cleaned. From your description of the trouble you experience, it would seem, however, as if the trouble were entirely due to the use of improper points. These should be neither of brass nor of platinum, but of the hard platino-iridium alloy that is specially compounded for the purpose. If the points are properly brazed on, there should be no trouble from their falling off.

(9332) J. G. asks: 1. When applied to a slide valve, what is meant by the term lead, and what is accomplished by same? A. The amount of opening for the admission of steam at the beginning of the stroke is called *steam lead*, and the opening for release at the end of the stroke is *exhaust lead*. The amount of the opening at dead crank center varies in ordinary engines from 1-64 to  $\frac{1}{8}$  inch valve lead, and may be as much as  $\frac{1}{4}$  to  $\frac{3}{8}$  inch in special designs of valve movement. The effect is a steam compression equal to the boiler pressure at the moment of change of motion of the piston. It neutralizes the strains and effects a smoother running of the engine. 2. What is meant by the term lap, and what is accomplished by same? A. The outside lap, called the *steam lap*, is the distance the steam edge of the valve extends beyond the edge of the port when the valve is in its central position. The inside lap, called the *exhaust lap*, is the distance the valve extends or laps over the exhaust port when the valve is in its central position. The effect of outside lap is a later admission and an earlier cut-off with longer expansion. The effect of inside lap is to make the exhaust occur later and to close earlier with a longer compression. The effect of all the lead and lap combinations is for the smooth running of a steam engine, its freedom from shock or strain, and for the greatest economy in the use of steam for power. 3. What is meant by cutting off steam before piston has traveled its full stroke, and what is accomplished by same? A. The cut-off in a steam engine is the technical expression as to the point in the stroke at which the steam inlet is closed and expansion commences. By this means the power of a given volume of steam is largely increased by utilizing the decreasing pressure due to its expansion during the remainder of the stroke from the point of cut-

off, so that from the most economical points of cut-off, which for an ordinary engine may be from 15 to 30 per cent of the stroke, a saving of from 25 to 50 per cent of the power value of the steam may be made.

(9333) A. C. A. writes: In regard to note 9316, A. F. S., page 164, I think a reason why lightning is so seldom seen in winter is because the condensation is never so rapid as in summer. His own observation shows that the harder the shower, the greater display of lightning. Now to my mind the electricity is produced in the cloud in the same manner as the rain-drop, by cohesion of electrical particles in the warm air that was carried up into the colder upper air, where the condensation takes place. Now, if the rain-drop was formed by cohesion of water particles until it becomes heavy enough to fall by gravitation to the earth, why not the other? There is rain without lightning, but never lightning without rain, thus showing that lightning is the result of rapid condensation, and rain not the result of lightning, as if the electric discharge started from the top of the cloud at the same time as a drop of water, it would reach the earth first, as it travels faster. The greatest display of lightning I have ever seen was in June, 1889, when nearly ten inches of rain fell from 1.40 to 2.20 P. M., forty minutes. This was a local shower, did not rain over two miles away from my point of observation in any direction, and I think I was in the center of it. There was no wind. The cloud did not move away, but just rained down until there was only a haze left. Even this remained full five hours after the rain ceased. This cloud could not have been electrified by induction from any other, for there was none other; clear sky all about. I observed the cloud at 11.30 A. M. directly overhead, and at 12.30 P. M. it had got quite black and was larger than when first noticed. At 1 o'clock my man and I went to work in a field, half a mile from house. I told the man we were going to get wet from that cloud overhead, and we did. There were about twenty flashes of lightning before any rain reached the ground, and they were close, not over ten seconds apart. When the rain began we started for shelter, but lost all sense of direction, as the rain was so thick we could not see, and but for the lightning flashes it would have been dark as night, but the flashes were almost continuous. The rain fell straight down, no wind to drive it. I do not take any stock in the idea of electric generation by friction between two clouds, nor by friction between cloud and air currents, because the clouds do not rub each other, any more than the exhaust steam from one locomotive rubs with that of another; they mingle and become one, the instant the two engines are side by side. The cloud goes with the current of air; is not steered like a ship, in some other direction. I have never seen any one who held the same idea as myself in regard to the formation of the electricity in the clouds, and I have asked many. Also have asked people to tell me as nearly as they could the size of a streak of lightning. I saw one strike a stump at least 30 inches in diameter, and the bright streak was broader than the stump. I was about 100 feet away, and looking at the stump at the time. Another time I saw one hit a barn a mile away, and the streak was as broad as a chimney on the house beside the barn, and the chimney was 26 inches wide. I could see the streak and chimney both at the same time; the barn showed fire in half a minute. I saw one streak hit my wood pile, and it looked as large as a  $\frac{3}{8}$ -inch rod, and snapped like a gun cap, while there was a big crash on the opposite side of the house from me half a second later. This was a sliver from the main discharge, as I have frequently seen a flash divide into several small ones, and one when not over 100 feet from the ground, and the parts went away horizontally, while the main body was vertical. I have always watched the lightning whenever I could, and have seen some queer antics of it. A. The theory of our esteemed correspondent does not reach to the point of explaining the origin of the electricity of the atmosphere. It begins with electricity already present in the atmosphere. There is no difficulty in accounting for the rise of intensity of electrification in the thunder storm. The fact that the air is always in fair and stormy weather alike charged with electricity is more difficult to account for. We cannot follow him in the measure of the diameter of a flash of lightning. The great enlargement of a bright line of light in comparison with its real size by irradiation prevents the testimony of the eye from having much value in the case. The account of the cloudburst, as such heavy showers are commonly but erroneously called, is very interesting.

(9334) W. A. H. and others ask: Please tell me the difference between non-luminous radium and radium (luminous). I refer to the article in your paper of January 2, namely: "A Home-Made Spintaroscope." Also, how can purple stains be removed from type-keys? A. Non-luminous radium is radium of so low a potency or purity as to give no light of itself, which can be perceived even after long effort in the deepest darkness. When a mixture of such radium and pulverized willenite is examined in the dark, it is found to be luminous. The willenite is caused to glow by the radium, which does not of itself glow. This is what is meant by the home-made spin-

tariscope. Prices quoted on chemicals a few weeks ago cannot be relied upon now, since these substances are rising very rapidly in market value. Purple stains can be removed from type-keys with alcohol if the stains are aniline.

#### NEW BOOKS, ETC.

CASSELL'S POPULAR SCIENCE. Vol. I. Edited by Alexander S. Galt. Illustrated. London, Paris, New York, and Melbourne. 1903. Square 8vo.

The book which lies before us comprises a series of articles well illustrated, and for the most part excellently written, describing in simple, terse language the scientific causes of the phenomena which play an important part in our daily lives. "How the Camera Works," "Meteors," "The Wizard Electricity," "A Piece of Sponge," "How and Why a Stone Falls," "Time Told by the Sun," "What is Radium?" are a few of the more suggestive titles of these articles. Since this is but the first volume, it is hardly fair to call attention to several topics which, in our opinion, should have been discussed, since they may find a place in subsequent volumes. Among these topics we may, however, be permitted to suggest those of "Bessemer Steel," "Aerial Navigation," "the Telephone," and the "Steam Engine." The subjects which are treated in this volume, however, cover a very wide range. They include astronomy, natural history, chemistry, electricity, anatomy, and geology. Each article, so far as we have been able to judge, gives a very comprehensive view of the particular subject which it discusses. The book shows what can be done in the way of treating science popularly and yet accurately.

GENERAL ZOOLOGY. Practical, Systematic, and Comparative. Being a Revision and Rearrangement of Orton's Comparative Zoology. New York: American Book Company. N. D. 12mo. Pp. 512. Price \$1.80.

The present textbook is suited to the needs of the general student, who wishes to learn the principal facts and theories of zoology, and thus to obtain a fairly comprehensive idea of the science. To this end it has seemed desirable to arrange a course of study, so that the student may gain by personal observation a concrete knowledge of the structure and activities of animals, and by so doing acquire some familiarity with the method of zoological investigation, so that he may also obtain a knowledge of the relationships of animals as expressed in an accepted scheme of classification. The laboratory exercises are well arranged, and the book is illustrated by 379 engravings, many of which are from life. We note particularly an excellent photograph of a beaver at work.

DIAGRAMMES ET SURFACES THERMODYNAMIQUES. Par J. W. Gibbs. Traduction de M. G. Roy, Chef des Travaux de Physique à l'Université de Dijon. Avec une introduction de M. B. Brunhes, Professor à l'Université de Clermont. Série Physico-Mathématique Scientia. Paris: C. Naud, éditeur. 1903. Pp. 100.

The influence exercised on contemporary chemistry by the ideas of Prof. Gibbs has constantly increased; and yet, even in its original English form, his work on thermodynamics remains comparatively inaccessible. The monograph before us is a French translation of two treatises on the geometrical representation of thermo-dynamic phenomena by means of diagrams and surfaces. The ideas of Prof. Gibbs have inspired many an interesting experiment for detecting the reactions which occur in thermic motors, by means of diagrams other than the exact figures of Clapenyrion. The present work will doubtless find in France fully as welcome a reception as the original met with in English-speaking countries.

TABLES AND OTHER DATA FOR ENGINEERS AND BUSINESS MEN. Compiled by F. E. Ferris, D.S. Nashville, Tenn.: University Press. 24mo. Pp. 152. Price 50 cents.

An excellent little pocketbook adapted for the vest pocket. The tables are unusually well selected.

AMERICAN HAND BOOK OF THE BREWING, MALTING, AND AUXILIARY TRADES. A Book of Ready Reference for Persons Connected with the Brewing, Malting, and Auxiliary Trades. Together with Tables, Formulas, Calculations, Bibliography, and Dictionary of Technical Terms. By Robert Wahl, Ph.D., and Max Henius, Ph.D. Second Edition. Chicago: W. C. Keener & Co. 1902. 16mo. Pp. 1,266. Price \$10.

If ever a reference book represented original work, this does. Its editors had no precedent whatever to guide them. To be sure, there are books on bottom fermentation brewing as practised on the continent of Europe; but these are in German. There are books on top fermentation brewing as practised in Great Britain. But even if all these books were available to the American brewer, they would not fulfill his requirements, for the reason that he employs neither of the two systems mentioned exclusively. The American brewing industry is a thing apart. It was for the purpose of fulfilling American requirements that the present handbook was written. From an examination

of its contents we are convinced that the work is all that its authors desired it to be. They have been decidedly successful in preparing a book of ready reference which the brewing, malting, and auxiliary trades will find useful.

MANUAL OF SCREW CUTTING. By William Simpson. Wollaston, Mass.: Published by the Author. 18mo. Pp. 72. Price 40 cents.

This little manual deals with screws, screw cutting, and other mechanical powers. It will prove useful to all mechanics.

GRAPHIC STATICS. With Applications to Trusses, Beams, and Arches. By Jerome Sondericker, B.S., C.E. New York: John Wiley & Sons. 1903. 8vo. Pp. 137, three folding plates. Price \$2.

This book is the outgrowth of an extended experience in teaching graphic statics at the Massachusetts Institute of Technology. While it deals specifically with problems encountered in building construction, it should be found serviceable to engineers and engineering students generally. As a preparation the reader should have a knowledge of statics and the strength of materials, including beam stresses and deflections, as these subjects are commonly presented. The whole matter of graphic statics is a most important one in view of our modern system of building construction, and the book before us is a most thorough and excellent treatise on the subject.

WATER SUPPLY. A Student's Handbook on the Conditions Governing the Selection of Sources and the Distribution of Water. By Reginald E. Middleton. London: Charles Griffin & Co., Ltd. Philadelphia: J. B. Lippincott Company. 1903. 8vo. Pp. 168.

This is an excellent book for engineering students, as it sets forth in a compact manner the general scientific principles on which the subject is based, and serving as an introduction to larger and more technical works. Special prominence has, therefore, been given to such questions as the quality of the water, the interpretation of analyses, the stability of masonry dams, flow of water through the pipes, and the general application of mathematics to the subject. The book will prove of interest to those for whom it was written, even though some of the practice may be at variance with that of our own country. The formulas and diagrams are particularly to be commended.

THE SUGAR CANE IN EGYPT. By Walter Tiemann. Altrincham, near Manchester, England: International Sugar Journal. 1903. 16mo. Pp. 75, 16 plates. Price \$2.

The British occupation of Egypt, which dates from 1882, has been followed by remarkable progress, as the wonderful development of the agricultural interests bear witness. While the technical and mechanical conditions in the factories of the colonial sugar industry have made great strides in progress, the *materia prima*, the sugar cane itself, has in most countries remained subject to the old primitive methods of culture. The object of the present work is to outline the present methods, and to show how improvements can be made. The book contains some interesting field experiments.

THE LOCALIZATION OF FAULTS IN ELECTRIC LIGHT AND POWER MAINS. By F. Charles Raphael. London: The Electrician Printing and Publishing Company, Ltd. New York: D. Van Nostrand Company. N. D. 8vo. Pp. 205. Price \$3 net.

The subject of the localization of faults in electric mains is a most important one, and it appears to have been a rather neglected part of electrical engineering. Methods are constantly changing, and the very latest are described in this second and revised edition. The author justly says that since the publication of the first edition, considerable progress has been made in the art of cable making and cable laying, and increased practice and experience have led to a nearer approach to perfection. This book should be in the hands of all practical electrical engineers.

ACETYLENE GAS. How to Make and Use It. By Cyril N. Turner. London: Percival Marshall & Co. N. D. 18mo. Pp. 62. Price 20 cents.

The author states that the inventor of the process was either an American, Willson, or Henri Moissan, the celebrated French chemist. We have never heard Mr. Willson's claim to the invention disputed. He certainly has everything very tangible in the patent line. This little book will prove of interest to amateurs.

GENERAL DATA ON THOMSON RECORDING WATTMETERS. Schenectady, N. Y.: General Electric Company. 1903. 16mo. Pp. 217.

All who are interested in selling current will be glad of the present volume. It is filled with tables and diagrams.

THE TECHNOLOGY OF SUGAR. By John Geddes McIntosh. London: Scott, Greenwood & Co. New York: D. Van Nostrand Company. 1903. 8vo. Pp. 408. Price \$4.50.

The British and Colonial sugar industry has been on the wane. Obsolete machinery and methods contributed much to the decadence of

the industry. It has, therefore, been the aim of the author to show the most modern methods employed in this industry. There are a large number of books on sugar making, but there is ample room for the present book, which deals with the classification of sugar, beet sugar, cane sugar, sugar refining, and the selection of sugars. All who are in any way identified with the sugar industry should have a copy of this book.

THE HOME MECHANIC. By John Wright. New York: E. P. Dutton & Co. 1903. 8vo. Pp. 435. Price \$3.50 net.

The present work deals with carpentry, metal work, repairs, steam engines, and similar subjects. The practice is English, but for that reason it would prove more useful to American readers. Still, however, it is thoroughly practical, and will prove to be a very useful book in the amateur's library.

A QUARTERLY ISSUE OF SMITHSONIAN MISCELLANEOUS COLLECTIONS.

The Smithsonian Institution has commenced the publication of a Quarterly Issue of its Miscellaneous Collections, "designed chiefly to afford a medium for the early publication of the results of researches conducted by the Smithsonian Institution and its bureaus, and especially for the publication of reports of a preliminary nature." The first number of the Quarterly Issue is a double one, and contains seventeen articles, ranging in size from 1 page to 73 pages, in addition to interesting and timely notes on the activities of the Institution, its collections, etc., the whole accompanied with fifty-six plates and numerous text figures.

The scope of the journal is broad, the first issue embodying articles on Mammalogy, Astrophysics, Paleontology, Archeology, Geology, Ornithology, Ichthyology, Ethnology, etc., thus covering a considerable range of scientific subjects.

## INDEX OF INVENTIONS

For which Letters Patent of the  
United States were Issued  
for the Week Ending  
March 15, 1904.

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

|                                                                                                   |         |
|---------------------------------------------------------------------------------------------------|---------|
| Adding-machine, W. H. Clark.....                                                                  | 754,544 |
| Adjustable wrench, Bordewisch & Wovries..                                                         | 754,740 |
| Air-braking systems, audible alarm for, J. H. Clark.....                                          | 754,847 |
| Air-heater, J. Watrous.....                                                                       | 754,726 |
| Air or other gaseous bodies, compressor for, H. C. Sergeant.....                                  | 754,901 |
| Aluminum sulfate, making, H. Spence.....                                                          | 754,824 |
| Ammonium nitrate, making, W. Mills.....                                                           | 754,668 |
| Amusement apparatus, W. S. Reed.....                                                              | 754,698 |
| Antiseptic telephone-mouthpiece, English & Ten Broeck.....                                        | 754,646 |
| Apparel, wearing, L. S. Althemer.....                                                             | 754,734 |
| Automobile lifting-truck, W. S. Kessler.....                                                      | 754,571 |
| Back-rest, folding, B. B. Billmeyer.....                                                          | 754,536 |
| Bag-holder, Madden & Thompson.....                                                                | 754,580 |
| Bale or package cover, I. Schlichter.....                                                         | 754,811 |
| Baling-press, T. P. Ormond.....                                                                   | 754,493 |
| Baling-press door-closer, E. Davis.....                                                           | 754,553 |
| Band-fastener, F. Sedlmair.....                                                                   | 754,714 |
| Barrel, F. E. Gage.....                                                                           | 754,923 |
| Battery. See galvanic battery.....                                                                |         |
| Battery tray, storage, T. A. Edison.....                                                          | 754,858 |
| Beams, securing strips of wood, etc., to iron, S. Davis.....                                      | 754,855 |
| Bearing, ball, T. H. Duncombe.....                                                                | 754,436 |
| Bearing, conical roller, J. P. Cowing.....                                                        | 754,751 |
| Bedclothes-holder, H. Crocker.....                                                                | 754,430 |
| Bedstead attachment, A. B. Shane.....                                                             | 754,615 |
| Beet-blocking machine, A. R. Mundt.....                                                           | 754,682 |
| Belt-fastener, I. Jackson.....                                                                    | 754,567 |
| Bib or faucet, C. Peck.....                                                                       | 754,889 |
| Bicycle, C. N. Stilson.....                                                                       | 754,720 |
| Bicycle-gearing, H. F. Maynes.....                                                                | 754,587 |
| Bicycle-gearing, Thompson & Maynes.....                                                           | 754,621 |
| Binder and file for pamphlets, books, ledgers, etc., F. B. Whitney.....                           | 754,628 |
| Binder, loose-leaf, J. L. Hanson.....                                                             | 754,766 |
| Binder, temporary, J. P. Mentzer.....                                                             | 754,791 |
| Bird-cage, J. A. Quelch.....                                                                      | 754,806 |
| Blasting charges, machine for preparing, F. J. Trayssac.....                                      | 754,830 |
| Bolt-screw catcher, S. V. Ivey.....                                                               | 754,873 |
| Bolt. See Expansion bolt.....                                                                     |         |
| Bolting-sieve cleaner, C. A. Shultz.....                                                          | 754,821 |
| Bottle-filling apparatus, J. Anderson.....                                                        | 754,951 |
| Bottle-filling machine, E. H. Parker.....                                                         | 754,602 |
| Bottle-stopper, non-refillable, J. G. Reddick.....                                                | 754,007 |
| Bottles, stopper for preventing refilling, G. B. Okey.....                                        | 754,685 |
| Bowling-alley, portable, F. Kary.....                                                             | 754,456 |
| Brake-beam, A. Lipschutz.....                                                                     | 754,785 |
| Brake-shoe, J. D. Gallagher.....                                                                  | 754,440 |
| Brake-shoe and producing same, C. G. Ette.....                                                    | 754,921 |
| Brake-shoe holder, A. M. Pemock.....                                                              | 754,604 |
| Branding implement, oil-burning, G. Fuller.....                                                   | 754,862 |
| Breastpin safety-catch, J. C. Nordt.....                                                          | 754,794 |
| Bridge and tailpiece, combination, E. Reach.....                                                  | 754,938 |
| Buckle, A. Addington.....                                                                         | 754,705 |
| Buckle, A. Addington.....                                                                         | 754,731 |
| Building, etc., blocks, apparatus for making, J. Brower.....                                      | 754,639 |
| Building, etc., blocks, making, J. Brower.....                                                    | 754,640 |
| Burglar-alarm, N. A. Lyle.....                                                                    | 754,470 |
| Bushing, G. & J. Strehl.....                                                                      | 754,512 |
| Butter-separator, J. Meyrick, Jr.....                                                             | 754,931 |
| Button and tie, collar, H. L. Blais.....                                                          | 754,842 |
| Cabinet, kitchen, C. F. Kade.....                                                                 | 754,870 |
| Cable-clip, J. McFarlane.....                                                                     | 754,884 |
| Cake-trimming machine, layer, C. F. Dietz.....                                                    | 754,548 |
| Calculating and recording machine, C. D. Baird.....                                               | 754,836 |
| Calendars and similar sheets, machine for bordering, J. F. Ross.....                              | 754,941 |
| Can-fluxing apparatus, J. G. & M. O. Rehffuss.....                                                | 754,702 |
| Can-making machine, J. G. & M. O. Rehffuss.....                                                   | 754,940 |
| Can tops and bottoms from forming-dies, pneumatic means for removing, J. G. & M. O. Rehffuss..... | 754,704 |
| Cans, machine for putting tops and bottoms on, J. G. & M. O. Rehffuss.....                        | 754,700 |
| Cans preparatory to being fluxed and soldered, apparatus for heating, J. G. & M. O. Rehffuss..... | 754,703 |
| Car-brake, H. E. & M. L. Brown.....                                                               | 754,419 |
| Car-brake, emergency, S. A. Duvall.....                                                           | 754,551 |
| Car-brake-operating mechanism, J. L. Peacock.....                                                 | 754,603 |
| Car brake, passenger, M. Tolitz.....                                                              | 754,829 |
| Car-coupling, W. F. Richards.....                                                                 | 754,706 |
| Car-coupling attachment, railway, W. Thornburgh.....                                              | 754,942 |
| Car discharging device, dump, Seaver & Huett.....                                                 | 754,809 |
| Car, dump, O. W. Meissner.....                                                                    | 754,475 |

(Continued on page 260)



# POPE MANUFACTURING COMPANY.



The renaissance of bicycling brings with it one of the finest mechanical devices invented since the beginning of this industry.

## THE TWO-SPEED GEAR CHAINLESS BICYCLE

Enables the rider, by a slight pressure of foot on pedal, to change from high to low gear for hill climbing and difficult roads.

Eastern Department, Hartford, Conn.

"Columbia" "Cleveland" "Tribune"  
"Crawford" "Fay Juveniles"

Western Department, Chicago, Ill.

"Crescent" "Rambler" "Monarch"  
"Imperial" "Crescent Juveniles"

Catalogues free at our 10,000 dealers' stores, or any one Catalogue mailed on receipt of a two-cent stamp.

**"Star" Lathes**  
Foot and Power  
Screw Cutting  
Automatic  
Cross Feed  
FOR FINE, ACCURATE WORK  
Send for Catalogue B.  
**SENECA FALLS MFG. CO.**  
695 Water Street,  
Seneca Falls, N. Y., U. S. A.

**Foot and Power and Turret Lathes, Planers, Shapers, and Drill Presses.**  
**SHEPARD LATHE CO.,** 133 W. 2d St., Cincinnati, O.

**ENGINE & FOOT LATHES**  
**MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES**  
SEBASTIAN LATHE CO. CINCINNATI, O.  
20 CUMMINS ST.

**It's the Hide That Counts**  
in the life of a belt. If it's carefully selected and well tanned and then made into such belting as  
**Schieren Belting**  
the result will be satisfactory to the end and the "end" will be many years distant. Our Dixie Belt Leather Book explains everything. Send for it.  
**CHAS. A. SCHIEREN & CO.**  
NEW YORK: 52 Ferry St.  
CHICAGO: 92 Franklin St.  
BOSTON: 192 Lincoln St.  
PITTSBURGH: 243 Third Av.  
PHILADELPHIA: 228 N. Third St.  
DENVER: 1519 Sixteenth St.  
HAMBURG: Pickhagen 4.

**GIANT STEAM SHOVELS**  
Toledo Ohio, U.S.A.  
**The Vulcan Iron Works Co.**

**THE NICKEL PLATE ROAD AGAIN SELLING LOW RATE COLONIST TICKETS TO THE PACIFIC COAST.**

Tickets on sale every day, March 1 to April 30, at rate of \$42.50. These tickets are good on our trans-continental tourist sleepers and via any route desired beyond Chicago. For full particulars see local agents, or write H. R. Payne, General Agent, 201 Main Street, Buffalo, N. Y., or A. W. Ecclestone, D. P. A., 385 Broadway, New York.

**Packard**  
Four-Cylinder.  
Model "L" 1904  
Actual 22 horsepower, with only 85 lbs. loaded weight to each horsepower. Speed range of 4 to 40 miles per hour. Anti-friction ball bearing axles, direct drive, mechanical valves for intake and exhaust. Winner of highest prizes for BOTH speed and endurance wherever entered.  
**\$3,000.**  
Send for illustrated descriptive literature and name of nearest agent.  
**PACKARD MOTOR CAR CO.,** Dept. 5, Detroit, Mich.  
Member Association of Licensed Automobile Manufacturers.  
New York Agents: PACKARD Motor Car Co., OF N. Y., 317-319 W. 59th St., New York City.

**NOISELESS Bevel Pinions**  
We can furnish our New Process Noiseless Pinions in bevels as well as spurs of any size wanted and to transmit any required horse power. Write for catalogue.  
**THE NEW PROCESS RAWHIDE CO.**  
Syracuse, N. Y.

**The OLDS GAS and OIL ENGINES.**  
The safest engine in the world. When gasoline is used the supply can only be pumped up as it is used, and it cannot mix with it until it reaches the mixer. Scott's engines 2 to 100 H. P. Portable engines 8 to 25 H. P. Write for full information and illustrated catalogue.  
**Olds Gasoline Engine Works, 216 River St., Lansing, Mich.**

**A.W. FABER**  
Manufactory Established 1761.  
LEAD PENCILS, COLORED PENCILS, SLATE PENCILS, WRITING SLATES, INKS, STATIONERS RUBBER GOODS, RULERS, ARTISTS' COLORS.  
**78 Reade Street, New York, N. Y.**  
GRAND PRIZE, Highest Award, PARIS, 1900.

**ARTESIAN**  
Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 5000 feet. We also manufacture and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 100 to 1200 feet. Write us stating exactly what is required and send for illustrated catalogue. Address  
**PIERCE WELL ENGINEERING AND SUPPLY CO.**  
136 LIBERTY STREET, NEW YORK, U. S. A.

**INDIAN MOTOCYCLE**  
**HENDEE MFG. CO.**  
Get our 1904 catalog. **SPRINGFIELD, MASS.**

|                                                                             |         |         |
|-----------------------------------------------------------------------------|---------|---------|
| Car friction draft-gear, railway, T. C. McKee                               | 754,593 | 754,594 |
| Car friction draft-gear, railway, P. N. Moore                               | 754,674 | 754,932 |
| Car friction draft-rigging, railway, W. H. Miner                            | 754,670 |         |
| Car friction draft-rigging, railway, P. N. Moore                            | 754,675 |         |
| Car friction spring draft-gear, railway, P. N. Moore                        | 754,677 |         |
| Car friction spring draft-rigging, railway, P. N. Moore                     | 754,678 |         |
| Car platform, N. Paulson                                                    | 754,688 |         |
| Car-replacer, E. Best                                                       | 754,915 |         |
| Car, steel, P. Wagner                                                       | 754,725 |         |
| Car track-brake, J. A. Brader                                               | 754,844 |         |
| Car-window sash-lifter, A. R. Bell                                          | 754,634 |         |
| Cars, megaphone attachment for passenger, W. H. Brunt                       | 754,918 |         |
| Cars, tandem friction spring draft-rigging for railway, P. N. Moore         | 754,676 |         |
| Carburetor, F. Jas.                                                         | 754,774 |         |
| Carding-machine attachment, Taylor & Scott                                  | 754,514 |         |
| Carding-machine feeding mechanism, P. L. McBride                            | 754,484 |         |
| Carpet-beating machine, C. P. Carey                                         | 754,540 |         |
| Carriages, automatic brake-shoe for baby, J. F. Snyder                      | 754,510 |         |
| Carrier, See Mail-carrier.                                                  |         |         |
| Case, G. A. Schwanbeck                                                      | 754,957 |         |
| Cash-carrier apparatus, Chamberlain & Chism                                 | 754,422 |         |
| Cash-carrier apparatus, D. E. Chism                                         | 754,424 |         |
| Cash-carrier box, D. E. Chism                                               | 754,423 |         |
| Casing-turner, W. Nesbitt                                                   | 754,597 |         |
| Cask bush or liner and means for attaching same, Ross & MacKenzie           | 754,708 |         |
| Catapult, L. G. Clark                                                       | 754,745 |         |
| Centrifugal machine, J. H. Ostrander                                        | 754,736 |         |
| Chalking device, H. F. M. Thompson                                          | 754,827 |         |
| Chart, dioptrical, W. W. Martin                                             | 754,663 |         |
| Churn, J. D. Metcalf                                                        | 754,882 |         |
| Circuit-breaker, automatic, W. M. Scott                                     | 754,505 |         |
| Cistern-top, S. Pomroy                                                      | 754,801 |         |
| Clasp, Charron & Girardot                                                   | 754,919 |         |
| Clock, astronomical, J. C. Burke                                            | 754,845 |         |
| Clock, electric, D. W. Thompson                                             | 754,622 |         |
| Cloth-holding device, E. Gessner                                            | 754,649 |         |
| Clothes-pouder, V. T. E. W. Lynch                                           | 754,879 |         |
| Clutch mechanism, C. F. Thoms                                               | 754,828 |         |
| Clutch mechanism, friction, S. J. Davis                                     | 754,644 |         |
| Clutch, speed-regulating magnetic, C. A. Pratt                              | 754,804 |         |
| Coal-elevator, J. Deady, Jr.                                                | 754,546 |         |
| Cock, stop and waste, J. M. Teahen                                          | 754,515 |         |
| Coffee, roasting, T. R. Timby                                               | 754,943 |         |
| Coffin, J. J. Schneider                                                     | 754,712 |         |
| Coin-controlled machine, automatic register, Ellis & Powell                 | 754,553 |         |
| Cold-storage apparatus, M. Cooper                                           | 754,749 |         |
| Compressing-dies, T. A. Edison                                              | 754,755 |         |
| Concrete-construction mold, metal, C. Weber                                 | 754,626 |         |
| Concrete, etc., machine for mixing, J. E. Kenisell                          | 754,927 |         |
| Conduit outlet-box, interior, W. F. Bossert                                 | 754,414 |         |
| Connecting-rod or pitman, C. H. Howland                                     |         |         |
| Cooking-utensil support, J. W. Marshall                                     | 754,653 |         |
| Cop-holder, K. R. Williams                                                  | 754,526 |         |
| Corn-shock loader, E. T. Maxwell                                            | 754,585 |         |
| Cotton-chopper, T. J. Lowry                                                 | 754,787 |         |
| Couch-spring, E. A. Anderson                                                | 754,835 |         |
| Coupling, See Car-coupling.                                                 |         |         |
| Crate, banana, J. A. Hadley                                                 | 754,444 |         |
| Cream-roll-forming machine, C. F. Dietz                                     | 754,549 |         |
| Cross-tie, metallic, C. W. Platt                                            | 754,693 |         |
| Curtain and shade holder, window, H. T. Andrew                              | 754,531 |         |
| Curtain-pole, D. Brehm                                                      | 754,554 |         |
| Cyanides and nitrates, making, W. E. Everette                               | 754,917 |         |
| Cycle, automatic coasting, E. A. Smith                                      | 754,647 |         |
| Damper mechanism, time, W. Hartzell                                         | 754,823 |         |
| Dark room, portable, W. H. Levey                                            | 754,446 |         |
| Digging and loading machine, D. McDonald                                    | 754,659 |         |
| Dividers, for drawing figures on rolls, mechanism for walking, P. Fuchs     | 754,592 |         |
| Dolls or other toy figures on rolls, mechanism for walking, P. Fuchs        | 754,906 |         |
| Domestic boiler, S. C. Shoup                                                | 754,861 |         |
| Door check and closer, J. A. Young                                          | 754,717 |         |
| Door check and closer, W. Pelzer                                            | 754,629 |         |
| Door or like frame, E. Ohnstrand                                            | 754,690 |         |
| Draft-rigging, Williamson & Pries                                           | 754,527 |         |
| Draft-rigging, W. Thornburgh                                                | 754,958 |         |
| Draft-rigging, tandem-spring, W. H. Miner                                   | 754,669 |         |
| Draft-rigging, tandem-spring friction, W. H. Miner                          | 754,671 |         |
| Drafting implement, H. A. Swenson                                           | 754,513 |         |
| Dredging and sluicing device, submarine, R. G. Riley                        | 754,611 |         |
| Dress-shield, Lee & Conkling                                                | 754,877 |         |
| Drier-rack, A. J. Zilker, et al.                                            | 754,530 |         |
| Drill-bits, etc., fastening device for, C. P. Brintzinger                   | 754,741 |         |
| Drill or pump rod grapple, J. Luke                                          | 754,579 |         |
| Dye, red-violet azo, A. Dorrer                                              | 754,856 |         |
| Dyes, making anthraquinone, Hepp & Wolpert                                  | 754,768 |         |
| Easel, J. Weber                                                             | 754,945 |         |
| Electric-circuit-limiting device, C. W. Potter                              | 754,496 |         |
| Electric furnace, C. A. Keller                                              | 754,656 |         |
| Electric-socket support, E. R. Gill                                         | 754,762 |         |
| Electric time-alarm, E. M. Benesch                                          | 754,410 |         |
| Electrical-distribution means, J. L. Creveling                              | 754,429 |         |
| Electrical plug and receptacle, G. W. Goodridge                             | 754,863 |         |
| Electrical selective apparatus, Peame & Krum                                | 754,689 |         |
| Electromagnetic device, E. K. Muller                                        | 754,681 |         |
| Elevator safety appliance, Cruickshank & Burnham                            | 754,432 |         |
| Engine, C. F. Chandler                                                      | 754,744 |         |
| Engine cooling device, explosive, J. White                                  | 754,728 |         |
| Envelope or card feeding device, D. S. Dufur                                | 754,434 |         |
| Excavator, backhoe, Selth & Kaphingst                                       | 754,900 |         |
| Excavating-machine, J. D. Moran                                             | 754,480 |         |
| Expansion-bolt, J. B. Gottshalk                                             | 754,764 |         |
| Explosive-engine, S. S. and A. Lewis                                        | 754,466 |         |
| Extensible case, E. G. Schriefer                                            | 754,814 |         |
| Fabrics, finishing, H. Bock                                                 | 754,843 |         |
| Farm-gate, C. P. Emery                                                      | 754,758 |         |
| Feed-bag, horse, J. Ratzer                                                  | 754,696 |         |
| Feed-water purifier, J. M. Smith                                            | 754,907 |         |
| Felt-spreader, J. H. Ostrander                                              | 754,797 |         |
| Fertilizer-distributor, M. L. Baker                                         | 754,408 |         |
| Finger-nail buffer, C. E. Moser                                             | 754,481 |         |
| Fire-alarm, automatic, M. K. Fred                                           | 754,555 |         |
| Fire and water proof insulating-covering for metallic surfaces, J. A. Heany | 754,868 |         |
| Firearm safety device, G. A. Horne                                          | 754,564 |         |
| Fireproof construction, G. Lieban                                           | 754,783 |         |
| Fireproof floor construction, R. C. Kyle                                    | 754,574 |         |
| Fireproof window frame and sash, I. W. Emerson                              | 754,437 |         |
| Fishing-tackle, S. Robbins                                                  | 754,892 |         |
| Flash-light apparatus, photographic, McColl & Klalber                       | 754,487 |         |
| Flexible tube, S. Palmer                                                    | 754,936 |         |
| Flooring, roofing, etc., structural arrangement applicable to, E. L. Pease  | 754,888 |         |
| Flue-cleaners, rotary motor for, A. Lemke                                   | 754,955 |         |
| Fluid-pressure brake, Spencer & Greiner                                     | 754,908 |         |
| Freezing-tank, C. W. Vollmann                                               | 754,522 |         |
| Furnace, See Electric furnace.                                              |         |         |
| Furnace, D. J. McKenzie                                                     | 754,792 |         |
| Furnace for burning tan or like fuel, D. M. Myers                           | 754,933 |         |
| Fusion, treating matters in, P. L. Hullin                                   | 754,566 |         |
| Galvanic battery, reversible, T. A. Edison                                  | 754,859 |         |
| Garbage-removing device, E. O. Poppe                                        | 754,890 |         |
| Garment-clasp, A. J. Krienitz                                               | 754,462 |         |
| Garment-stretcher, J. B. Miller                                             | 754,478 |         |
| Garment-supporter, L. B. Schoch                                             | 754,813 |         |
| Gas and coke, retort for making, A. C. Kio-man                              | 754,459 |         |
| Gas-burner, atmospheric, A. E. Harris                                       | 754,561 |         |
| Gas-burner, regenerative, J. W. McKnight                                    | 754,595 |         |
| Gas-detecting means, thermostatic, J. E. Baldwin                            | 754,534 |         |
| Gas-detector, G. A. Nelson                                                  | 754,596 |         |
| Gas-engine, P. H. Brennan                                                   | 754,418 |         |
| Gas generator, acetylene, Robertson & Heap                                  | 754,808 |         |
| Gas purification, apparatus for, F. Jas.                                    | 754,773 |         |
| Gate, H. H. Bell                                                            | 754,535 |         |
| Gate-opener, G. C. Laney                                                    | 754,876 |         |
| Gear-molding machine, F. Kepp                                               | 754,777 |         |
| Gear, transmission, P. H. Brennan                                           | 754,638 |         |
| Gear, variable-speed and reversing, H. R. Bevier                            | 754,738 |         |
| Gearing, differential, H. E. Bayley                                         | 754,914 |         |
| Gearing, variable-speed, A. B. Shultz, et al                                | 754,905 |         |
| Glass machine, sheet, S. Deely                                              | 754,752 |         |
| Glass-working machine, I. W. Colburn                                        | 754,426 |         |

**Calendar Clock Attachment**  
Can be used in connection with any clock, as shown in cut, or simply as a calendar. **Automatic and Simple.** Suitable for offices, schools, churches, public buildings, etc. Will sell right to manufacture on royalty.  
**JOHN I. PEATFIELD**  
Arlington, Mass.

**If a Postage Stamp**  
and a few cents worth of writing material combined with the investment of five minutes time would put a larger income in your pocket, would you make the expenditure?  
We deal in the most conservative line of securities and guarantee satisfaction. Rigid investigation welcomed. Write us for list of offerings.

**ABBOTT & COMPANY**  
Dealers in High Class Investments,  
Dept. S, 23 Court St., BOSTON, MASS.

**The Hygrophant**  
shows with accuracy and without computation the temperature and degree of humidity. Send for circular  
**J. S. F. HUDDLESTON**  
20 Devonshire St., Boston

**DIVIDEND**  
PAYING MINING, OIL, TIMBER, SMELTER, AND INDUSTRIAL STOCKS making possible LARGE INTEREST AND PROFITS, listed and unlisted, our specialty. Booklets giving full information mailed free on application.  
**DOUGLAS, LACEY & CO.,**  
Bankers & Brokers, 66 Broadway, New York


**USE GRINDSTONES?**  
If so we can supply you. All sizes mounted and unmounted, always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. Ask for catalogue.  
**The CLEVELAND STONE CO.**  
2d Floor, Wilshire, Cleveland, O.

**STEAM TURBINES.—THEIR CONSTRUCTION, Operation and Commercial Application.**  
SCIENTIFIC AMERICAN SUPPLEMENTS 1306, 1307, 1308, 1422, 1400, 1447, 1370, 1372. The articles have all been prepared by experts in steam engineering. Price 10 cents each, by mail. Munn & Co., 361 Broadway, New York City, and all newsdealers.

**TOOLS FOR MECHANICS.**  
Send for Free Catalogue No. 16 B.  
**The L. S. Starrett Co., Athol, Mass., U. S. A.**

**For Either Hand or Power**  
This machine is the regular hand machine supplied with a power base, pinion, countershaft, etc., and can be worked as an ordinary power machine or taken from its base for use as a hand machine. Length of pipe handled easily in small room. Illustrated catalogue—price list free on application.  
**THE CURTIS & CURTIS CO.,**  
6 Garden St., BRIDGEPORT, CONN.

**We Solicit Contracts**  
And can compete in **QUALITY and PRICE** on work for which the varied machinery of our numerous factories is suited.  
ADDRESS  
**POPE Manufacturing Company**  
21 Park Row New York City



**The Joys of Touring**  
Come in fullest measure to those who know the sense of absolute safety, the thrill of measureless speed, and the feeling of luxurious comfort that abound in  
**Peerless Direct Drive Touring Cars**  
\$3,700 to \$6,000  
Peerless Cars are easy to handle. They are sent out ready to run and stay so.  
Photograph of the "Peerless Girl V," size 18 x 29 inches, without advertising and suitable to frame, mailed you for ten cents stamps or coin. Write for new illustrated catalog.  
**THE PEERLESS MOTOR CAR CO.**  
Cleveland, Ohio  
Member Association Licensed Automobile Manufacturers.

**Patents, Trade Marks, COPYRIGHTS, etc.,**  
Address **MUNN & CO.,** Solicitors of Patents.  
Office of the SCIENTIFIC AMERICAN  
361 Broadway, New York.  
Branch Office: 625 F St., Washington, D. C.  
Hand-book Sent Free on Application.

**CRESTMOBILE \$800**  
The BEST CAR Built in America  
Proved by Its Splendid Records.  
Tonneau for Four, \$850.  
Other LOW Priced Models.  
Export Prices \$50 Extra.  
**CREST MFG. CO.,** Cambridge, Mass., U.S.A.

**THE EUREKA CLIP**  
The most useful article ever invented for the purpose. Indispensable to Lawyers, Editors, Students, Bankers, Insurance Companies and business men generally. Book marker and paper clip. Does not mutilate the paper. Can be used repeatedly. In boxes of 100 for 25c. To be had of all booksellers, stationers and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Manufactured by Consolidated Safety Pin Co., Box 121, Bloomfield, N. J.

**GAS ENGINE IGNITERS**  
LATEST TYPE. BEST MADE.  
For Marine, Automobile or Stationary Engines. Fully Guaranteed.  
Write for Circular.  
**The Carlisle & Finch Co.,**  
233 E. Clifton Ave., Cincinnati, Ohio


**MARINE ENGINES**  
1, 2, 3 and 4 Cylinder  
1 1/2 to 40 H. P.  
Launches 17 to 50 feet  
Send for new catalog  
**GRAND RAPIDS GAS ENGINE & YACHT CO.**  
Grand Rapids, Mich.

**BUILD YOUR OWN BOAT BY THE BROOKS SYSTEM**  
\$5.00 EXACT SIZE PATTERNS, COMPLETE INSTRUCTIONS FOR PATTERNS, EACH STEP ILLUSTRATED—HUNDREDS OF CUSTOMERS HAVE BUILT THIS COMBINATION ROW BOAT SAIL BOAT AND LAUNCH IN FOUR DAYS TIME AT A TOTAL COST OF \$24. MATERIAL PURCHASED LOCALLY COSTS ABOUT \$20. PATTERNS OF ALL KINDS AND SIZES OF BOATS AT PRICES 16 FT LONG-4 FT BEAM. FROM \$30 UP. PARTICULARS FREE. 25¢ BRINGS 64 P. ILLUSTRATED CATALOGUE AND SET OF WORKING INSTRUCTIONS AND ILLUSTRATIONS. WRITE TO DR. BROOKS BOAT MFG. CO., STA. A, BAY CITY, MICH.

**MATCH MACHINERY.**  
BIG MONEY IN MATCHES.  
We manufacture everything pertaining to the business. The Very Latest Process. We will furnish a manager or teach any purchaser the business.  
**F. W. MURPHY & BRO.,**  
1118 Ashtab Block, Chicago, Ill., U. S. A.

**50 Years' Experience**  
**PATENTS**  
Trade Marks, Designs, Copyrights, Etc.  
Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents. Patents taken through MUNN & Co. receive Special Notice, without charge, in the  
**Scientific American**  
A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.  
**MUNN & CO.,** 361 Broadway, New York  
Branch Office 625 F St. Washington, D. C.





**The MEDART BOAT BUILDING MATERIALS**  
Bring best construction within the range of materials, at a small cost.  
Yachts, Launches, Row Boats.  
Send stamp for catalog.  
**FRED MEDART, 3545 DeKalb St., St. Louis, Mo.**

**AERIAL NAVIGATION.—THEORETICAL and Practical Discussions.** Pictures and descriptions of actually built dirigible balloons and aeroplanes will be found in SCIENTIFIC AMERICAN SUPPLEMENTS 1161, 1149, 1150, 1151, 1404, 1405, 1413, 1455. Price 10 cents each, by mail. Munn & Co., 361 Broadway, New York City, and all newsdealers.

**"Power" Wire Rope**  
**"POWER" ROPE**  
MOST POWERFULL WIRE ROPE MADE  
**BRODERICK & BASCOM ROPE CO.**  
ST. LOUIS, MO.

**The Auto-Sparker**  
To Owners of Gasoline Engines, Automobiles, Launches, Etc.  
does away entirely with all starting and running batteries, their annoyance and expense. No belt—no switch—no wires. Can be attached to any engine now using batteries. Fully guaranteed; write for descriptive catalog.  
**Motsinger Device Mfg. Co.,**  
14 Main St., Pendleton, Ind.

**Valuable Scientific Papers**  
ON TIMELY TOPICS  
Price 10 cents each, by mail

**RADIUM AND THE RADIO-ACTIVE SUBSTANCES.** No better or clearer scientific account has been published than that contained in SCIENTIFIC AMERICAN SUPPLEMENT 1429. The paper presents all that is at present known about radium and the radio-active substances.

**ELECTRONS AND THE ELECTRONIC THEORY** are discussed by SIR OLIVER LODGE in SCIENTIFIC AMERICAN SUPPLEMENTS 1428, 1429, 1430, 1431, 1432, 1433, 1434.

**THE PANAMA CANAL** is described from the engineering standpoint in SCIENTIFIC AMERICAN SUPPLEMENT 1359.

**WIRELESS TELEGRAPHY.** Its Progress and Present Condition are well discussed in SCIENTIFIC AMERICAN SUPPLEMENTS 1425, 1426, 1427, 1386, 1388, 1389, 1383, 1381, 1327, 1328, 1329, 1431.

**HOW TO CONSTRUCT AN EFFICIENT WIRELESS TELEGRAPH APPARATUS AT SMALL COST** is told in SCIENTIFIC AMERICAN SUPPLEMENT 1363.

**SUBMARINE NAVIGATION.** An exhaustive review of the subject is published in SCIENTIFIC AMERICAN SUPPLEMENTS 1414, 1415, 1222, 1223.

**SELENIUM AND ITS REMARKABLE PROPERTIES** are fully described in SCIENTIFIC AMERICAN SUPPLEMENT 1430. The paper is illustrated by numerous engravings.

**THE INTERNAL WORK OF THE WIND.** By S. P. LANGLEY. A painstaking discussion by the leading authority on Aerodynamics, of a subject of value to all interested in airships. SCIENTIFIC AMERICAN SUPPLEMENTS 946 and 947.

**LANGLEY'S AERODROME.** Fully described and illustrated in SCIENTIFIC AMERICAN SUPPLEMENTS 1404 and 1405.

**STEAM TURBINES.** Their Construction, Operation and Commercial Application. SCIENTIFIC AMERICAN SUPPLEMENTS 1306, 1307, 1308, 1422, 1400, 1447, 1370, 1372. The articles have all been prepared by experts in steam engineering.

**PORTLAND CEMENT MAKING** is described in excellent articles contained in SCIENTIFIC AMERICAN SUPPLEMENTS 1433, 1465, 1466.

**AERIAL NAVIGATION.** Theoretical and Practical Discussions. Pictures and Descriptions of actually-built dirigible balloons and aeroplanes will be found in SCIENTIFIC AMERICAN SUPPLEMENTS 1161, 1149, 1150, 1151, 1404, 1405, 1413, 1455.

Price 10 cents each, by mail  
**MUNN & COMPANY**  
361 Broadway New York

|                                                                                                        |         |
|--------------------------------------------------------------------------------------------------------|---------|
| Glove-turner, G. Burr.....                                                                             | 754,539 |
| Gold-separator, La Bud & Barton.....                                                                   | 754,657 |
| Governor, N. Lombard.....                                                                              | 754,469 |
| Governor, engine, H. Holzwarth.....                                                                    | 754,563 |
| Grain-blower, G. Merkel.....                                                                           | 754,476 |
| Grain-separator, F. M. Smith.....                                                                      | 754,617 |
| Grain-separator, J. K. White.....                                                                      | 754,729 |
| Grain-separator straw-rack, J. Johanneck.....                                                          | 754,874 |
| Grinding and polishing machine, J. B. Lobet.....                                                       | 754,978 |
| Grist-mill, S. L. Shelby.....                                                                          | 754,903 |
| Guide-wheel, A. H. Mathesius.....                                                                      | 754,473 |
| Gun, F. Novotny.....                                                                                   | 754,599 |
| Gun, automatic, C. Petersen.....                                                                       | 754,691 |
| Gun, electromagnetic, K. Birkeland.....                                                                | 754,637 |
| Gun shell-ejector mechanism, F. Novotny.....                                                           | 754,598 |
| Gun sight, shot, P. O. Elterich.....                                                                   | 754,920 |
| Guns, fluid-brake for recoil, E. K. Rothe.....                                                         | 754,896 |
| Hair-dressing device, J. T. Wilcox.....                                                                | 754,949 |
| Hammer, steam, C. E. Billin.....                                                                       | 754,636 |
| Hanging basket and pot, combination, F. Neidl.....                                                     | 754,683 |
| Harness-rack, C. H. Mustgrove.....                                                                     | 754,483 |
| Harvester, B. Holthaus.....                                                                            | 754,926 |
| Harvester butt-adjuster, J. F. Steward.....                                                            | 754,719 |
| Harvester, corn, A. Neer.....                                                                          | 754,491 |
| Harvester grain-deck, A. Reinhardt.....                                                                | 754,609 |
| Harvester-headboard, J. F. Steward.....                                                                | 754,718 |
| Harvester tongue-truck, E. A. Johnston.....                                                            | 754,568 |
| Harvester toppe and stripper, cane, G. D. Latas.....                                                   | 754,788 |
| Hat-fastener, F. S. Rowdell.....                                                                       | 754,916 |
| Hat pin or fastener, Troupe & Brooks.....                                                              | 754,519 |
| Header and stacker, combined, J. H. Kindsvater.....                                                    | 754,780 |
| Heat-regulator, automatic electric, D. N. Leib.....                                                    | 754,465 |
| Hedge-bar fastening, Fehr & Kaufmann.....                                                              | 754,860 |
| Heel, adjustable shoe, A. Westwood.....                                                                | 754,947 |
| Hide working and unhairing machine, R. F. Whitney.....                                                 | 754,525 |
| Hinge, separable screen, H. B. Higgins.....                                                            | 754,769 |
| Hinge, separable screen, C. Rowland.....                                                               | 754,809 |
| Honey, fermenting, A. V. Kouba.....                                                                    | 754,461 |
| Hook. See Suspension-hook.                                                                             |         |
| Hook-rack, Rubicam & Baxter.....                                                                       | 754,503 |
| Horse-rake, J. H. Randolph.....                                                                        | 754,499 |
| Horsehoe, J. A. Martin.....                                                                            | 754,789 |
| Hub, metal-covered vehicle, G. A. McKeel.....                                                          | 754,490 |
| Ice-creper, C. F. Becknagel.....                                                                       | 754,500 |
| Ice-tank, J. L. Hopkins.....                                                                           | 754,772 |
| Induction-coil, R. Miller, Jr.....                                                                     | 754,666 |
| Ingot-crane, C. L. Taylor.....                                                                         | 754,910 |
| Internal-combustion engine for cycles, H. Le-pape.....                                                 | 754,929 |
| Intestine wringer, beef, H. C. Ziprick.....                                                            | 754,630 |
| Iron pyrites from zinc-blende, separating, K. Danziger.....                                            | 754,643 |
| Ironing-table, W. O. Schellhamer.....                                                                  | 754,898 |
| Kettles, etc., attachment for jacket, F. M. Kimball.....                                               | 754,779 |
| Kiln-door, H. H. Hacker.....                                                                           | 754,559 |
| Labeling-machine, D. W. Kneisly.....                                                                   | 754,460 |
| Lace holder, shoe, N. Comp.....                                                                        | 754,851 |
| Lace or shoestring holder, shoe, R. E. R. Thomson.....                                                 | 754,517 |
| Ladder and scaffold support, T. Copeman.....                                                           | 754,427 |
| Ladder-hanger, S. C. Johnson.....                                                                      | 754,776 |
| Lamp, J. L. Creveling.....                                                                             | 754,428 |
| Lamp, electric pocket, A. E. Post.....                                                                 | 754,694 |
| Lamp for canes, umbrella-sticks, etc., J. W. Allen.....                                                | 754,631 |
| Lampblack-making machine, J. H. Mann.....                                                              | 754,471 |
| Larding or salting device, R. R. Reynolds.....                                                         | 754,501 |
| Latch, D. W. Tower.....                                                                                | 754,721 |
| Lead salts, making, W. Mills.....                                                                      | 754,667 |
| Lead-carriage-securing means, C. E. Hutch-ings.....                                                    | 754,872 |
| Letter-box, door-bell, and name-plate, com-bination, H. Messersmith.....                               | 754,664 |
| Leveling instrument, G. Townsend.....                                                                  | 754,723 |
| Line-casting machine, W. S. Scudder.....                                                               | 754,614 |
| Link, separable, E. C. Vale.....                                                                       | 754,521 |
| Litholeum carpets, manufacturing, F. K. Magnus of Ekstrom.....                                         | 754,581 |
| Lino-type-machines, producing notches in lino-types or slugs as they are cast in, W. R. Speechley..... | 754,619 |
| Liquid-distributing system, Williams & Whit-man.....                                                   | 754,953 |
| Liquid-separator, centrifugal, T. H. Springer.....                                                     | 754,309 |
| Lister attachment, J. A. Herron.....                                                                   | 754,449 |
| Loading apparatus, E. T. Maxwell.....                                                                  | 754,586 |
| Locomotive-boiler, S. F. Prince, Jr.....                                                               | 754,497 |
| Loom shedding apparatus, N. & J. Chai-ze.....                                                          | 754,846 |
| Loom web-replenishing mechanism, W. H. & H. H. Hacking.....                                            | 754,560 |
| Lubrication, apparatus for force-feed, J. F. McCona.....                                               | 754,486 |
| Lubricator, J. J. Mull.....                                                                            | 754,737 |
| Mail-box carrier, G. B. Olney.....                                                                     | 754,686 |
| Mail-carrier, P. P. O'Neill.....                                                                       | 754,795 |
| Mail-delivery box, T. R. Gray.....                                                                     | 754,441 |
| Map, E. Heubach.....                                                                                   | 754,450 |
| Massage device, O. Zar-Adusht-Hanish.....                                                              | 754,925 |
| Massage-machine, P. J. Kroll.....                                                                      | 754,463 |
| Match-case, S. Robert.....                                                                             | 754,707 |
| Measure, tailor's, S. M. Griffen.....                                                                  | 754,765 |
| Measuring and weighing machine, R. L. Pat-terson.....                                                  | 754,937 |
| Metal-plate-doubling machine, B. H. Doll.....                                                          | 754,433 |
| Microscopes, fine adjustment for, C. F. Dieck-mann.....                                                | 754,954 |
| Milking-machine, Hulbert & Park.....                                                                   | 754,453 |
| Miter-box, J. A. Traut.....                                                                            | 754,624 |
| Molding apparatus, R. A. Penrose.....                                                                  | 754,495 |
| Mop-wringer, C. E. Hill.....                                                                           | 754,870 |
| Mortising chain cutter, portable, G. A. D'Isese.....                                                   | 754,752 |
| Mountain-climber, reversible, N. Laub.....                                                             | 754,577 |
| Mouse-trap, T. L. Ray.....                                                                             | 754,891 |
| Mowing-machine pitman connection, F. P. Burkhardt.....                                                 | 754,538 |
| Music-rack, folding, J. H. Rockwell.....                                                               | 754,502 |
| Musical instruments, means for regulating the expression of mechanical, R. W. Pain.....                | 754,886 |
| Nail-extractor, A. Dudley.....                                                                         | 754,754 |
| Nitrogen compounds for atmospheric nitro-gen, making, H. Mohner.....                                   | 754,474 |
| Nozzle, exhaust, W. S. Clarkson.....                                                                   | 754,746 |
| Nut, lock, Evans & Williams.....                                                                       | 754,488 |
| Nut-lock, J. C. Mitchell.....                                                                          | 754,590 |
| Nut-lock, J. E. Hedrick.....                                                                           | 754,767 |
| Oil-burner, A. Macaulen.....                                                                           | 754,661 |
| Oil-cake-treating apparatus, A. B. Lawther.....                                                        | 754,576 |
| Ordnance automatic firing device, L. Oby.....                                                          | 754,885 |
| Ore and pulp sampler, automatic, C. Allen.....                                                         | 754,912 |
| Ore and slime separator, automatic, C. Allen.....                                                      | 754,911 |
| Ores from magnetic gangue, separating, A. Edison.....                                                  | 754,756 |
| Organ, D. Schustek.....                                                                                | 754,713 |
| Oven, bake, H. Hecker.....                                                                             | 754,866 |
| Package, shipping, J. A. Bower.....                                                                    | 754,537 |
| Packing, rod, N. H. Albrecht.....                                                                      | 754,834 |
| Padlock, J. B. Miller.....                                                                             | 754,479 |
| Paper-folding machine, E. D. Casterline, re-issue.....                                                 | 12,204  |
| Pedestal, angular, J. Howland-Sherman.....                                                             | 754,871 |
| Pen, fountain, W. Bovill.....                                                                          | 754,416 |
| Petroleum, apparatus for refining crude, J. M. O'Neill.....                                            | 754,687 |
| Phonographic apparatus, Skiff & Grant.....                                                             | 754,508 |
| Phosphorus compound and making same, or-ganic, S. Posternak.....                                       | 754,803 |
| Photographic film, R. A. Anthony.....                                                                  | 754,736 |
| Photographic film, flexible, F. A. Anthony.....                                                        | 754,735 |
| Photographic view-finder, J. A. Robertson.....                                                         | 754,803 |
| Piano attachment, pneumatic, E. C. Pryor.....                                                          | 754,498 |
| Piano-players, pedal-stop action for auto-matic, W. F. Cooper, Jr.....                                 | 754,750 |
| Pin. See Hat-pin.                                                                                      |         |
| Pipe and nut wrench, combined, J. C. Shi-der.....                                                      | 754,509 |
| Piston-rod, H. A. J. Neumann.....                                                                      | 754,793 |
| Pitman, K. F. Seith.....                                                                               | 754,506 |
| Plant support and holder, adjustable, H. C. Chessan.....                                               | 754,542 |
| Plow, J. Kheil.....                                                                                    | 754,572 |
| Post-hole digger, C. Butcher.....                                                                      | 754,421 |
| Power machine, hand or foot, J. P. Cline.....                                                          | 754,849 |
| Power mechanism, interchangeable hand and motive, Ellicott & Norris.....                               | 754,757 |
| Propelling apparatus, vessel, M. P. Schetzel.....                                                      | 754,431 |
| Pump, J. M. Crowley.....                                                                               | 754,710 |
| Pump, heating and condensing feed, W. Tate.....                                                        | 754,826 |
| Pump, lubricating, McCanna & Markle.....                                                               | 754,485 |
| Puzzle, J. Van Putten.....                                                                             | 754,724 |
| Pyrographic work, tool for, Z. N. Tyssowska.....                                                       | 754,944 |
| Rail-bender, R. O. Hintz.....                                                                          | 754,562 |
| Rail-joint, W. Watkins.....                                                                            | 754,727 |
| Railway cross-tie, T. J. Kitto.....                                                                    | 754,458 |

**The APPLE Ignition Dynamo**  
Saves battery troubles, attached to any gas engine. Governors, Storage and Dry Batteries, Spark Coils, Plugs, Switches, Automatic Timing Devices.  
**The Dayton Electrical Mfg. Co.**  
88 Reibold Bldg., DAYTON, O.

**The Franklin Model Shop**  
Experimental work for inventors; any-thing in metal from a single piece to a complete working model. Apparatus for colleges. Exhibition models. Introduc-tion samples of patented articles. Special tools for making metal novelties. Inventions perfected. Drawings and de-signs worked out from inventors' ideas. Send for circular.  
**PARSELL & WEED,**  
129-131 West 31st Street, New York.

**"The Sharer"**  
A new foot power that can be applied to all light machinery. A kick starts the machine and an occasional kick keeps it going. Send for our Booklet.  
**SLOTKIN & PRAGLIN,**  
210A Canal St., New York.

**A Southern Home**  
In a country free from excessive heat and cold, healthful and prosperous.  
**LANDS at LOW PRICES**  
For printed matter, circulars, etc., giving full particulars, write  
**M. V. RICHARDS,** Land and Industrial Agent,  
Southern Railway and Mobile & Ohio Railroad,  
Washington, D. C.

If you want the best **CHUCKS**, buy Westcott's  
Little Giant Double Grip  
Drill Chucks, Little Giant  
Improved,  
Oneida Drill  
Chucks, Cut-ting-off  
Chucks, Scroll  
Combination  
Lathe Chucks, Geared  
Combination Lathe Chucks, Plain Universal Lathe Chucks, Independent Lathe Chucks. Made by  
**Westcott Chuck Co., Oneida, N. Y., U. S. A.**  
Ask for catalogue in English, French, Spanish or German.  
FIRST PRIZE AT COLUMBIAN EXPOSITION, 1893.

**WONDER Acetylene Burners**  
Price **ARE THE BEST**  
40c. each. Sold by good dealers or write  
**THE STATE LINE MFG. CO.**  
9th & 10th Sts., Chattanooga, Tenn., U. S. A.

**"COMMERCIAL CALCULATOR."** All measures, tables and calculations for every business worked out ready for instant use. No business man, mechanic, apprentice or office man can afford to be without it; send 50c. to Tunis Mfg. Co., 708 Chestnut St. Phila., Pa.

**MAXIMUM POWER—MINIMUM COST.**  
If you use a pump for beer, lard, acids, starch, petroleum, brewer's mash, tanner's liquor, cottonseed oil or fluids, hot or cold, thick or thin you want to get the **TABER ROTARY PUMP** which does the most work at the least expense. Simply constructed. Can be run at any desired speed. Perfectly durable. All parts are interchangeable. Needs no skilled workman. Defects guaranteed. Catalogue free.  
**TABER PUMP CO.,** 32 Wells St., Buffalo, N. Y., U. S. A.


**Patents, Trade Marks, COPYRIGHTS, etc.,**  
Address **MUNN & CO.,** Solicitors of Patents.  
Office of the SCIENTIFIC AMERICAN  
361 Broadway, New York.  
Branch Office: 625 F St., Washington, D. C.  
Hand-book Sent Free on Application.

**POWER**  
For any power purpose we offer The American Gas & Gasoline Engine, in actual service, it will be found simple, durable, economical of fuel, and a most satisfying power, easily operated, without the aid of skilled help. A modern up-to-the-minute ex-pensive Engine. We also build Vertical Engines. Catalogue sent of either, or both, to interested parties.  
**AMERICAN GAS & GASOLINE ENGINE CO.,**  
70 Keenebec Street, Portland, Maine.

**TOOLS AS A TOPIC**  
must be interesting to every handi-craftsman. There is a mine of infor-mation in  
**Montgomery & Co.'s Tool Catalogue** which enumerates thousands of tools. Capital handbook of reference. Pro-fusely illustrated. Sent by mail for 25 cents. discount sheet included.  
**MONTGOMERY & CO.,**  
105 Fulton St., New York City. CATALOGUE No. 21

**Hydro-Carbon Motors**  
Headless Self-Contained  
It is as easily controlled as a steam engine. Variable spark. The only perfect moderate priced launch engine on the market. Let us convince you. Write to-day.  
**Grant-Ferris Co., Troy, N. Y.**

**50 BULBS**  
25 Cents.  
Will grow in the house or out of doors.  
Tulips, Hyacinths, Crocus, Fuchsias, Jonquils, Daffodils, Dewey Lily, Tuberoses, Gladioli, Chinese Lily, Begonia, Mexican Lily, etc.  
All postpaid, 25c. in stamps or coin. As a premium with these Bulbs we will send FREE a giant collection of flower seeds—over 200 varieties—Address, **Hillside Nursery, Somerville, Mass.**



**Wherever a Wheel Will Turn a Cadillac Will Go.**  
The Cadillac is the only automobile embodying broadly utilitarian principles. The picture above shows a strong, stylish, powerful touring car that will accommo-date four people comfortably; that is as smooth-running and reliable as any high-priced machine. Remove the ton-neau, and it becomes a smart runabout—superior to every other in simplicity and ease of operation; equaled by none in speed, strength, appearance or mechanical excellence.  
**CADILLAC**  
is an auto-mobile absolutely unique in perfection of design and carefulness of construction. No other is so easily and perfectly adaptable to the various requirements of business and pleasure; no other has so many points of intrinsic superiority. Improved wheel steering-gear; new departure in brakes; positive ignition. Trans-mission is simple, noiseless and "fool-proof." When cars running on high gear the speed can be regulated on ordinary roads by throttle alone. Engine develops eight-horse power, runs without vibration and will drive steadily, surely, powerfully, "wherever a wheel will turn."  
Model A, 1904, with detachable ton-neau, seating four, all facing forward, \$850.00; without tonneau, \$750.00. All 1904 Cadillacs are equipped with Clincher Tires.  
Our free illustrated booklet N gives address of agency nearest you, where the Cadillac may be seen and tried.  
**Cadillac Automobile Co.,**  
Detroit, Mich.  
Member Association of Licensed Automobile Manufacturers.


**DR. DYKE'S "DISEASES OF A GASOLENE AUTOMOBILE AND HOW TO CURE THEM."**  
A book for owner, intending purchaser or repairman.  
Hints and suggestions with illustrations, Diagrams and Connections.  
Price \$1.50  
**A. L. DYKE AUTO. SUPPLY COMPANY**  
2108 Olive St., St. Louis, Mo.  
Send 10c. for the largest Auto. Supply Cat. in the world

**\$100. to \$300. MONTHLY.**  
Men and women. Salesmen, Managers and Agents. Delightful business year round. Hustlers getting rich. Write today for brand-new plan and Special Offer this month. 100 per cent profits. No risk. Goods well advertised. National reputation. Fully guaranteed. Customers delighted. We're an old firm, capital \$100,000.00. Catalogue FREE. Any energetic man or woman can get good position, paying big wages.  
**WORLD MFG. CO.,**  
81 World Bldg., Cincinnati, Ohio.

**ORIGINAL BARNES Upright Drills**  
Positive Feed  
10 to 50-inch Swing  
Send for Drill Catalogue.  
**W. F. & JNO. BARNES CO.**  
(Established 1872)  
1999 Ruby St., Rockford, Ill.

**For More Light on the Subject send for our PHOTO-PAMPHLET**  
**PERFECTED GRANITE ROOFING**

**EASTERN GRANITE ROOFING CO.**  
Irving Building New York  
**PRINTING TAUGHT FREE**  
With every Model Printing Press and outfit (cost \$5 and up) we give free a complete course in the art of printing. While you're learning you can make money at home by printing for others. Write for particulars, and catalogue No. 10. Three World's Fair Highest Awards. **THE MODEL PRESS**  
708 Chestnut Street, Philadelphia.



### Model "K"

here illustrated, is the strongest and most powerful car of its weight ever built. It has full elliptic springs, two powerful brakes, 30-in. wheels and 3 1/2 inch tires, 84-in. wheel base, 2 cylinder opposed engines of 16 actual horsepower, and carries five people over any kind of roads, in any kind of weather. Nothing equal to it, either in power or appearance, sold for double the price.

## Rambler

### Touring Cars

Six different models \$650 to \$1,350 at the factory.

Model "K" with four lamps and horn, \$1,200 at the factory. Same car fitted with canopy top, beveled plate glass swinging front and side baskets, Model "L" \$1,350 at the factory. Rambler Delivery Wagons, with detachable top, \$850 at the factory.

Our new illustrated catalogue shows each different style of car and tells its special points of merit. Shall we mail you a copy?

Thos. B. Jeffery & Co., Kenosha, Wis., U. S. A.  
Chicago, 304 Wabash Ave. Boston, 145 Columbus Ave.

### Not in the Front Rank. It is the Leader

#### 2 1/2 H. P. Single Cylinder Motor Cycle

For Speed Long Life Mileage Power For Pleasure Business Economy Style



Our Double-Cylinder Machine holds all world's records. Get catalog.

G. H. CURTISS MFG. CO. - Hammondsport, N. Y.

### "Time is Money"



And this wrench will do the work for you in less than half the time of other wrenches, and the harder the work, the tighter it holds. The body of this wrench is made of malleable steel and warranted not to break. Retail Price, \$1.00 Each.

HUDSON PARER COMPANY  
Leominster, Props. & Mfrs. Massachusetts

THE CARE OF ACETYLENE GAS is discussed in SCIENTIFIC AMERICAN SUPPLEMENTS 1189, 1444, 1289. Munn & Co., 361 Broadway, and all newsdealers.

## THE EXCELLENT GROUT

### STEAM CARS

are SIMPLE, STRONG and SPEEDY. The Grout is noiseless, and does not vibrate or throw either standing or running. As a hill climber the Grout is doing remarkable work. The Grout Steam Runabout at \$650 is not a mere road cart or "buggy." It is a sturdy, compact and serviceable car for hard and constant usage. Send for book.

Grout Brothers  
Automobile Co.  
Orange, Mass.

# \$650


## THE SMITH PREMIER TYPEWRITER

is strongly linked to the BUSINESS WORLD

Our interesting booklet explaining just why, sent on request.

THE SMITH PREMIER TYPEWRITER CO.  
EXECUTIVE OFFICE  
287 Broadway  
New York  
FACTORY  
Syracuse, N. Y.

|                                                                                     |         |
|-------------------------------------------------------------------------------------|---------|
| Railway danger-signals, electrically-operated stopping means at, W. L. Adamson..... | 754,406 |
| Railway, electric, Huber & Bach Eschenburg                                          | 754,565 |
| Railway-frog, Kimball & Connors.....                                                | 754,875 |
| Railway plow, electric, J. H. Akers.....                                            | 754,832 |
| Railway-rail joint, A. Barnes.....                                                  | 754,913 |
| Railway-rails, device for preventing the creeping and wandering of, E. Masik.....   | 754,881 |
| Railway-switch, T. E. Gummerson.....                                                | 754,864 |
| Railway-switch, automatic, M. M. Whitfield                                          | 754,627 |
| Railway-tie plate, W. S. Jones.....                                                 | 754,654 |
| Railways, automatic brake-applying device for, Meyer & Geritz.....                  | 754,665 |
| Register, H. A. Nichol.....                                                         | 754,684 |
| Rheostat, L. Lyndon.....                                                            | 754,660 |
| Rheostat, C. R. Pitrat.....                                                         | 754,692 |
| Ring and listening key, C. H. North.....                                            | 754,935 |
| Roll-holder, J. Barry.....                                                          | 754,420 |
| Roof valleys, means for covering tile, W. Ludowici.....                             | 754,578 |
| Rope-haulage, socket, G. W. Minto.....                                              | 754,589 |
| Rotary engine, H. Berglund.....                                                     | 754,411 |
| Rotary steam-engine, H. C. Mitchell.....                                            | 754,672 |
| Rule, P. S. Hamrick.....                                                            | 754,445 |
| Safe, E. E. Thompson.....                                                           | 754,623 |
| Safety-pin, A. Buckelew.....                                                        | 754,743 |
| Sash holder and lock, O. E. Howe.....                                               | 754,452 |
| Sash, pivoted, G. Kabureck.....                                                     | 754,655 |
| Sash, window, G. H. Lawrence.....                                                   | 754,575 |
| Scenic effects, apparatus for producing, E. O. Healy.....                           | 754,867 |
| Scenographic apparatus, Austen & Bradwell                                           | 754,532 |
| Scenographic apparatus, E. J. Austen.....                                           | 754,533 |
| Scholar's companion, A. E. Greves.....                                              | 754,558 |
| School companion, T. Crawford.....                                                  | 754,852 |
| Screen, D. D. Pinkham.....                                                          | 754,800 |
| Screen hanger, half-sized, H. B. Higgins.....                                       | 754,771 |
| Seat-spider, H. W. Bolens.....                                                      | 754,413 |
| Seine-hauling apparatus, H. C. Albee.....                                           | 754,833 |
| Self-adjusting wheel, Root & Wallace.....                                           | 754,894 |
| Semelliptic spring, T. A. Shea.....                                                 | 754,715 |
| Sewing machine feeding mechanism, D. Noble.....                                     | 754,934 |
| Sewing machine ruffling mechanism, A. Laubscher.....                                | 754,928 |
| Shade goods, machine for trimming and applying, E. O. Engberg.....                  | 754,759 |
| Sharpener, disk, W. J. Julian.....                                                  | 754,455 |
| Shaving mug, I. E. Foltz.....                                                       | 754,761 |
| Sheet metal edging machine, E. P. Lockwood.....                                     | 754,786 |
| Shelf support, adjustable, E. G. Schrieffer.....                                    | 754,816 |
| Shoe attachment, athletic, J. G. Mitchell.....                                      | 754,673 |
| Shovel and foot protector, J. Christiansen.....                                     | 754,543 |
| Shoveling device, J. G. Westbrook.....                                              | 754,946 |
| Show case, W. H. J. Guest.....                                                      | 754,443 |
| Show case, C. W. Selden.....                                                        | 754,507 |
| Shutter work, F. D. O'Brien.....                                                    | 754,832 |
| Shuttle, float detecting, E. Lamoureux.....                                         | 754,658 |
| Sidevalve on street crossings, J. A. Rose.....                                      | 754,895 |
| Siding, sheet metal, E. G. Charlebois.....                                          | 754,541 |
| Sieve, F. W. Haseh.....                                                             | 754,865 |
| Signaling system, wireless, H. Shoemaker.....                                       | 754,904 |
| Silt and sand separator, automatic, C. Allen.....                                   | 754,732 |
| Skirt hanger, S. J. Goldsmith.....                                                  | 754,763 |
| Skid, coasting, W. F. Parmelee.....                                                 | 754,887 |
| Soldering apparatus, can, J. G. & M. O. Reh-fuss.....                               | 754,939 |
| Soldering machine, can, J. G. & M. O. Reh-fuss.....                                 | 754,699 |
| Speaking figure, Spencer & Lynde.....                                               | 754,825 |
| Spring, See Couch spring.....                                                       |         |
| Stacker hoisting mechanism, J. H. Kindsvater.....                                   | 754,781 |
| Stacker, pneumatic, J. Henry.....                                                   | 754,448 |
| Steam boiler, C. B. Bearick.....                                                    | 754,482 |
| Steam boiler, R. W. Barton.....                                                     | 754,837 |
| Stock, hoisting device for live, L. W. Johnson.....                                 | 754,775 |
| Stone cleaning composition and making same, P. J. Brahen.....                       | 754,417 |
| Stone, manufacture of artificial, F. W. Dunn.....                                   | 754,550 |
| Stove, O. P. Green.....                                                             | 754,557 |
| Stove fire box, cooking, J. Mulveny.....                                            | 754,482 |
| Stove, gas, H. A. Guignon.....                                                      | 754,651 |
| Straw, artificial, J. H. White.....                                                 | 754,948 |
| Stuffing box, C. D. Shorts.....                                                     | 754,820 |
| Stump extractor, Wheeler & Whittle.....                                             | 754,524 |
| Subcellar attachment, W. H. Bevans.....                                             | 754,412 |
| Suspenders, J. W. Burgett.....                                                      | 754,641 |
| Suspension hook, L. H. Torrey.....                                                  | 754,518 |
| Tally, progressive, J. W. Green.....                                                | 754,442 |
| Tank and heater, J. E. Bates.....                                                   | 754,835 |
| Tap, barrel, H. Pesenfeldt.....                                                     | 754,760 |
| Tapping device, Smith & Pelton.....                                                 | 754,618 |
| Telephone receiver support, H. L. Goodwin.....                                      | 754,556 |
| Telephonic relay or repeater, I. Kitsee.....                                        | 754,457 |
| Tension device, F. W. Temple.....                                                   | 754,516 |
| Theater building, A. Schlechter.....                                                | 754,711 |
| Threshing engine belt removing device, C. McCollor.....                             | 754,488 |
| Threshing machine, A. W. Collis.....                                                | 754,850 |
| Threshing machine clover hulling attachment, C. Saylor.....                         | 754,612 |
| Tie, B. F. Priddat.....                                                             | 754,605 |
| Tie fastener, E. F. Priddat.....                                                    | 754,606 |
| Tile grinding apparatus, T. H. Mooney.....                                          | 754,591 |
| Tilting bin and sample display device, A. J. West.....                              | 754,522 |
| Tire, H. G. Fiske.....                                                              | 754,648 |
| Tire, pneumatic, J. Dupont.....                                                     | 754,645 |
| Tires, machine for inserting transverse wires in solid rubber, A. E. Ellinwood..... | 754,552 |
| Tobacco pipe, J. Berchtold.....                                                     | 754,840 |
| Tool, combination, A. A. Blicke.....                                                | 754,739 |
| Tool, combination, Schmidt & Iskyan.....                                            | 754,812 |
| Tool, pneumatic, C. W. Peck.....                                                    | 754,906 |
| Tooth cleaning implement, G. C. Bossomay.....                                       | 754,841 |
| Torch, acetylene gas, W. H. Marsh.....                                              | 754,472 |
| Toy, C. A. Scadding.....                                                            | 754,709 |
| Toy gun, J. B. Mason.....                                                           | 754,434 |
| Traction engine, L. Beckwith.....                                                   | 754,409 |
| Transits, slope stake attachment for engineers, W. G. Russell.....                  | 754,897 |
| Transmitter, reversible, Simmons & Moore.....                                       | 754,822 |
| Trimming machine, N. M. Schuster.....                                               | 754,818 |
| Trolley hook for manipulating self-loading grabs, Hoover & Mason.....               | 754,652 |
| Trolley wheel retainer, J. A. Kilpatrick.....                                       | 754,778 |
| Truck, C. E. Davis.....                                                             | 754,545 |
| Tube, See Flexible tube.....                                                        |         |
| Tube cleaner, E. T. Deas.....                                                       | 754,854 |
| Tube scraper, E. M. Smith, et al.....                                               | 754,952 |
| Tufted fabrics, apparatus for the manufacture of, G. Morton.....                    | 754,883 |
| Tug fastener, hame, A. G. Shields.....                                              | 754,716 |
| Tunnel construction, J. W. Reno.....                                                | 754,807 |
| Turbine, steam, E. E. Fagerstrom.....                                               | 754,439 |
| Turbine, steam, P. J. Hedlund.....                                                  | 754,447 |
| Typewriter, feeding device, D. S. Dufur.....                                        | 754,435 |
| Typewriting machine, A. R. Jarman.....                                              | 754,434 |
| Typewriting machine, C. Gabrielson.....                                             | 754,922 |
| Valve, engine, J. H. Jones.....                                                     | 754,569 |
| Valve for turbine engines, governor, J. H. K. McCollum.....                         | 754,489 |
| Valve gear, F. Williams.....                                                        | 754,950 |
| Valve gearing, steam engine, J. B. Stanwood.....                                    | 754,620 |
| Valve, governor, D. J. Lyon.....                                                    | 754,880 |
| Valve, relief, N. Lombard.....                                                      | 754,467 |
| Valve, safety, N. Lombard.....                                                      | 754,468 |
| Valve, throttle, J. Desmond.....                                                    | 754,547 |
| Valve, trap, C. W. Clewell.....                                                     | 754,747 |
| Vehicle draft attachment, F. H. Sharp.....                                          | 754,902 |
| Vehicle frame and spring construction, W. F. Richards.....                          | 754,610 |
| Vehicle or machine, wheeled, L. W. Towne.....                                       | 754,722 |
| Vehicle running gear, R. A. Moore.....                                              | 754,680 |
| Vehicle, self propelled, J. C. Berube.....                                          | 754,635 |
| Vehicle shaft motion, device for preventing, W. N. Cleveland.....                   | 754,642 |
| Vehicle steering device, motor, Porsche & Lohner.....                               | 754,802 |
| Vehicle storm curtain, B. S. D. S. Martin.....                                      | 754,930 |
| Vehicle top support, G. Grogan.....                                                 | 754,650 |
| Vehicle wheel, P. A. Sanginetti.....                                                | 754,504 |
| Vending machine, coin actuating, C. A. Smiley.....                                  | 754,616 |
| Ventilator, F. J. Prochaska.....                                                    | 754,805 |
| Vessel sighting or observing tube, S. Lake.....                                     | 754,464 |
| Vibrating screen, W. J. Bell.....                                                   | 754,839 |
| Wagon, lumber, B. F. Padget.....                                                    | 754,601 |
| Waist attachment and skirt supporter, combination, A. Buckelew.....                 | 754,742 |
| Wardrobe, folding, H. H. Schuster.....                                              | 754,613 |
| Warping machine electric stop motion, Crocker & Denn.....                           | 754,748 |
| Washboiler fountain attachment, W. A. Mayor.....                                    | 754,790 |



## SPECIAL FEATURE

### World's Fair

#### SAINT LOUIS

Buckingham Club Building, new and strictly fire-proof, fronting on Forest Park, with 300 handsomely furnished suites of rooms, for the exclusive use of members and their families. Will open April 30th, 1904.


People of high social and business standing, desiring the best accommodations in St. Louis during their visit to the World's Fair, are joining the Club. All applications for membership must be approved by the membership committee. The Board of Directors of this Club is composed of the most prominent business men of St. Louis.

If interested, send us your name and address, with references, and club book and full particulars will be furnished you. Early attention is important, as only a limited number of members will be accepted. Address BUCKINGHAM CLUB, ST. LOUIS.

REFERENCES: Hon. D. R. Francis, President Louisiana Purchase Exposition Co., and every Bank or Trust Co. in St. Louis.

## Columbia

### Light Gasoline Tonneau



12-14 Horse Power (Honest Rating). Weight 1,700 lbs.  
Price \$1,750. Canopy Top, \$200 Extra

New system of control makes the two-cylinder opposed motor, which is placed forward in a removable bonnet, as flexible as a steam engine with none of its defects and limitations. High gear available for all ordinary speeds and grades. Gear changing by positive levers—no notches, no indices—making this the easiest of all gasoline cars to operate. Speed, two to thirty miles per hour. Lubrication automatic. Tonneau seats of full carriage size. Materials and workmanship highest grade in every detail.

24-30 Horse Power Touring Car (Chicago-New York Record) - \$3,500  
30-35 Horse Power Touring Car - 4 000  
Light Electric Runabout, new model - 850

Catalogue of Columbia Gasoline Cars and Electric Pleasure Vehicles will be sent on request; also separate catalogues of Electric Town Carriages of the coach class and Commercial Vehicles.

ELECTRIC VEHICLE COMPANY, HARTFORD, CONN.

NEW YORK 134-136 138 West 39th St. (Opp. Metropolitan Opera House)  
CHICAGO 1413 Michigan Ave.  
BOSTON 74-78 Stanhope St.

Member Association of Licensed Automobile Manufacturers

## A Scientific Germicide

### To prove the wonderful curative powers of

# Hydrozone

to all afflicted with Sore Throat I will send


One Trial Bottle Free

to anyone sending me 10 cents to pay postage. Hydrozone is a harmless germicide, which will cure you.

Booklet on treatment of diseases sent free on request.

Sold by all druggists.  
Prof. Charles Marchand  
Dep't U, 63 Prince St., New York

## SEALS BOTTLES, PACKAGES, BOXES, PAPERS, CAR DOORS



Send for a sample of the great Twentieth Century

### SIGNATURE SEAL

THIS Seal has two parts—the Lock and Breakable Key. To seal any article, pass both ends of the wire through the eye of the block, turn key until it breaks off. Signatures may be written permanently with a pencil on one side of the block. Signatures may also be stamped or printed on the block. The stub of the key may be used to keep "tab" on the seals used, so that a count is easily kept by the sender. No tools necessary.

Write to-day for Literature.

D. K. HIETT, 185 Dearborn St., CHICAGO, ILL.

## BUCKMOBILE

The average American road is little adapted for the use of automobiles, but by reason of its peculiar buckboard construction all roads are alike to the "Buckmobile." It has every feature which should be incorporated in 1904 construction. Write for name of nearest agent or we will be pleased to sell you direct. Send to-day for catalogue.

BUCKMOBILE CO. UTICA, N. Y.  
New York Agents, 1900 Broadway, cor. 63d St.

## AMERICAN JUMP SPARK IGNITION OUTFITS

MARINE AUTOMOBILE STATIONARY MOTORCYCLE

SEE CATALOGUE W. AMERICAN COIL COMPANY, Somerville, Mass.

## Insured For Five Years

A paint policy is a good thing, and it's good policy to paint with

### PATTON'S SUN-PROOF PAINTS



because they are known to be absolutely sun and weather-proof. You put it on—we take the risk. Give you a real guarantee for five years. Been doing this a long time without losing a house. What is safe for us is wise for you. Our free Paint Book tells all about Patton's Sun-Proof Paint and throws in a lot of good paint advice. A postal brings a copy—quick.

PATTON PAINT COMPANY  
227 Lake St., Milwaukee, Wis.  
PITTSBURGH PLATE GLASS CO., General Distributors.



**Mosler "SPIT-FIRE" Spark Plug**

Guaranteed to "SPIT-FIRE" when others spark only.

Fit Any Engine, Any Thread.

**Mosler SPIT-FIRE**

1679 Broadway, N.Y.

Pat. April 22, 1902; September 15, 1903.


**FREE TRIAL**

**WITTE Gas and Engines**

are sold on 30 Days' Free Trial. Size 1 1/2 to 40 H.P. For all power purposes. Catalog E.

**WITTE IRON WORKS**

517 W. 5th St., Kansas City.



**From Any Point of View**

**THE Remington Typewriter**

**IS THE BEST INVESTMENT**

It leads in durability, reliability, permanent excellence of work, adaptability to all classes of work, ease, speed and convenience of operation, and economy in service.

**REMINGTON TYPEWRITER CO.**

327 Broadway, New York

**What Is Daus' Tip-Top?**

TO PROVE that Daus' "Tip-Top" is the best and simplest device for making 100 copies from pen-written and 50 copies from typewritten original, we will ship complete duplicator, cap size, without deposit, on ten (10) days' trial.

Price \$7.50 less trade discount of 33 1/3 per cent, or \$5 Net

The Felix F. Daus Duplicator Co., Daus Bldg., 111 John St., New York

**Save Your Fuel**

by freeing your boilers of scale with the **Dean Boiler Tube Cleaner**. It will save you hundreds of dollars every year. We send it for a free trial. Write to-day for our book, "Economy in the Boiler Room."

**WM. B. PIERCE CO.**

319 Washington Street, Buffalo, N. Y.

**A faint heart**

never passed the life insurance doctor. The time to get insured is now--when every organ is perfectly healthy. Our little booklet "The How and the Why" will tell you how easily you can be insured by mail.

**PENN MUTUAL LIFE INS. CO.**

PHILADELPHIA

**TYPEWRITERS ALL MAKES**

All the Standard machines SOLD or RENTED ANYWHERE at HALF MANUFACTURERS' PRICES. Shipped with privilege of examination. Send for Cat.

**Typewriter Emporium, 203 LaSalle St., Chicago**

**ON THE SURFACE**

**Warren's Natural Asphalt Sand Surfaced Roofing**

**LOOKS ALL RIGHT**

and it wears better than it looks. Does not require painting. Anyone can apply it. Comes ready to lay in rolls of 108 sq. ft.

**Warren Chemical & Mfg. Co., 18 Battery Pl., New York**

**"Perfection" AIR MATTRESS**

(Camp Mattress with Pillow attached. Also showing Mattress inflated.)

**THE IDEAL BED**

For Home, Camp, Yacht, Hospital

Non-Absorbent--Hygienic--Odorless. When deflated can be rolled into small package for storage or transportation. No CAMPING OUTFIT COMPLETE WITHOUT THEM. "Perfection" Air Cushions for Office, Easy, and Invalid Chairs, Yachts and Small Boats. Send for descriptive booklet "A" and price list.

**Mechanical Fabric Co., PROVIDENCE, R. I.**

|                                                                          |         |
|--------------------------------------------------------------------------|---------|
| Washing and bleaching, composition of matter for, T. Mellor .....        | 754,588 |
| Washing device, clothes, C. H. Gunn .....                                | 754,924 |
| Washing machine, vessel or receptacle, W. B. Page .....                  | 754,494 |
| Watch movement winding wheels, ornamentation of exposed, O. Ohlson ..... | 754,000 |
| Watch, stem winding, A. Anzelewitz .....                                 | 754,407 |
| Watch, stop, E. Philippe .....                                           | 754,793 |
| Water closet, H. O. Krakow .....                                         | 754,573 |
| Water closet, P. A. Allen .....                                          | 754,733 |
| Water closet ventilating device, W. J. Powers .....                      | 754,695 |
| Water heater, electrical, H. M. Hill .....                               | 754,451 |
| Water tube boiler, Bessingham & Embling .....                            | 754,415 |
| Watering machine, automatic stock, S. C. Clark .....                     | 754,848 |
| Weather strip, J. S. Senglar .....                                       | 754,819 |
| Weather strip, H. Eagon .....                                            | 754,857 |
| Windmill, C. H. Mikkelsen .....                                          | 754,477 |
| Window, O. E. Cluss .....                                                | 754,425 |
| Wires, combined guide and guard for overhead, C. M. Zellers .....        | 754,529 |
| Wolf trap, J. W. Sprague .....                                           | 754,511 |
| Wood and the product thereof, preparing, M. Lichtenberg .....            | 754,782 |
| Wrench. See Adjustable wrench.                                           |         |
| Wrench, L. Trudeau .....                                                 | 754,520 |
| Wrench, Ash & Stewart .....                                              | 754,633 |
| Wrench, J. A. Abolt .....                                                | 754,831 |
| Wrest plate, E. Hilger .....                                             | 754,869 |
| Wringers. See Mop wringer.                                               |         |
| Yarn skein delivering apparatus, W. Matheson .....                       | 754,584 |
| Yarn treating apparatus, H. Lindenberg .....                             | 754,784 |

**DESIGNS.**

|                                                                         |        |
|-------------------------------------------------------------------------|--------|
| Book cover, W. M. Rhoads .....                                          | 36,850 |
| Mantel, F. A. Broadbent .....                                           | 36,851 |
| Mug, L. W. Rice .....                                                   | 36,853 |
| Paper knife, L. W. Rice .....                                           | 36,854 |
| Pin head, hat, W. Turton .....                                          | 36,848 |
| Spoons, forks, or similar articles, handle for, J. E. Straker, Jr. .... | 36,852 |
| Tableware, metallic border for, A. Steffan .....                        | 36,849 |

**TRADE MARKS.**

|                                                                                                  |        |
|--------------------------------------------------------------------------------------------------|--------|
| Anesthetic for the painless extraction of teeth, local, H. L. Wheeler .....                      | 42,240 |
| Antiseptic emollient, Schaefer Chemical Co. ....                                                 | 42,249 |
| Beverage, certain named, W. H. Hutchinson & Son .....                                            | 42,233 |
| Books made of textile fabric, H. S. Dean .....                                                   | 42,227 |
| Carpet sweepers, National Sweeper Co. ....                                                       | 42,253 |
| Cotton piece goods, G. Willis & Co. ....                                                         | 42,250 |
| Disinfectant, C. Reinsch .....                                                                   | 42,251 |
| Fiber composition, certain named articles of, J. M. Grasser .....                                | 42,257 |
| Files and rasps, G. & H. Barnett Co. ....                                                        | 42,256 |
| Foods or condition powders, stock, West Coast Stock Food Co. ....                                | 42,238 |
| Furniture, certain named, Booklovers Library .....                                               | 42,255 |
| Insect powders and liquid vermin exterminators, C. E. Woodruff .....                             | 42,239 |
| Jellies and preserves, fruit, G. L. Harting .....                                                | 42,234 |
| Matches, friction, Ohio Match Co. ....                                                           | 42,232 |
| Medicine for cure of certain named diseases, Alpoli Company .....                                | 42,243 |
| Medicine for diseases of the internal organs, G. Phipps .....                                    | 42,245 |
| Medicines for cure of female complaints, Dr. Richards Dyspepsia Tablet Association .....         | 42,244 |
| Oil, cotton seed, Kentucky Refining Co. ....                                                     | 42,236 |
| Oysters in canned and bulk form, Toke Point Oyster Co. ....                                      | 42,235 |
| Pills, Lanman & Kemp .....                                                                       | 42,241 |
| Receptacles, certain named, Hartmann Trunk Co. ....                                              | 42,252 |
| Remedy for certain named diseases, R. W. Whitlatch .....                                         | 42,242 |
| Remedy for certain named diseases, cones used as, A. J. Shilling .....                           | 42,247 |
| Remedy, pile, C. Mayne .....                                                                     | 42,246 |
| Ropes, cords, twine fiber, twine, and binder twine, International Harvester Co. of America ..... | 42,258 |
| Salve, C. L. Buddenbohn .....                                                                    | 42,248 |
| Tables and appliances for playing certain named games, Knickerbocker Co. ....                    | 42,251 |
| Underwaists, children's, H. & W. Co. ....                                                        | 42,229 |

**LABELS**

|                                                                                             |        |
|---------------------------------------------------------------------------------------------|--------|
| "Cuti Balm," for a lotion, E. Reith .....                                                   | 10,825 |
| "Discount," for newspapers, periodicals, magazines, pamphlets, etc., S. B. Hutchinson ..... | 10,819 |
| "Flor de Astor," for cigars, Park & Tilford .....                                           | 10,830 |
| "Good Chairs," for chairs, Buckeye Chair Co. ....                                           | 10,839 |
| "Lochinvar Old Highland Scotch," for whisky, New York Importation Co. ....                  | 10,833 |
| "Mapo," for syrup, D. P. Ingham .....                                                       | 10,834 |
| "March's Hair Health," for hair and scalp cleanser, J. G. March .....                       | 10,823 |
| "Nu-Trex Flaked Wheat Food," for cereal food, American Fine Arts Co. ....                   | 10,837 |
| "Purity Brand Condensed Milk," for condensed milk, United States Condensed Milk Co. ....    | 10,836 |
| "Royal Iris," for cigars, American Lithographic Co. ....                                    | 10,829 |
| "Shamrock Flaxette," for handkerchiefs, Acheson Harden & Co. ....                           | 10,821 |
| "Smith's Tender Joint Shoe," for shoes, C. G. Smith .....                                   | 10,820 |
| "Smoker's Teeth Powder," for tooth powder, Weaver Conger Co. ....                           | 10,824 |
| "Tarbelle Whiskey," for whisky, P. McIntyre .....                                           | 10,832 |
| "The Lightning Fire Extinguisher," for fire extinguishers, Suffolk Chemical Co. ....        | 10,840 |
| "The Magic Curler," for hair curlers, J. B. Hall .....                                      | 10,822 |
| "The Merchant Prince," for cigars, A. J. Schmidt .....                                      | 10,827 |
| "Three Minute Plum Pudding," for a food preparation, A. T. Knapp .....                      | 10,838 |
| "Welsh's Embro," for a liniment, Scotch Embrocation Co. ....                                | 10,826 |
| "White Star," for gin, H. Gravier .....                                                     | 10,831 |
| "Wyoming Condensed Milk," for condensed milk, United States Condensed Milk Co. ....         | 10,835 |

**PRINTS.**

|                                                                                                           |     |
|-----------------------------------------------------------------------------------------------------------|-----|
| "All Nations Use the Singer," for sewing machines, Singer Manufacturing Co. ....                          | 931 |
| "Athlophoros," for a medicine, Athlophoros Co. ....                                                       | 927 |
| "Bromo-Seltzer," for bromo seltzer, Emerson Drug Co. ....                                                 | 926 |
| "C. D. & T," for electric cars, Cincinnati, Dayton & Toledo Traction Co. ....                             | 932 |
| "Foxy Grandpa's Multiplier," for a multiplier, F. J. Smith .....                                          | 922 |
| "Golden Rule Hair Restorative," for a hair restorative, Citizens Wholesale Supply Co. ....                | 929 |
| "Non-Aqua," for shoes, O. McCormick .....                                                                 | 924 |
| "Ozomulsion," for medicine, Ozomulsion Co. ....                                                           | 928 |
| "Pride of Reldsville," for smoking tobacco, R. Harris & Bro. ....                                         | 925 |
| "The Romander Comfort Passenger Car," for passenger cars, H. Romander .....                               | 933 |
| "The Victor Jewel Premium Machine," for talking machines and accessories, Victor Talking Machine Co. .... | 930 |

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

**PERFORATED METAL**

OF EVERY DESCRIPTION AND FOR ALL USES.

THE HARRINGTON & KING PERFORATING CO., 225 N. UNION ST. CHICAGO, ILL. U.S.A.

**SPECIAL LOW RATES VIA THE NICKEL PLATE ROAD**

to points in the West and Southwest. One way Colonist and round trip Homeseekers' tickets on sale first and third Tuesdays of each month to April inclusive. See local agents, or write R. E. Payne, General Agent, Buffalo, N. Y., or A. W. Ecclestone, D. P. A., 385 Broadway, New York.

**SPECIAL MANUFACTURING.**

**DIES AND STAMPINGS TO ORDER.**

SPECIAL MACHINERY--MODELS--EXPERIMENTAL WORK. DROP FORGING DIES AND DROP FORGINGS. HARDWARE SPECIALTIES ETC. MANFD. TO ORDER--SEND SAMPLES OR DRAWINGS FOR ESTIMATES. WRITE FOR OUR BOOKLET. THE GLOBE MACHINE & STAMPING CO. 970 HAMILTON ST., CLEVELAND, OHIO.

**WANTED--White Metal Articles to Cast.** Also all kinds of Plating and Press-work.

**NATIONAL SHEET METAL CO., Peru, Ill.**

**Export Trade**

**How to Secure and How to Hold It**

Valuable hints on how to secure Export Trade sent gratis on request. Address

**EXPORT EXPERT**

Box 773, New York

**ICE MACHINES.** Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 899 Clinton St., Milwaukee, Wis

**MODELS & EXPERIMENTAL WORK.** Inventions developed. Special Machinery. E. V. BAILLARD, Fox Bldg., Franklin Square, New York.

**SPECIAL MACHINERY** Tools and Dies. Model & Experimental Work. Costello Machine Works. 60 Centre St., New York

**Shavers, Stop Swearing!** DRESSING for razor strops, based on scientific experiment. Post-paid, 10 cents silver. Strop-O Co., Wash., D. C.

**FOR SALE--PATENTS** on our own inventions. Prices reasonable. Sutherland & Company, 110 S. Broadway, Los Angeles, California.

**CHEMICAL EXAMINATIONS OF ALL KINDS.**

DR. H. C. STIEFEL, Bissell Block, Pittsburgh, Pa.

**ELECTRICITY HOW TO MAKE.** A Dynamo, Storage Battery, Telegraph Instrument, Electric Bell, Motor. 5 Books, 10c. each. BUBIER PUBLISHING CO., Box S. LYNN, MASS.

**NAME PLATES--STEEL STAMPS**

"EMPLOYEE CHECKS, KEY TAGS & BADGES"

**J. ROBBINS MFG. CO. 58 KNEELAND ST.**

SEND FOR CATALOGUE....BOSTON, MASS.

Dies, Tools and Special Machines. Models and Experimental Work. General Machine Work. PR. J. BENDER & SONS, Inc., 87 Frankfort St., New York

**NOVELTIES & PATENTED ARTICLES**

Manufactured by Contract. Punching Dies, Special Machinery. E. Konigsow & Bro., 181 Seneca St., Cleveland, O.

**Magical Apparatus.**

Grand Book Catalogue Over 700 engravings, 25c. Parlor Tricks Catalogue, free.

**MARTINKA & CO., Mfrs., 433 Sixth Ave., New York.**

THE SCHWEDTLE STAMP CO. STEEL STAMPS, LETTERS & FIGURES. BRIDGEPORT, CONN.

**MASON'S Pat. Friction Pulleys and Clutches**

Starting Machinery without shock, and connecting line shafting. Most reliable and durable. Mason's New Pat. Whip-Hoist effective and simple.

Manfd. by VOLNEY W. MASON & CO., Inc. Providence, R. I., U. S. A.

**Experimental & Model Work**

City & advice free. Wm. Gardam & Son, 45-51 Rose St., N.Y.

**MODELS & GEARS**

CATALOGUES FREE. UNION MODEL WORKS 193 CLARK CHICAGO.

Patentable Combined Working Machine For Sale. For use of Cabinet Makers, Machinists, etc. Has capacity of 12 different apparatus. Foot power. All rights to buyer. Sold separately or together. C. Buddig, Eustis, Neb.

For Sale.--Blue Prints and Castings for Motorcycle Gasoline Engines. L. T. Barnes, 75 Truxton St., B'klyn

**OLDSMOBILE**

For business or pleasure, in rain or sunshine, the pioneer runabout has no equal. It represents the latest and best in automobile construction--the product of the largest automobile plant in the world. All roads alike to the Oldsmobile.

**Price, \$650.**

For full information see our nearest agent, or write direct. A captivating story "Golden Gate to Hell Gate" will be sent upon receipt of a two-cent stamp. Address Dept. 21,

**Olds Motor Works, Detroit, U. S. A.**

Touring Runabout Price \$750.

Light Tonneau Car Price \$950, without rear seat \$850.

Member of the Association of Licensed Automobile Manufacturers

**THE IDEAL SIGHT RESTORER**

**RESTORES THE SIGHT**

WEAK EYES MADE STRONG.

**SPECTACLES ARE A NUISANCE, NECESSITY ONLY MAKES ONE WEAR THEM.**

**PREVENTS FAILING SIGHT**

DULL EYES MADE BRIGHT.


Write for ILLUSTRATED TREATISE ON THE EYE, Mailed Free.

**THE IDEAL COMPANY, 239 BROADWAY, NEW YORK.**



THE WINTON MOTOR CARRIAGE CO., Cleveland, U.S.A.

## Orient Buckboard



Model of 1904. With TWO SPEED. Price \$425. Write for Catalogue.

WALTHAM MFG. CO., Waltham, Mass.

## HOROLOGICAL DEPARTMENT

BRADLEY POLYTECHNIC INSTITUTE

Formerly Parsons Horological Institute

PEORIA, ILLINOIS

LARGEST and BEST

WATCH SCHOOL in AMERICA


We teach Watch Work, Jewelry, En-

graving, Clock Work, Optics. Tuition

reasonable. Board and rooms near

school at moderate rates.

Send for Catalog of Information.



## CHARTER

GAS and GASOLINE

For All Work.

Stationaries, Portables, Hoisters, Pump-

ers, Sawing and Boat Outfits.

Send for Catalogue and Testimonials.

State Your Power Needs.


CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

## BRIDGE WHIST

The Boston Bridge Whist Score Book. Each book contains one hundred sheets, size 4 1/2 x 7 1/2. Also a complete set of Bridge rules. 25c. Postpaid on request. No charge for one hundred copies. Send for information.

R. W. EMERSON &amp; Co., 290 Devonshire St., Boston, Mass.

Scales. All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 400 useful articles, including Safes, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.



THE CARE OF ACETYLENE GAS IS discussed in SCIENTIFIC AMERICAN SUPPLEMENTS 1189, 1441, 1289. Price 10 cents. Mann &amp; Company, 361 Broadway, New York City, and all newsdealers.

## Photo Lenses


and Shutters of every kind for all purposes; Professional, Amateur, Process.

Sold Round the World on all Cameras. Catalogue free.

Bausch &amp; Lomb Opt. Co.

ROCHESTER, N. Y.

New York Chicago Boston



## BRISTOL'S RECORDING INSTRUMENTS.

Pressure Gauges, Vacuum Gauges, Voltmeters, Amperemeters, Wattmeters, and Thermometers, make continuous records Day and Night. Will pay for themselves. Every instrument fully guaranteed and sent on 30 days' trial. Send for Circulars and Specimen Chart.


The Bristol Company, Waterbury, Conn.

SILVER MEDAL PARIS EXPOSITION.

## CRUDE ASBESTOS

DIRECT FROM MINES

PREPARED ASBESTOS FIBRE for Manufacturers use R. H. MARTIN, OFFICE, ST. PAUL BUILDING 220 B'way, New York.



## WONDER of the AGE

Jackson's Patent High Head Centrifugal Pump. Guaranteed to raise water 1000 feet or more and maintain an efficiency of from 70% to 84%. First choice of the Engineer for City Water Works, Draining Mines, Hydraulics, Irrigating and Reclaiming Land. Beats the world for Durability, Economy and Efficiency. Catalogue No. 6.

BYRON JACKSON MACHINE WORKS, - - SAN FRANCISCO, CAL.

## WARNING!

The following Manufacturers and Importers are licensed under the pioneer patent on

## Gasolene Automobiles

Number 549,160, granted to George B. Selden, dated November 5th, 1895.

### MANUFACTURERS:

Electric Vehicle Co.  
Winton Motor Carriage Co.  
Packard Motor Car Co.  
Olds Motor Works  
Knox Automobile Co.  
The Haynes-Apperson Co.  
The Autocar Co.  
The George N. Pierce Co.  
Apperson Bros. Automobile Co.  
Locomobile Co. of AmericaThe Peerless Motor Car Co.  
Standard Motor Construction Co.  
Waltham Manufacturing Co.  
Pope Motor Car Co.  
J. Stevens Arms & Tool Co.  
H. H. Franklin Mfg. Co.  
Smith & Mabley, Inc.  
The Commercial Motor Co.  
Berg Automobile Co.  
Cadillac Automobile Co.Northern Manufacturing Co.  
Pope-Robinson Co.  
The Kirk Manufacturing Co.  
Elmore Manufacturing Co.  
E. R. Thomas Motor Co.  
Buffalo Gasolene Motor Co.  
The F. B. Stearns Co.  
Pope Manufacturing Co.  
Sandusky Automobile Co.  
Crest Manufacturing Co.

### IMPORTERS:

Smith & Mabley, Inc.  
Central Automobile Co.  
Alexander FischerHollander & Tangeman  
Standard Automobile Co.  
E. B. GaliaherAuto Import Co.  
F. A. LaRoche Co.  
Sidney B. Bowman Auto'bile Co.

Both the basic Selden patent and all other patents owned by members of this Association will be enforced against infringers. Manufacturers, Importers, Dealers and Agents, also Users of unlicensed machines are liable.

ASSOCIATION OF LICENSED AUTOMOBILE MANUFACTURERS  
No. 7 EAST 42d STREET, NEW YORK

## CHEMICAL CAMPHOR

1. Five times as powerful as camphor for the destruction of insects and vermin.

2. Costs only one-seventh as much as camphor per pound or one-thirty-fifth as much considering the smaller quantity used.

3. Absolute protection against moths.
4. Quickly drives away and destroys mice.
5. Protects against mildew and infection.
6. Leaves no disagreeable after-odor.
7. Will not injure the finest fabric.
8. Is in flake-form and so more economical to use.

TWO POUNDS 30 CENTS


If your Druggist does not have it send to

## METCALF'S

39 Tremont Street  
& Copley Square  
BOSTON, MASS.

15 to 21 Clinton Street.

## THE GRIFFIN MILL



is sold more largely to Portland Cement Works than any other make. Here's the proof conclusive: 579 Mills sold in the past two years to following works:

Lehigh Portland Cement Co., Ormsd, Pa.  
Lehigh Portland Cement Co., Mitchell, Ind.  
Lehigh Portland Cement Co., Wellston, Ohio.  
Central Cement Co., Copley, Pa.  
Glens Falls Portland Cement Co., Glens Falls, N. Y.  
Cuyaga Lake Cement Co., Ithaca, N. Y.  
National Portland Cement Co., Durham, Ont.  
Sandusky Portland Cement Co., Syracuse, Ind.  
Newways Portland Cement Co., Newways, Mich.  
Great Northern Portland Cement Co., Baldwin, Mich.  
Midland Portland Cement Co., Bedford, Ind.  
Bonneville Portland Cement Co., Siegfried, Pa.  
Iroquois Portland Cement Co., Caledonia, N. Y.  
Alpha Portland Cement Co., Alpha, N. J.  
Whitehall Portland Cement Co., Cementon, Pa.

Struthers Furnace Co., Struthers, Ohio.  
Texas Portland Cement & Lime Co., Dallas, Texas.  
Iola Portland Cement Co., Iola, Kan.  
Walsh Portland Cement Co., Stroh, Ind.  
Kansas Portland Cement Co., Iola, Kansas.  
Alma Cement Co., Wellston, Ohio.  
Aetna Portland Cement Co., Fenton, Mich.  
Penn-Allen Portland Cement Co., Allentown, Pa.  
Martins Creek Portland Cement Co., Martins Creek, N. J.  
Wolverine Portland Cement Co., Coldwater, Mich.  
Bronson Portland Cement Co., Bronson, Mich.  
Quaker Portland Cement Co., Sandts Eddy, Pa.  
Diamond Cement & Lithograph Stone Co., Chicago, Ill.  
Mississippi Valley Portland Cement Co., Louisiana, Mo.  
Belleville Portland Cement Co., Belleville, Ont.  
Toledo Portland Cement Co., Manchester, Mich.

It is the way the "Griffin Mill" works that does it. Best work, least time, smallest expense. Illustrated catalogue free, if you ask for it.

BRADLEY PULVERIZER CO., 92 State Street, Boston, Mass.

## Big and Little—Heavy and Light

## The HARTFORD SINGLE TUBE and DUNLOP DOUBLE TUBE Tires

Stand foremost for Uniform Quality, Honest Construction and Durability. That each is the most serviceable tire of its class is universally acknowledged by those buyers who desire The Best regardless of cost, and thus consider the question of their needs intelligently. Let us advise you regarding the proper size and weight of tire best adapted to your requirements. Branches in principal cities.


## The HARTFORD RUBBER WORKS COMPANY

HARTFORD CONN

(Users of SOLID RUBBER TIRES may rest assured that our reputation as makers of only high-class goods will be carefully sustained in connection with this product)




## 5,000 sq. ft. of BLUE PRINTS in 24 Hours



THE FRANKLIN AUTOMATIC CONTINUOUS FEED ELECTRIC BLUE PRINT MACHINE prints continuously by Electric Light, day or night. Handles tracings of any length, size or kind. The tension is automatic and does not depend on skill of operator. Used by largest railroads and United States Government. Patented in United States, Canada and Europe. Made in two sizes, for 36 and 42-inch tracings. Send for descriptive circular.

WILLIAMS, BROWN &amp; EARLE, Dept. L, 918 Chestnut St., Philadelphia.

## NEW ENGLAND WATCHES



AMERICUS

Screw Case  
Water Tight  
and Dust ProofThe New England Watch Co.  
NEW YORK OFFICE: 37 & 39 Maiden Lane LONDON OFFICE: 7 Snow HillJESSOP STEEL CO  
MFRS OF CRUCIBLE SHEET STEEL  
WASHINGTON, PA.

## PRESIDENT SUSPENDERS

Comfort and service. Guaranteed—"All breaks made good." 50c and \$1.00. Any shop or by mail. C. A. EDGARTON MFG. CO., Box 310, Shirley, Mass.